

Bryce Canyon

Historic Resource Study



Bryce Canyon Lodge

HISTORIC RESOURCE STUDY

Bryce Canyon National Park

by
Nicholas Scrattish

September 1985

United States Department of the Interior
National Park Service
Rocky Mountain Regional Office
Branch of Historic Preservation

TABLE OF CONTENTS

brca/hrs/hrs.htm
Last Updated: 25-Aug-2004

Bryce Canyon

Historic Resource Study



TABLE OF CONTENTS

[COVER](#)

[ILLUSTRATIONS](#)

[MAPS](#)

[EPIGRAM](#)

[ACKNOWLEDGEMENTS](#)

[PREHISTORY](#)

INTRODUCTION
GEOLOGY AND GEOGRAPHY--A SKETCH
FLORA AND FAUNA
ABORIGINAL OCCUPATION
 Paiute Place Names

[MODERN DISCOVERY](#)

EXPEDITIONS TO THE THE BRYCE CANYON REGION
MORMON SETTLEMENT NEAR BRYCE CANYON
 Attitude Toward Natural Phenomena
POPULARIZATION
 Zion and the North Rim
 Forest Service
 Private Party—the Syretts

[REGIONAL DEVELOPMENT](#)

CONCEPT—ORIGINS
 Denver and Rio Grande Western Railroad
UNION PACIFIC SYSTEM
 Lund-Cedar City Spur
 Cedar City Complex
 Incorporation of Utah Parks Company
 Section 36, Bryce Canyon
 Syrett Camp
 Water Supply for Section 36
 Reconnaissance for Bryce Canyon Lodge
 Construction Program's Organization
 Materials for Bryce Lodge
 Transportation Franchise
REGIONAL ROAD DEVELOPMENT (1923-25)

Zion-Mt. Carmel Road (1927-30)

[NATIONAL MONUMENT STATUS](#)

LEGISLATION (1919-24)

FOREST SERVICE ADMINISTRATION (1923-28)

EARLY ACTIVITIES OF THE UTAH PARKS COMPANY AT BRYCE
CANYON (1924-29)

Absence of Contractual Agreements

Initial Construction Phase at Bryce Canyon

[NATIONAL PARK STATUS](#)

CREATION OF BRYCE CANYON

LAND ACQUISITION

Boundaries — Marian Frost Settlement

Abbreviated Grazing History

PARK ESTABLISHMENT (1929-56)

Joint Administration with Zion

Separate Administration for Bryce Canyon

OPERATIONS OF THE CONCESSIONER

Contracts

The Middle Years

The Road to Liquidation

PHYSICAL DEVELOPMENT

Park Roads — Rim Road

Park Roads — By-Pass Road

Rapid Construction Phase

The Civilian Conservation Corps in Bryce Canyon

Establishment, Administration, and Contribution of NP-3

Trails

Liquidation of Camp NP-3

Recent Construction Phase — Isolated Construction

Recent Construction Phase — MISSION 66 Construction

[APPENDIX A](#)

[ENDNOTES](#)

[BIBLIOGRAPHY](#)

LIST OF ILLUSTRATIONS

[Illustration No. 1](#) - Ebenezer Bryce and his wife

[Illustration No. 2](#) - Ebenezer Bryce cabin beside the Paria River, near Tropic, Utah

[Illustration No. 3](#) - Tourists' Rest, c. 1920-23

[Illustration No. 4](#) - Site of Former Denver & Rio Grande Depot

[Illustration No. 5](#) - Lund, Utah

[Illustration No. 6](#) - Lund, Utah, 1/4 mile

[Illustration No. 7](#) - Union Pacific Depot

[Illustration No. 8](#) - Chauffer Lodge

[Illustration No. 9](#) - Commissary Building (Union Pacific)

[Illustration No. 10](#) - El Escalante Hotel in Cedar City, Utah

[Illustration No. 11](#) - Bryce Canyon Lodge, 1924

[Illustration No. 12](#) - Concrete walks connecting Standard Cabins to Bryce Canyon Lodge

[Illustration No. 13](#) - Interior of a Standard Cabin, Bryce Canyon or Zion

[Illustration No. 14](#) - Construction of Deluxe Cabin No. 3 at North Rim. October 30, 1927

[Illustration No. 15](#) - Construction of Deluxe Cabin No. 3 at North Rim. November 13, 1927

[Illustration No. 16](#) - Construction of Deluxe Cabins North Rim. November 19, 1927

[Illustration No. 17](#) - Deluxe Cabins at Bryce Canyon

[Illustration No. 18](#) - Interior of a Deluxe Cabin, Bryce Canyon or North Rim

[Illustration No. 19](#) - Utah Parks Company Shelter at Bryce Canyon Point, July 1945

[Illustration No. 20](#) - Maurice Cope supervising trail repairs

[Illustration No. 21](#) - Par view of custodian's residence under construction

[Illustration No. 22](#) - Near view of the custodian's residence under construction

[Illustration No. 23](#) - Custodian's residence, showing detail of rock corner

[Illustration No. 24](#) - Bryce Canyon's comfort station No. 1 under construction, summer of 1929

[Illustration No. 25](#) - Comfort station No. 1 after completion

[Illustration No. 26](#) - Comfort station No. 2 under construction, late summer of 1929

[Illustration No. 27](#) - Comfort station No. 2 after completion

[Illustration No. 28](#) - Checking kiosk, completed on August 28, 1928

[Illustration No. 29](#) - Checking kiosk, near view

[Illustration No. 30](#) - UPC cafeteria building completed in 1932

[Illustration No. 31](#) - UPC cafeteria building subsequent to 1937 remodeling

[Illustration No. 32](#) - Bryce Canyon employees cabins (2) WPA project F.P. 8

[Illustration No. 33](#) - Bryce Canyon comfort station - WPA project F.P. 11

[Illustration No. 34](#) - Bryce Canyon museum-overlook at Rainbow Point

[Illustration No. 35](#) - Bryce Canyon's CCC Camp, NP-3

[Illustration No. 36](#) - CCC crew hauling logs in Bryce Canyon

[Illustration No. 37](#) - CCC enrollees loading logs along rim road

[Illustration No. 38](#) - Standard Oil Service Station

[Illustration No. 39](#) - Placement of exterior walls for residence No. 134

[Illustration No. 40](#) - Residence No. 129 after installation of interior and exterior walls

[Illustration No. 41](#) - Installation of forms for foundation walls on equipment storage buildings

[Illustration No. 42](#) - installation of canopy on extension to utility building

[Illustration No. 43](#) - Campfire circle at North Campground prior to modernization

[Illustration No. 44](#) - Modernization under construction at North Campground

[Illustration No. 45](#) - Completion photograph of modernization campfire lecture facility at North Campground

[Illustration No. 46](#) - Staging for campfire circle under construction at Sunset Campground

[Illustration No. 47](#) - Completion photograph of campfire lecture facility at Sunset Campground

LIST OF MAPS

[Map No. 1](#) - Regional Road System, c. 1922

[Map No. 2](#) - Bryce Canyon National. Monument, June 8, 1923

[Map No. 3](#) - Bryce Canyon National Monument, October 1, 1927

Please note: This report is a NPS publication, which is normally considered to be in the public domain. However, this report may contain illustrations that are copies of materials NOT in the public domain, for which one-time reprint permission was obtained prior to publication. Persons wishing to use these illustrations of non-NPS origin for any purpose beyond educational perusal must obtain their own permissions from the owners of the original materials.

<<< [Previous](#)

<<< [Contents](#) >>>

[Next](#) >>>

Bryce Canyon

Historic Resource Study



EPIGRAM

Nicholas "Nick" Scrattish's professional career began as a newly-minted PH.D. teaching in a California college. It ended too early as a promisingly productive research historian with the National Park Service. Nick brought to his work a finely-honed intellectual curiosity, a commitment to competence, and a resourcefulness that informed every manuscript that he authored. He also brought to those with whom he worked an engaging personality, an appreciation of the absurd, and an impatience with humbug that made him a stimulating laborer in the historical vineyard. This resource study is representative of the quality work that he produced from his doctoral dissertation to the report that he completed within hours of his tragic death. The "hot-eyed Croat" was an excellent scholar, a valued colleague, and a credit to this profession and the service.

John Luzader
Denver, Colorado
September 1985

[<<< Previous](#)

[<<< Contents >>>](#)

[Next >>>](#)

brca/hrs/hrs0a.htm
Last Updated: 25-Aug-2004

Bryce Canyon

Historic Resource Study



ACKNOWLEDGEMENTS

The author wishes to express gratitude for help given by numerous individuals. Former Superintendent Tom Hobbs and his staff could not have been more cooperative. Viola B. Rose, the Superintendent's Secretary, took the time to collect and mail a number of important park documents used in the study. John Luzader of the Professional Support Group, Denver Service Center and since retired, rendered trenchant advice. Barry Combs, Director of Public Relations, Union Pacific Railroad, put corporate research materials at my disposal and allowed the use of a printer-reader. John Witherbee, Union Pacific's Research Specialist, forwarded additional materials. The National Park Service was not asked to pay a cent for these invaluable service.

I also wish to thank Bob Svenningsen of the Denver Federal Records Center; Richard Crawford of the National Archives; Don Snoddy, Nebraska State Historical Society Archivist; Irvin C. McClay of the Utah State Archives; Jay Hammond, Coordinator of Collections at the Utah State Historical Society; and Victor Jackson, Zion Naturalist. Mrs. Maurice Cope, a delightful person, graciously permitted an interview and opened the family's Bryce collection to my inspection. Mrs. Agatha May made available the use of her family collection. I am appreciative to others who allowed interviews. Notwithstanding the assistance given by those above, any errors of fact and judgment that have found their way into this study are my own. Since Nickolas Scrattish's death, the manuscript has been finely edited and typed by Mrs. Joyce Moe. Mrs. Susan Tenney provided additional manuscript editing, and a final copy was typed by Mrs. Monta-Glea Trebilcock.

[<<< Previous](#)

[<<< Contents >>>](#)

[Next >>>](#)

Bryce Canyon

Historic Resource Study



PREHISTORY

INTRODUCTION

Small by National Park standards, the 56.2 square miles of Bryce Canyon National Park (BRCA) occupy the eastern edge of the Paunsaugunt Plateau in south-central Utah. The park is not a canyon. Rather, it is a spectacular series of 14 huge amphitheaters, each of which is carved at least 1,000 feet into the chromatic limestone of the Paunsaugunt Plateau. Thus, the geological features of Bryce Canyon represent the park's principal distinction. In fact, Bryce properly presents one of the world's best sites for an appreciation of the inexorable, titanic forces which have shaped the globe's surface. Each of the park's amphitheaters is crowded with protean rock sculptures. Domes, pinnacles, windows, natural bridges, arches, and temples accent an ethereal landscape. The color of these rock formations, augmented by a rising or setting sun, is delicate and often extraordinarily beautiful. Reds, yellows, and whites are predominant, and at least 60 tints of these basic colors have been recognized. In southern Utah this rock is referred to as the Wasatch Formation or Pink Cliffs.

GEOLOGY AND GEOGRAPHY A SKETCH

Due to its outstanding geomorphic qualities, this area of the State has been studied intensively by geologists for more than a century. In the aggregate their research has conclusively demonstrated the reasons for the resultant fairyland of Bryce Canyon. About 60,000,000 years ago, during the Eocene Epoch of the Tertiary Period, most of southern Utah was covered by water. Inland seas and lakes deposited silt, sand, and lime in beds as deep as 2,000 feet thick. Minerals cemented rock particles together. The weight of overlying deposits and incomprehensible lengths of time completed the transition from sediment to sedimentary rock. Subsequently, about 13,000,000 years ago, near the beginning of the Pliocene Period, diastrophic pressure from within the earth caused the entire area to rise slowly. Beds of rock formerly located at sea level were pushed to heights of several thousand feet or more. These beds cracked along fault lines and separated into the seven major tables located in southwestern Utah. Two of these plateaus, exclusive of the Paunsaugunt Plateau, are located within a few miles of the park. The Aquarius Plateau lies to the east. To the west, the Markagunt Plateau is visible across the Sevier Fault.

Because of this homologous regional development, the geological story of Bryce Canyon is inseparable from that of other scenic attractions in southwestern Utah and northwestern Arizona. The sedimentary foundations of Bryce Canyon and Cedar Breaks National Monument, 65 miles to the northeast, rest on what would be the summit of Zion National Park. Zion, in turn, has its foundation on what would be the rim of the Grand Canyon. It is well known that the Grand Canyon clearly reveals the story of ancient geological time (Paleozoic). Some of its exposed rock in the Inner Gorge dates back approximately 1,750,000,000 years. Zion, Bryce Canyon, and Cedar Breaks dramatically complement this record. The former displays the events of medieval geological time (Mesozoic). Bryce Canyon and Cedar Breaks present a graphic record of modern geology (Cenozoic).

The Paunsaugunt Plateau has had its sides exposed to the elements. Full of fractures, these sides are extremely vulnerable to the forces of erosion—particularly weathering. Both physical weathering (disintegration) and chemical weathering (decomposition) are prominent in widening Bryce Canyon's amphitheaters. Disintegrative agents, such as frost action, principally weakens rocks that were fractured in the faulting process. Organic elements, too, such as the pressure from plant roots and burrowing animals, serve to loosen rock material.

Streams and their myriad tributaries, which form from rain and melting snow, do drain off the Paunsaugunt Plateau but flow opposite the amphitheaters. Rather, it is the rain and snow that fall directly into the amphitheaters—and intermittent streams formed from these sources—that are responsible for down-cutting. [1] The park's deepest and most precipitous amphitheaters are carved by the most active intermittent streams at work for the longest time. Naturally, periodic floods greatly accelerate this process. Amphitheater walls on the eastern edge of the Paunsaugunt Plateau have been receding in a northwesterly direction at the approximate rate of 1 foot per 50 years. It has probably taken over a million years for the plateau rim to erode back from the original fault escarpment, some 2-1/2 miles to its present location. [2]

Protean rock formations in Bryce Canyon are basically determined by the hardness of the rocks themselves. Since rock strata exhibit different degrees of hardness, they erode at different rates. More resilient limestones tend to form shelves and ledges. When eroded, softer shales and sands leave grooves, recesses, and small caves.

The brilliant coloration of rock formations in Bryce Canyon results from the presence of specific minerals originally present in the sedimentary rock. Once exposed these minerals oxidize. Hydrous iron oxide compounds, such as hematite and limonite, produce gradations of red and yellow respectively. Purplish or lavender rock likely contain manganese oxides. White sections of rock—and to a lesser extent, cream—have had most of the mineral content leached out of them. In places within the park's amphitheaters, the whiter limestones and siltstones of the Wasatch Formation are coated with a thin layer of reddish sediment. This phenomenon results from a once higher mineral deposit left by rain or snow-melt. Evaporation often leaves the colorful residue plastered to a much lighter surface.

FLORA AND FAUNA

As a result of elevation and precipitation, the plants of Bryce Canyon grow in three distinct but overlapping zones. At an altitude of 6,600 to 7,000 feet the Upper Sonoran Zone furnishes a habitable environment for sagebrush, the pinyon pine, and Utah juniper. These areas within the zone are often collectively referred to as the "pygmy forest." A Transition Zone from 7,000 to 8,500 feet displays a profusion of yellow pine, which constitutes approximately half of the park's trees. Above 8,500 feet, the Canadian Zone sports white pine and ancient bristlecone pine, white fir, blue spruce, and aspen clustered in groves or standing alone.

Mammals most frequently seen within the park include mule deer, porcupines, skunks, yellow bellied marmots, ground squirrels, pine squirrels, gray fox, picket gophers, a variety of mice, and the ubiquitous chipmunk. Red-tailed hawks, woodpeckers, owls, and ravens well represent larger members of the bird family. The park's smaller birds include flycatchers, swallows, jays, chickadees, wrens, thrushes, and a variety of sparrows. Only a few species of reptiles are able to exist in the high, cold forest of the Paunsaugunt region. These include the horned lizard, desert whiptail lizard, and three snakes—the gopher snake, garter snake, and Great Basin rattlesnake.

ABORIGINAL OCCUPATION

Scant information is available regarding the archeological resources of Bryce Canyon or its immediate environs. [3] There is, consequently, little to imply that the aboriginal inhabitants of Utah or adjoining states found the Bryce Canyon area an attractive place for large-scale settlement. Some fragmentary artifacts have been located in the canyons tributary to the Paria River south of the park. These are thought to identify the Basket Makers as the earliest known inhabitants of the region. Shortly after A.D. 1000, the Puebloans may have followed the Basket Makers into the region, occupying some sites along tributaries of the Paria and Sevier River. [4] If these were indeed Puebloans perhaps their archeological remains—best preserved in rock carvings and paintings on canyon walls—represent the outposts of the main Pueblo settlements in Arizona and New Mexico. A more recent theory holds that it was really Indians of the Desert Culture who migrated into the area and emulated a higher Puebloan civilization to the south and east. [5] Whether Puebloan or Desert Culture, post-Basket Maker activity in the Paunsaugunt region faded rapidly after A.D. 1200.

Thereafter, the Paiutes—a primitive, peaceful, seminomadic people—gradually filtered into the area. Paiute arrowheads and chipped obsidian tools have been found in relative abundance, implying that the region was used by them for hunting and gathering activities, but little else. At about the same time it is thought that Navajos from south of the Colorado River made periodic incursions into the Bryce Canyon region in search of animal pelts and readily available booty. [6] No native Americans of any kind now live in Garfield County, which is where Bryce Canyon is located, nor in adjoining Kane and Wayne Counties.

Paiute Place Names

Paiute legends and place names illustrate how these aborigines viewed Bryce Canyon. In 1936 "the legend of Bryce Canyon" was explained to the Zion-Bryce Park Naturalist by Indian Dick, an elderly Paiute who then lived on the Kaibab Reservation:

Before there were any Indians, the Legend People, To-when-an-ung-wa, lived in that place. There were many of them. They were of many kinds—birds, animals, lizards, and such things—but they looked like people. They were not people; they had power to make themselves look that way. For some reason the Legend People in that place were bad; they did something that was not good, perhaps a fight, perhaps some stole something the tale is not clear at this point. Because they were bad, Coyote turned them all into rocks. You can see them in that place now, all turned into rocks; some standing in rows, some sitting down, some holding onto others. You can see their faces, with paint on them just as they were before they became rocks. The name of that place is Angka-ku-wass-a-wits. This is the story the people tell.

Indian Johnnie, Dick's nephew, translated "Angka-ku-wass-a-wits" as "red painted faces." The Paiute name "Unka-timpe-wa-wince-pock-ich" has often been cited as the Paiute name for Bryce Canyon, supposedly meaning "red rocks standing like men in a bowl-shaped recess." [8] When asked by the Naturalist about this name, Indian Dick replied that the Paiutes never referred to Bryce Canyon that way. [9] The Paiute, Toney Tillohash, has explained that the phrase could be used as a descriptive term, but would literally mean "red-rocks-many-standing-holes." [10]

brca/hrs/hrs1.htm

Last Updated: 25-Aug-2004

Bryce Canyon

Historic Resource Study



MODERN DISCOVERY

EXPEDITIONS TO THE BRYCE CANYON REGION

On October 20-21, 1776, a Spanish entrada under the direction of the Franciscan Friars, Silvestra Vélez de Escalante and Francisco Atanasio Dominguez, crossed the northwestern Arizona plateau area—somewhat southwest of Bryce Canyon. The "Santa Gertrudis" camp, on the night of October 20, was one of the western branches of Kanab Creek, about 10 miles southwest of Pipe Springs. A night later the "Santa Barbara" camp was made in Kimball Valley near Johnson Creek, 8 miles southeast of Fredonia. At the time the friars' immediate aim was to search for a westward river crossing. Their long range goal was to establish a connecting route between the missions of New Mexico and California. Given the entrada's path, it is probable that the Pink Cliffs were visible on the far skyline to the northeast. [[11](#)]

In 1826 Jedediah Smith rediscovered the Sevier and Virgin, the westernmost rivers in Utah's high plateau country. Smith was the first American to travel overland to Spanish California. Four years later another American frontiersman named George Yount passed northwest of the park through the present sites of Circleville, Panguitch, and Cedar City. He, too, was enroute to California. In 1844, after a reconnaissance of the Great Basin, Captain John C. Fremont followed the old Spanish trail northward, past the present sites of Cedar City, Parowan, and Circleville. Fremont retraced his steps 9 years later enroute to California. Mormon scouts, sent out by the church to ascertain the location of favorable agricultural and grazing lands in southern Utah, first visited the Sevier River near Panguitch in 1852. This party probably had a good view of the Sunset Cliffs on the west edge of the Paunsaugunt Plateau. [[12](#)]

A party of Indian fighters, under the command of Captain James Andrus, was sent out from St. George in 1866 to pursue maulauding Navajo. These men traversed the upper Paria Valley and were probably the first white men to view the eastern escarpment of the Paunsaugunt Plateau. The southern end of the Plateau was first visited in 1879 by Major J. W. Powell, a geographer working for the U.S. Geological Survey. On this trip his efforts appear to have been restricted to the area above Alton and the Kanab Creek drainage. Scarcely a year later Alvin Thompson and F. S. Dellenbaugh, subordinates under Powell's direction, traversed the bases of the Paunsaugunt and Aquarius Plateaus. They most likely followed a route previously established by the noted Mormon missionary, Jacob Hamblin. Later, Thompson and Dellenbaugh climbed into what is now Bryce Canyon from the south, near Rainbow Point.

This tentative probe into the future park set the stage for a quick succession of visits by Edwin E. Howell, Grove Karl Gilbert, and Lieutenant W. L. Marshall—all members of the mid-1870s Wheeler survey. Howell intensively studied the exposure of the Wasatch Formation at Table Cliffs. Gilbert's surveys centered on the Paunsaugunt Plateau and Paria Valley. An excerpt from his 1872 notebook follows:

Up the Sevier (East Fork) a few miles and then to the left a few miles more until we came suddenly on the grandest of views. We stand on a cliff 1,000 feet high,

the "Summit of the Rim." Just before starting down the slope we caught a glimpse of a perfect wilderness of red pinnacles, the stunningest thing out of a picture. [13]

The Wheeler survey was accompanied by an artist, John E. Weyss, whose pencil drawing of erosional remnants is the first known illustration of what is now Bryce Canyon. [14]

During the clement months of 1875-77, Captain Clarence E. Dutton and his colleagues gathered material for two definitive studies of the high plateau region, published in 1880 and 1882. The later study is titled Tertiary History of the Grand Canon District with Atlas and includes a plate captioned "The Pink Cliffs (Eocene) upon the southern end of the Paunsaugunt Plateau." This "heliotype" plate was drawn from a photograph by W. H. Holmes, and appears to show a section of the rim above Willis Creek. [15]

On November 18, 1876, one of the most poetic descriptions of Bryce Canyon was written by T. C. Bailey, U. S. Deputy Surveyor, during a few moments of feverish inspiration. At the time Bailey was surveying a Guide Meridian and came onto what is now known as Sunset Point:

Immediately east and south of the last corner set, the surface breaks off almost perpendicularly to a depth of several hundred feet—seems indeed as though the bottom had dropped out and left rocks standing in all shapes and forms as lone sentinels over the grotesque and picturesque scenes. There are thousands of red, white, purple, and vermilion colored rocks, of all sizes, resembling sentinels on the walls of castles, monks and priests in their robes, attendants, cathedrals and congregations. There are deep caverns and rooms resembling ruins of prisons, castles, churches with their guarded walls, battlements, spires, and steeples, niches and recesses, presenting the wildest and most wonderful scene that the eye of man ever beheld, in fact, it is one of the wonders of the world. [16]

MORMON SETTLEMENT NEAR BRYCE CANYON

Neither Mormon reconnaissance during the 1850s nor the Federal surveys of the mid-1870s served to direct much public attention to the Bryce Canyon region. The Mormons did begin settlement near the eastern edge of the park in 1874, but this did nothing to directly popularize Bryce Canyon's uniqueness. [17] To some extent Bryce Canyon's obscurity, until the second decade of the 20th Century, can be attributed to its distance from railways and sizeable towns. Rough wagon roads to the general vicinity of the Paunsaugunt rim existed but required a slow travel, either through rocky Sevier Canyon or Red Canyon, and then on to the spongy top of the Paunsaugunt Plateau. For several months of the year heavy snow drifts impeded any kind of approach at all.

On December 24, 1874, the David O. Littlefield and Orley D. Bliss [18] families laid out farms in the upper Paria Valley, near the junction of the Paria River and Henrieville Creek. These hardy souls were joined by eight additional families the following year. The settlement's proximity to the Pink Cliffs prompted the name Clifton (Cliff town). Ebenezer Bryce and his family, who came to Clifton in 1875 or 1876, became disenchanted with the settlement and moved upstream to Henderson Valley (New Clifton). Between 1878-80, with the aid of Daniel Coulding and others, Ebenezer Bryce began and completed an irrigation ditch 7 miles long from Paria Creek, to make possible the raising of crops and stock. Bryce was also instrumental in building a road to make nearby timber and firewood more accessible. Local people began to use the road and customarily called the amphitheater, in which the road terminated, "Bryce's Canyon." Ebenezer Bryce had originally moved into the

upper Paria Valley because of his wife's fragile health. [19] Apparently, the climate was not kind enough. In 1880 the Bryce family left New Clifton for Arizona.

Clifton was abandoned in 1877. The majority of its settlers relocated to a site about a mile upstream, which they named Cannonville. Three families from Clifton established themselves on the present site of Henrieville, approximately 5 miles east of Cannonville. Three miles southwest of Cannonville a few families established a settlement on Yellow Creek which they called Georgetown—later transformed into a single ranch. Of all these settlements, Cannonville became the most successful and remained so until the late 1880s.

In 1889 a shortage of water for irrigation and the consequent limitation of arable land in the upper Paria Valley gave rise to a scheme for diverting water from the East Fork of the Sevier River, a 14 miles distance on the Paunsaugunt Plateau, over the east rim of the Plateau and 1500 feet down into the Valley. The proposed ditch may have originally been envisioned by Ebenezer Bryce, shortly before his departure for Arizona. Locally financed by the Cannonville and East Fork Irrigation Company work was begun on May 15, 1890. Confidence in the project was shown by James Ahlstrom and C. W. Snyder, who started to build houses on land which the ditch would supply water to. During the summer of 1891, local confidence increased and a town site was laid out, named Tropic to reflect the locale's summer climate. The Tropic Canal was completed on May 23, 1891. This not only insured the village of Tropic's future, but made it the most important settlement east of the future park. [20]

Attitude Toward Natural Phenomena

No, sir; I never have paid much attention to it; he frankly confessed. It is pretty common to us folks.

I was born right over behind that cliff in the fields of the town of Tropic—you can see them from here, only three or four miles away. I have trailed stock through here every summer since I could ride a horse, but I have never been off the trail this far in my life until I saw you fellows just now.

Yes, it is kind of interesting; rough country for critters off the trail, though, down in there; they used to call it Bryce's Canyon when "Bill" Bryce ran stock up here, before the government took the pasture over. Mother was born a little further down on the Paria, but she never was here until last summer. [21]

Twentieth-century chroniclers of Bryce Canyon have often expressed mild disapproval that Mormon settlers in the vicinity were so little impressed with the natural grandeur only a stone's throw from their back yards. [22] In fairness to these people, it is, perhaps, more just to empathize with the spirit of a different time—to perceive the situation as they perceived it. Mormon pioneers in the Bryce Canyon region were an assiduous, God-fearing group, whose struggle against the harsh realities of everyday life left little psychic energy for an appreciation of magnificent scenery. [23] The descendants of these hardy pioneers best express what was probably the real relationship between the people and their environment:

Our grandparents were thrilled with its (i.e. Bryce Canyon's) beauty and often referred to it as beautiful "Potato Valley Mountains." Many of us remember them telling us about this canyon as well as of Cedar Breaks. But they could do little about it. They were too busy trying to make a livelihood for their families. There were no roads, just poor trails, their wagons and wagon wheels were worn out, their horses or ox teams were poor and unable to make any trips, save for the bare necessities. [24]

POPULARIZATION

Zion and the North Rim

After lying dormant for 40 years, it is difficult to imagine how Bryce Canyon could have attracted so much attention—beginning in the late teens—had it not been for the proximity of other scenic locations in the area, particularly Zion and the North Rim of the Grand Canyon. It is worth stating as a principle of economic development for southern Utah that all scenic attractions could be tied into a tourist "loop." This had much to do with Bryce Canyon's subsequent popularization. Secondly, a sprinkling of Mormon settlements east and northwest of Bryce Canyon brought with them an uneven but tangible improvement in the area's roads. Inadvertent explorers of lesser known byways, such as salesmen, were destined to drive some of the first automobiles into Tropic and Cannonville. Their accounts of the area encouraged visits by others. [25]

Forest Service

I shall always feel that the part I played in introducing Bryce Canyon to the world is the greatest accomplishment of my life.

J. H. Humphrey [26]

Nevertheless, it is not to these anonymous businessmen that the origins of popularization of Bryce Canyon can be traced, but rather to Forest Service Supervisor named J. W. Humphrey. [27] On July 1, 1915, Humphrey was transferred from Moab, Utah, to Panguitch—then headquarters for the old Sevier Forest. Humphrey could not take over management of the Sevier Forest until early August, so he used the interim to familiarize himself with the area. During one of his forays into the East Fork Range, Humphrey was prompted by Forest Service Ranger Elias Smith of the East Fork Division to view the eastern escarpment of the Paunsaugunt Plateau. Humphrey showed little interest in the suggestion, but Smith was insistent. When Humphrey came on to the rim, just south of where Bryce Lodge stands, he was stunned:

You can perhaps imagine my surprise at the indescribable beauty that greeted us, and it was sundown before I could be dragged from the canyon view. You may be sure that I went back the next morning to see the canyon once more, and to plan in my mind how this attraction could be made accessible to the public. [28]

First hand accounts imply that Mark Anderson, foreman of the Forest Service grazing crew, was elected by Humphrey to publicize the "find." Anderson states that immediately after viewing Bryce Canyon for the first time in the spring of 1916, he rode into Panguitch and telephoned a telegram, by way of Marysville, to the District Forester in Ogden. In it Anderson requested that Regional Forest Service photographer George Coshen be sent down to Bryce Canyon with movie and still cameras to take pictures of the grazing crew "at work" near the plateau rim. Coshen, escorted by Forest Service Ranger Wallace Riddle arrived in Panguitch the following evening with his equipment. All the next day he took pictures which Anderson captioned. The movie and a number of still pictures were sent to Washington, D. C., and shown to Forest Service officials. According to Anderson, these pictures, or copies of them, were also made available to Union Pacific Railroad officials in Omaha. [29]

Another member of the Forest Service grazing crew, Arthur W. Stevens, wrote a short, illustrated article late in 1916 for Outdoor Life an early Union Pacific publication. [30] At about the same time Humphrey dictated an article, published under the name J. J. Drew, [31]

for the Red Book, a periodical issued by the Denver and Rio Grande Western Railroad. These were the first descriptive articles of Bryce Canyon to be published.

Late in the spring or early summer of 1916, Humphrey with the support of Anderson and James T. Jardine—then in charge of National Forest Service grazing studies—secured an appropriation of \$50. The money was used to build rough bridges across the East Fork of the Sevier River and Tropic Canal. Dead timber was also cleared out of "Dave's Hollow." [32] Homesteaders did most of the roadwork; the Forest Service furnished the necessary materials for the bridges. The finished product was a dry weather road that made the plateau rim near the present lodge accessible to automobile traffic. To traverse the corral at Dave's Hollow Ranger Station it was necessary to open and close a gate on both the north and south sides of the station. [33] When the road between Panguitch and Tropic was later altered, Humphrey was granted an additional appropriation of \$150 to connect the "rim road" to it.

The year 1917 saw Bryce Canyon really opened to the world. While engaged on a business trip in Cedar City, Humphrey encountered a photographer, Adams, who had heard of the canyon. Humphrey agreed to take the photographer up to the rim, if Adams could get over to Panguitch. Apparently, Adams managed to do so, and in Humphrey's words "secured some of the best pictures taken up to that time . . . and these he placed on sale [as postcards], and they added to the advertisement of Bryce Canyon." Later in the year Humphrey also showed Marcus Jones, a botanist-photographer, and J. Cecil Alter the wonders of Bryce. Alter, the U.S.D.A. meteorologist in Salt Lake City, wrote an article on Bryce, Improvement Era published March 1919 in the Utah journal. [34] During the clement months of 1917, C. B. Hawley, a director of the Utah State Automobile Association, made the trip to Bryce Canyon and reported his "find" to officers of the Association in Salt Lake City. F. C. Schramm, another director of the Association, was sent out shortly afterward to confirm Hawley's description. Schramm's report was even more flattering than Hawley's had been. Hawley, Schramm, and State Senator William Seegmiller of Kanab then encouraged Oliver J. Grimes, official photographer of the Salt Lake Tribune to visit Bryce Canyon. [35]

Grime's visit to the canyon is notable for several reasons. His full page article on Bryce Canyon, titled "Utah's New Wonderland," appeared in the Sunday Magazine Section of the Salt Lake Tribune on August 25, 1918. A profusely illustrated article, it was probably read by more people than anything on Bryce Canyon up to that time. Grimes convincingly put forward the case that Bryce Canyon was open to automobile traffic, and furnished explicit directions from Panguitch to the Plateau rim:

0.0 miles - Leave Panguitch on the Kanab road
7.3 - Road forks, turn left and cross river [the Sevier]; go through Red Canyon and some sand and washes and, at
18.2 - Road forks at corral on right; turn right and, at
20.0 - Gate—Go through it; (I didn't and got lost).
24.8 - Bryce's canyon.

Grimes later became State Secretary to Governor Bamberger (1917-20). The Governor himself was no supporter of scenic attractions. [36] Grimes, however, found it within his power to help influence the State Legislature. His unceasing efforts, abetted by an article on Bryce Canyon included in the October 5, 1918, issue of the Scientific American, [37] seemingly influenced the Utah Legislature. On March 13, 1919, a Joint Memorial passed the Legislature which reads as follows:

On the public domain within the boundaries of the Sevier National Forest, in the Pink Mountain region, near Tropic, Garfield County, Utah, there is a canyon popularly referred to as "Bryce's Canyon" which has become famed for its

wonderful natural beauty. Inasmuch as the State and Federal Governments have indicated a desire that the natural attractions of our State and our Country be protected and preserved for the enjoyment of posterity, therefore, your memorialists respectfully urge that the Congress of the United States set aside for the use and enjoyment of the people a suitable area embracing "Bryce's Canyon" as a national monument under the name of the "Temple of the Gods National Monument."

General recognition of Bryce Canyon as an area of National Park caliber dates from this time. [38]

Private Party—the Syretts [39]

When the Forest Service made the first attempt to publicize Bryce Canyon in the spring of 1916, Reuben (Ruby) Carlson Syrett and his wife, Clara Armeda (Minnie), were living in Panguitch. The Syretts had been scouting the area to start up a ranch. Six weeks after the birth of their first daughter on March 15, 1916, the Syretts decided to homestead a quarter section near Bryce Canyon. Their choice of land, approximately 3-1/2 miles north of what is now Sunset Point, was a fortunate one. Apparently, the Syretts lived at the Bryce ranch 6 weeks before a Tropic rancher, Claude Sudweeks, introduced them to the rim: "They were speechless, just stood and looked. When they could talk, they could only whisper." [40]

During the late summer of 1916 the Syretts began to invite their friends in Panguitch up to see the canyon. This was an amateurish but effective way for them to advertise the area's scenic qualities. Most people in Panguitch thought the Syretts were foolish to homestead in such a desolate locale, [41] but Ruby and Minnie tenaciously hung on to their homestead claim, and even began to purchase additional land near the homestead. Because of the severe winters, the Syretts spent some time between 1916-19 in Escalante—about 30 miles due east of Cannonville. Here Ruby helped his brother run a flour mill. Agricultural pursuits in Tropic also occupied the family.

By 1919 word had spread to Salt Lake City that Bryce Canyon was eminently worth visiting. On a Sunday in the spring or summer of 1919 a sizeable group from the capital did make the trip. To accommodate these people the Syretts erected a tent near Sunset Point and served a noon meal. Later in the day Ruby went back to the Bryce ranch and brought up five or six beds, which he dispersed under the pine trees near the Plateau rim. The Syretts provided an evening meal and breakfast the following morning. Before noon on that Monday more people arrived. Whether by design or chance the Syretts began accommodating tourists. [42] They remained near Sunset Point until the fall of that year.

During the spring of 1920 the Syretts decided to build a permanent lodge on the southeast quarter of Section 36 of Township 36 South, Range 4 West, Salt Lake Base and Meridian. This land had been set aside as a school section by the State, so before Ruby started construction he obtained "verbal" permission from the State Land Board. [43] The lodge, soon named "Tourist's Rest," was made of sawed logs and measured 30 feet by 71 feet. It contained a sizeable dining room with a fireplace, a kitchen, a storeroom, and several adjoining bedrooms. In keeping with the Syrett's informal nature, the lodge's double front doors served as a guest register. Visitors thoroughly enjoyed carving their names onto the doors. Eight or ten functional cabins were built near the lodge, as well as an open air dance platform, measuring 35 feet by 76 feet. [44] This modest complex accommodated tourists from all over the world, [45] and the Syretts did well by it until it was sold to a subsidiary of the Union Pacific System in September 1923.

<<< [Previous](#)

<<< [Contents](#) >>>

[Next](#) >>>

brca/hrs/hrs2.htm
Last Updated: 25-Aug-2004

Bryce Canyon

Historic Resource Study



REGIONAL DEVELOPMENT

CONCEPT-ORIGINS

By the early 1920s four major parties recognized Bryce Canyon's scenic potential. These included: (1) the influential citizens of Salt Lake City, acting through Utah's State government; (2) the National Forest Service; (3) the National Park Service; and (4) the Union Pacific System. Each party was interested in the Canyon's development for different reasons, and each was thus apt to rate its importance differently. All parties, however, were unanimous on two issues. First, if Bryce Canyon's development was pursued, the cooperation of the remaining three groups was essential. Second, any meaningful physical plan for Bryce Canyon was inseparable from the more general economic development of southwestern Utah.

On paper the State of Utah stood to gain the most from nationally popularizing Bryce Canyon. In the summer of 1922, however, Salt Lake City's most important boosters had temporarily directed their attention elsewhere. They were captivated by the Wasatch summit drive project, and were convinced that this attraction near the capital would hold up westbound motorists for several days. A good chunk of the tourist auto traffic might not even bother going on to the coast. For the time being, substantial investments in southwestern Utah by the State would have to wait.

One high ranking Forest Service official, Acting Forester F. A. Sherman, considered that the Salt Lake people were on the "wrong tack." [46] In Sherman's opinion, Utah's version of an Alpine scenic highway was unlikely to hold up more than 25 percent of the westbound motorists. Even those who took the drive could tear through it in a day and continue westward. Sherman's contention was that tourists from east of Colorado were psychologically primed for California. These people were only inclined to stop in Salt Lake City to see the Mormon Tabernacle, maintenance their automobiles, gas up, and move on.

Sherman firmly stated where he thought the State should place its primary emphasis:

It is my feeling that Utah's best bet, which is also Salt Lake's best bet, is to emphasize and capitalize the very unique attractions in the southern part of the State, such as Bryce's Canyon, Cedar Breaks, Zion National Park, and the Grand Canyon. Their aim should be to divert the west-bound traffic south from Salt Lake through their State to Bryce Canyon, Grand Canyon, Zion Canyon, Cedar Brakes [sic], and then westward. Of course they (tourists) will not be spending their money in Salt Lake City, but you will see enough of Utah to realize that most of the money left in the State eventually finds its way into the capital city. [47]

The Forest Service realistically knew that leadership in the development of southwestern Utah was not going to come out of Salt Lake City. Nevertheless, whoever took charge would have to lend a sympathetic ear to public opinion emanating from the capital.

A report monitoring recreation problems in District 4 was presented to Forest Service

officials in Washington, D. C., during the fall of 1922 by "collaborator" Frank A. Waugh. He noted the geographic unity of southwestern Utah, the acute need for better roads, and the assessment that Bryce Canyon presented the most urgent problems in the entire District. Waugh thought it incumbent on the Forest Service to take lead in making Bryce Canyon a national monument. By effecting an exchange of Forest Service lands, the agency was in a position to acquire Section 36 from the State with a minimum of delay. Waugh recommended the prompt appointment of a Forest Ranger for the area, a topographical survey, and careful reconnaissance for available water. [48] His well thought out report also presented the first known physical plan for Bryce Canyon.

I . . . recommend that, in order to avoid serious mistakes, a development plan for this area be worked out at the earliest possible opportunity. This plan should cover, amongst other features, the following:

1. Location of hotel and attached camps, with ground plan for the same.
2. Location and equipment of public camp-ground for automobile tourists.
3. Location, distribution and allocation of water supply.
4. General sanitary plans.
5. Suitable approach to camp and to rim view.
6. Trails along the rim of the Canyon.
7. Trails into the Canyon.
8. Location of store, post office and other services.
9. Location of public garage and service station.
10. Aeroplane landing. (Someone has already been at the Canyon looking for such a landing.)
11. All night camps in the Canyon. [49]

Steven Mather, the first Director of the National Park Service, was undoubtedly interested in the scenic region of southwestern Utah. He was, however, against including Bryce Canyon in the National Park System. [50] Mather preferred to have Bryce Canyon become Utah's first State park, and urged this course of action upon Governor Charles R. Mabey and the State Legislature. On December 19, 1921, a general meeting of all interested parties was convened in Salt Lake City to create a State Park Commission. In accordance with Mather's wishes, the "Committee on Legislation and Geographic Boundaries" recommended that Bryce Canyon be made the first of a series of State parks. [51] Only in 1924, when the State failed to do anything with Bryce, did Mather agree to Bryce Canyon's acquisition as a national monument. Given this status it would be provisionally administered by the Forest Service.

Because of its considerable financial resources and the company's willingness to invest in projects that promised to turn a tidy profit, the Union Pacific was probably the party most actively interested in Bryce Canyon. There were, however, formidable problems involved in the development of Bryce Canyon, and these the company had to carefully weight against future gains. The Union Pacific had two immediate problems. The first was to assess its relationship to the State of Utah, the Forest Service, and the National Park Service and determine how cooperative these agencies would be to one another. The second involved ascertaining the intentions of the Denver and Rio Grande Western Railroad (D.& R.G.), whose existing track to Marysville, Utah, positioned it to outflank a major developmental project by the Union Pacific.

Section 36 rightfully appeared to Union Pacific officials as the key to Bryce Canyon's future development. If the State refused to implement a conciliatory policy, the railroad's investment in Bryce Canyon was an unjustifiable risk. Major difficulties were not anticipated with the Forest Service. In fact, the Union Pacific would have preferred to deal exclusively with the Forest Service, in lieu of the National Park Service. [52] Mather's opinion of Bryce Canyon

was probably known to Union Pacific officials, which implied that friction over Bryce Canyon between Federal agencies would be minimal.

Denver and Rio Grande Western Railroad

J. W. Humphrey once made an effort to interest the Denver and Rio Grande (D. & R.G.) Western Railroad in Bryce Canyon, shortly after its "discovery" in the spring of 1916. He explained how tourist traffic could be easily linked to the North Rim of the Grand Canyon, and "other attractions down that way." [53] At about the same time the Union Pacific reputedly received the pictures and color movies shot in Bryce Canyon by Forest Service photographer George Goshen. [54] Why one railroad had its interest aroused and the other did not is an issue worth examining.

The growth of southern Utah's livestock industry and the promise offered by metallic ore deposits in the area prompted the D. & R.G. to extend its trackage from Thistle, Utah, to Marysvale. The first train entered Marysvale on August 7, 1890, [55] and construction of Marysvale's depot followed 9 years later. [56] In 1915 a big mining boon struck Marysvale. Gold was discovered in the mountains near town, although workable claims proved short lived. A more important resource proved to be nonmetallic alunite ore, from which alumina oxide and potash as a by-product were extracted. As long as the German embargo of potash lasted during World War I, an Armour subsidiary—Mineral Products Corporation—prospered. Three additional companies outside Marysvale concentrated exclusively on mining crushed potash ore for the manufacture of ammunition and fertilizer. [57]

Within a few short years Marysvale grew from a town of a few hundred to several thousand.

Horse drawn carriages and hacks met the train each morning to pick up the passengers and cart them off to either the Bullion Hotel, the Pines, the Grand Hotel, the Marysvale Hotel or the Straw Place. [58]

At this juncture the D. & R.G. supposedly executed plans to push its trackage all the way to Flagstaff. [59] Marysvale's economy again took a radical turn when the war's end dramatically braked the demand for high-cost aluminum. Potash could be imported more cheaply than mined in Utah. The town's economy began to slip into a steady decline. By the early 1920s both freight and passenger traffic were way off standards set during the teens.

During the clement months of 1922, however, some tourist traffic was still routed through Marysvale. Touring automobiles from three outfits eagerly met the morning Salt Lake City mail train. Arthur E. Hanks operated out of Marysvale. He conducted a 1-1/2 day tour to Bryce Canyon, as well as a 4-1/2 day junket to the North Rim via Bryce Canyon. H. I. Bowman headquartered his touring service out of the Highway Garage in Kanab, Utah. Given his location, it was necessary for him to base tours on the number of miles traveled:

50 cents per mile 5 passenger car (4 passengers and driver);
60 cents per mile 7 passenger car (6 passengers and driver); a minimum of 20 miles will be charged for each day. Two children under six years of age carried in lieu of one adult; 25 pounds baggage per capita carried free. [60]

Only Parry Brothers of Cedar City offered tours to Bryce Canyon, the North Rim, Zion National Park, and Cedar Breaks. Touring was expensive in the early 1920s. The Parry Brothers' North Rim-Bryce Canyon excursion, a 5-day affair, cost each adult \$80; the 8-day Bryce, North Rim, Zion, Cedar Breaks loop \$140. [61]

Notwithstanding the light volume of tourist traffic conducted through Marysvale, the Union Pacific (UP) was deeply concerned about the D. & R.G.'s future plans for Marysvale. On

October 17, 1921, W. S. Basinger, Passenger Traffic Manager of the company, directed a brief report to H. M. Adams, Vice President in charge of traffic for U. P.; in it Basinger frankly expressed his uncertainty over the matter:

The construction of a railroad only a part of the way into the scenic territory would simplify very materially the problem of developing it in that respect, in that it would decrease the distance for auto transportation. The general impression exists that most of this territory is valueless except for its scenic attractions. The fact is quite the contrary and I feel sure that the opportunities for successful development, both from a freight and passenger standpoint, are large and are well worth careful consideration.

The D. & R.G. now have a line extending south from Thistle, Utah, to Marysvale, which is situated at the north end of the territory described. From time to time there are rumors that this line will be extended. Some of these rumors state that the extension will be on account of the large amount of lumber available. Others are based on oil development of which there are some indications. Whether, however, the D. & R.G. have ever given serious consideration to the extension of this line, I am unable to say. [62]

As early as 1916 J. W. Humphrey had gotten the distinct impression from D. & R.G. officials in Salt Lake City that any plans to build a tourist hotel at Marysvale, or to provide company bus service to scenic attractions, was out of its line. Humphrey inferred from his interview with unspecified personnel that "possibly financial difficulties of their H. H. System prevented them from undertaking a new project of that kind." [63] An examination of D. & R.G. archival materials does suggest that the company was in and out of financial trouble during the early 1920s. [64]

An intracorporate letter, dated August 22, 1922, proves that by this time the Union Pacific felt it could accurately ascertain the D. & R.G.'s position regarding the southern Utah tourist trade. This key piece of correspondence was directed from Union Pacific President Carl H. Gray to Judge H. S. Lovett, Chairman of the company's Executive Committee in New York City.

I have discussed the question of D. & R.G.W. competition with Mr. J. H. Young [unidentified]. He tells me they will be glad to enter into the same arrangement with us that they now have for Yellowstone Park excursions, establishing a line of rates which would permit passengers to go from Denver to Salt Lake City via the D. & R.G.W., to be delivered to our line at that point, in which event, they would not put in any excursion rates permitting a side trip to Marysvale. This would bring all excursion business which moves via either line, to one railroad from Salt Lake City to Cedar City. I would regard this as a satisfactory arrangement from both standpoints, because I cannot believe they can ever satisfactorily handle passengers over this long branch with the character of service which they could afford to provide. I think we can safely disregard Marysvale as an element of competition. [65]

[<<< Previous](#)

[<<< Contents >>>](#)

[Next >>>](#)

Bryce Canyon

Historic Resource Study



NATIONAL MONUMENT STATUS

LEGISLATION (1919-24)

The Legislative Memorial, directed to Congress by the State of Utah in March 1919, was followed within months by Utah Senator Reed Smoot's legislative attempt to make Bryce Canyon a national park. [182] Senate Bill 3379, "a bill to establish the Utah National Park in the State of Utah," was introduced to the first session of the 66th Congress on November 9, 1919. [183] During the spring of 1920 the Secretary of the Interior, John Barton Payne, was asked to report on the bill, and defined his Department's position as follows:

That this area covered in the pending bill should be at once brought under full national contract and protection is not only desirable but imperative, but it is believed that this should be accomplished by creating it a National Monument by presidential proclamation rather than as a national park. Later on, when investigation of the other areas has been made . . . it will not be difficult to have the entire area created as a national park if Congress so decides. [184]

Smoot, even though Chairman of the Committee on Public Lands, found himself stymied. Later in 1920 Smoot was probably instrumental in soliciting descriptions of Bryce from John A. Widtsoe, President of the University of Utah, and Herbert B. Gregory, Professor of Geology at Yale University. Bryce Canyon itself was given extensive publicity by the National Parks Association. [185] These measures appear to have had a favorable effect on Congress, and Smoot was encouraged enough to introduce Senate Bill 487 to the first session of the 67th Congress on April 12, 1921. [186] Senate Bill 487 was a duplicate of the Utah Parks bill he had introduced some 18 months earlier. Yet, Smoot hoped the new Republican Administration, and the new Secretary of the Interior, Albert B. Fall, would see things differently. Fall reported on Senate Bill 487 in mid-June 1921:

I am informed that there are certain other areas in the general vicinity which probably should be considered for inclusion in a park if one be created, and that the Bureau of Parks proposes to conduct an investigation in the vicinity, probably this year.

I believe it would be well to defer the enactment of the legislation until that investigation is completed. [187]

There was little Smoot could now do but bide his time.

The park proposed by Smoot was comparatively diminutive, comprising no more than 11-5/8 sections of land (7,280 acres). Eight of these lay within the eastern side of the Powell National Forest, [188] and included: (1) Section 31 in T. 36 S., R. 3 W. (S.L.M.); (2) Sections 6, 7, and 8 in T. 37 S., R. 3 W.; (3) Sections 1, 12, and 13 in T. 37 S., R. 4 W.; and (4) the much discussed Section 36 in T. 36., R. 4 W.

Late in 1922 Senator Smoot had apparently given in to the idea that Bryce would have to become a national monument before it became a national park. On December 19, 1922, a meeting was held in Smoot's Washington office. Present were Union Pacific's General Traffic Manager W. A. Basinger, Acting Director Arno B. Cammerer, Assistant Director Horace Albright of the National Park Service, Utah General Land Office Commissioner Spry, Utah Congressman Don Colton, and Mr. Kneipp of the Forest Service. The future status of Bryce Canyon was practically the sole topic of discussion, and two important decisions resulted from the conference. First, Smoot agreed that for the time being the campaign to make Bryce Canyon a national park should be shelved, and instead steps be taken to make it a national monument. Second, the monument would retain the 11-5/8 sections asked for in the proposed national park, with the 3-5/8 sections outside Powell's boundary incorporated into it. Additionally, all present agreed that Bryce Canyon National Monument should be administered by the U. S. Forest Service. [[189](#)]

Strong recommendations by the Departments of Interior and Agriculture, and the Institute's high appraisal of Bryce Canyon's geological uniqueness, [[190](#)] prompted President Harding to proclaim Bryce Canyon a national monument on June 8, 1923 (Map 3). In order to effect national monument status for the entire 11-5/8 sections, it was necessary to change Powell's boundaries so as to include: (1) all of Section 32 in (2) the W1/2, NE1/4, and W1/2 of the SE1/4 of Section in T. 37 S., R. 3 W.; (3) the W1/2 and W1/2 of the E1/2 of Section 8 in the same Township as Section 5; and (4) all of Section 17 in the same Township as Sections 5 and 8. T. 36 S., R. 3 W.; Smoot probably acceded to the creation of a national monument only to gain time and strengthen his contention that Bryce Canyon be made a national park. On December 10, 1923, he introduced Senate Bill 668 to the first session of the 68th Congress [[191](#)] — a duplicate of his 1919 and 1921 National Park bills. This time Smoot's campaign was abetted by the support of Michigan Congressman Louis B. Cramton, who was the Chairman of the subcommittee for Department of Interior appropriations. Cramton had traveled extensively throughout the High Plateau country during July 1923, [[192](#)] and was invited by the American Automobile Association to deliver a broadcast, extolling the wonders of scenic southern Utah. [[193](#)]

Cramton did this over the radio in Washington, D. C., on April 17, 1924. The speech was florid but undoubtedly influential. An excerpt follows:

This rapid outline of the other wonders of this region must now suffice while I give my time to Bryce Canyon, so aptly termed by Prof. Frederick Pack of Utah University as Nature's "most delicate jewel."

[. . .]

I want to tell you my impressions of the canyon as from its rim I saw the full succession of its inspiring contrasts, its richly beautiful panorama—by the glare of day, with the passing of the sun, in the dim starlight, at the rising of the moon at midnight, and at the dawning of another day. The ordinary schedule of my waking and sleeping was shattered, but that does not matter if you have but a day at Bryce. The maze of forms and outlines in the canyon gives fancy free rein and you are thrilled not only by what the eye perceives but by what it "half creates" as well, as Wordsworth has it.

Sit with me here near the chasm's brink as the sun drops low. Before your fancy presents to you the city beautiful, the myriad forms left in the disorder of chance after centuries of erosion resolve themselves into something planned . . . The architecture is all in harmony. Great buildings rising hundreds of feet, passageways, sometimes but a few feet wide, separating one structure from

another, but the walls erect and accurate, story upon story. From Acropolis Hill see how the grade drops rapidly to the waterless river bed which is parked so plentifully with trees on either side of the watercourse. Rising then abruptly to the right from the river are vermillion cliffs, where the palace of the king appears, surrounded by great turreted walls, a steep approach leading to the castle itself, nestling close against the barren cliff.

There is no sound; no smoke arises; nothing in motion but the circling cliff swallow. It is simply the ideal of fancy.

The sun has gone. Darkness falls closer and deeper and the fine tracery of the architecture dims from sight, only the lighter shades of some of the buildings holding prominence. Still you can see the great commanding outline of the fortress and in the center the white of the crowning Acropolis. The swallows are no longer flying about . . . There are no tones, no lights from below; only the splashes of white upon the dark background, set off with darker markings of the tree areas. The city of fancy is asleep.

At midnight we cautiously approach again the rim and watch, while far in the east over Acropolis Hill a glow enriches the horizon. Soon a silver point comes to view, like a star of hope for the darkened city. Rapidly rises the majestic moon that whitens the night and brings out formless shapes of the city but does not lighten. It mounts to the heavens and the city to the west of us reflects it dimly. It is a spectral city, and the watcher under the rays of moon, the million wonders of the Milky Way, and all the stars overhead, comes to imagine an occasional moving in the tenantless homes. But there is nothing in the city but night.

Up again and to the watcher's post; the day is dawning. A rosy hue in the east; an orange glow over Table Cliff Plateau; to the right a group of clouds which simulate a snowclad range of peaks for a time and then revert to cloud banks, reflecting rosy tints, as mounts the orb of day.

[. . .]

Before you now in glare of day is a prehistoric city of Babylonish splendor. It seems to have been covered with the sands of ages and appears now as if largely revealed by recent excavations still to be completed, banks of earth still in part enshrouding edifices and walls the impression mounting that further beauties are yet to be revealed.

Far in the east you see the modern Utah town of Tropic, surrounded by its fertile green fields, a touch of reality to bring fancy back to earth. But the spell of Bryce Canyon hangs long in your memory. [[194](#)]

Cramton's mellifluous tongue certainly did nothing to prejudice Smoot's cause. However, it was not until June 7, 1924, that Public Law No. 227 of the 68th Congress established the "Utah National Park." Smoot's immediate reaction to the bill's passage is not known, but he could not have been completely happy with it. The law's key provision stipulated that the Utah National Park, encompassing the same tracts of land as Bryce Canyon National Monument occupied, would not be made a national park until all "land within the exterior boundaries of the aforesaid tract shall first become the property of the United States." [[195](#)]

FOREST SERVICE ADMINISTRATION (1923-28)

Unanimous agreement that Bryce Canyon National Monument should be administered by the Forest Service was based on the monument's contiguity to Powell National Forest. Thus, in theory, the monument's supervision would be nothing more than an extension of supervision for Powell National Forest. That the Forest Service exercised its administrative responsibility for Bryce Canyon with a light hand is borne out by available facts. During the 1927 tourist season, the monument was supervised by "Forest Service Ranger" V. O. Brown. Actually, Ranger Brown was employed jointly by Garfield County, the Forest Service, and the Utah Parks Company—but received his salary exclusively from the latter. Brown remained in Bryce Canyon from June 1 to November 1. He took care of the automobile campground, gave out information to campers and Utah Parks Company tourists, and guided visitors on trail trips. In September 1927 visiting National Park Service personnel got the distinct impression Brown earned most of his compensation from tips. [196]

Brown's situation is instructive, because it shows the Forest Service followed its principle of spending money for physical improvement rather than administration. [197] In fact, the key contribution made by the Service to the monument's development had to do with roads. As early as 1923 the Forest Service cooperated with the State Highway Commission to make Bryce Canyon more accessible to the public. Funds allotted for the general development of National Forests were used to improve the Panguitch-Tropic road via Red Canyon, and the Bryce Canyon road from what is now Ruby's Inn to the SE1/4 of Section 36 in the monument. A total of \$123,000 was appropriated for the Panguitch-Tropic project, of which \$6,300 had been spent by July 1, 1923. Similarly, of \$22,300 set aside for the Bryce road, \$1,600 was spent by the end of fiscal year 1922. [198] In 1927, the monument road was described as having been constructed according to the standards of the Bureau of Public Roads. At the time the Forest Service proposed to extend this road some 4 miles southeast, toward Bryce Point. [199]

Forest Service expenses for the monument itself were comparatively small. For example, during fiscal year 1923 only \$500 was allotted for administration. [200] In 1927 not more than \$100 was spent on maintenance and improvements. [201] Between 1923-28, then, the Forest Service essentially did the following: First, and most importantly, it provided a good road into the monument, and a fair weather road as far as Bryce Point; Second, the automobile campground was maintained at no more than adequate standards. In the 1927 season, 16 tables, 12 garbage cans, and 5 toilets—3 for men and 2 for women—had to suffice for 150 to 200 automobiles, each carrying an average of 4 people; [202] Third, several miles of foot and horse trails were constructed and kept up between what is now Sunrise Point and Bryce Point; Fourth, a "ranger" was kept on duty during the clement months to give tourists general information, and to accompany groups on trail trips.

Between 1923-28 no accurate record was maintained on visitation statistics. V. O. Brown estimated that 4,200 cars would enter the monument during the 1927 season. Of these approximately 60 percent used the campground—the remainder the lodge. Averaging four to a car, then, some 16,800 people entered the monument by automobile, and another 8,000 by Utah Parks Company vehicles, for a rough total of 25,000. [203] In subsequent years, this ratio of 2:1—between tourists who came in by private automobile and the carriage trade—was to dramatically increase in favor of the former.

EARLY ACTIVITIES OF THE UTAH PARKS COMPANY AT BRYCE CANYON (1924-29)

Absence of Contractual Agreements

As explained in "Incorporation of Utah Parks Company," it was because of National Park Service Director Mather's unwillingness to grant a railroad company concessions in Zion that the Union Pacific found it necessary to secure these in the name of a subsidiary—the Utah Parks Company. Accordingly, the Utah Parks Company's authorization to operate at Zion was based on a contract between the Utah Parks Company and the National Park Service, dated June 9, 1923. A near-duplicate contract was effected between the same parties for operations at the North Rim on November 10, 1927. Transportation rights exercised by the Utah Parks Company in Zion and the North Rim were obtained from the Parry brothers. The situation encountered by the Utah Parks Company at Bryce Canyon was somewhat different. Since the Forest Service exercised administration over the national monument from 1923-28, the Utah Parks Company temporarily had no need of a formal concessions agreement.

Initial Construction Phase at Bryce Canyon

The first cost estimate for Bryce Canyon Lodge was given to Union Pacific Chairman Lovett by President Gray in a letter dated August 14, 1922. At this time Gray said 100-room structures at Bryce Canyon and Zion would cost from \$150,000 to \$175,000 each. [204] The following April, Gray revised this figure to \$315,000 for a 75-room lodge at Bryce Canyon, and \$335,000 for the same type of structure at Zion. [205] Lovett, upon receipt of these escalated estimates, became irritated. In his telegram to Gray, dated October 5, 1923, he asked Union Pacific's President to clarify the issue at once. [206] The following day, in a letter to Lovett, Gray admitted embarrassment for the earlier estimate—a figure given before there was an opportunity for detailed investigation. Subsequent consultations with architectural and construction personnel convinced Gray that he had badly underestimated the problems posed by Bryce Canyon's remote location, scarcity of usable timber and the severely limited labor pool in the Bryce Canyon's environs. [207]

Construction of the lodge began on a site approximately 4,000 feet south of the monument's north boundary, and 700 feet from the Canyon's rim. This spot was probably chosen by Underwood, Lancaster, Jones, and Hull during their reconnaissance of the area in the first week of May 1923. [208] Architect Underwood's later plans for Utah Parks Company buildings were approved by National Park Service Landscape Architect Hull, Superintendent E. T. Scoyen of Zion, and National Park Service Director Mather. [209] Foundation work and skeletal construction was probably completed during the working season of 1924. Both Melford Ahlstrom and Harmon Shakespeare, local residents who assisted in the lodge's construction, affirm that no unusual problems or delays occurred. [210]

In the original main building, finished by May 1925, there was an office and lobby, a dining room, kitchen, and showers and toilets for both sexes. The entire second floor was taken up by sleeping accommodations for overnight guests.

It is not known exactly when the main building's rock facade was applied, but it was definitely in place prior to September 1927. [211] Underwood's drawings for the wings are dated February 19, 1926, with revisions made on May 16. It must be assumed the wings were added during the working season of that year. Underwood's sketches for the wings show the rock facade, so it may have been added to the entire building during the clement months of 1926. There is no evidence to indicate precisely why the Utah Parks Company added the wings when it did, but the company's principal motive obviously stemmed from a desire to quickly increase the number of sleeping accommodations. A curio store occupied the lower level of the south wing. The addition of a Recreation Hall in 1927 rounded out the lodge's final configuration.

By September 1927 no fewer than 67 standard and economy cabins were grouped about the lodge. Construction on these had begun during 1925. Concrete walks connected all cabins to

the lodge. For the sake of esthetics, electrical wiring was placed in underground conduits. [212] Furnishings for standard cabins were surprisingly similar to those for deluxe cabins.

In September 1927 only 5 deluxe cabins were in existence, and 10 more augmented the lodge complex in 1929. Construction techniques at Bryce Canyon appear to have followed closely those used for the deluxe cabins at North Rim 2 years earlier. Lodge poles presented a particular problem for the deluxe cabins at Bryce Canyon, since each had to be 49 feet 10 inches long and 10 inches through the tip. The Utah Parks Company wanted nearly 100 of these and according to Harmon Shakespeare, Supervisory Forest Service Ranger Wallace Riddle was particularly cooperative allowing Shakespeare to "mark" those trees most suitable for the poles. [213] Concrete walks also connected the deluxe cabins to the lodge. As the illustrations make clear, the Utah Parks Company used a consistent motif for both the standard and deluxe cabins.

Service structures, including a garage, were begun in 1925. The most significant of these are included in the architectural data section. By the fall of 1927 water used by the complex was pumped from the springs at East Creek. Only an "infinitesimal" amount was obtainable from those located on White Man's Bench. [214] As early as 1927 it was apparent that the water supply at Bryce Canyon presented long-range problems. Sewage from the lodge complex was carried in a 6-inch pipe to a treatment plant approximately 1/2-mile north of the lodge building, and 500 feet west of the main road. Effluent first flowed into a septic tank, and was then sterilized with chlorine. Telephone service between Bryce Lodge and Cedar City was established by the fall of 1927. Apparently, the line provided excellent long distance capability. [215]

A bill of sale between the Los Angeles and Salt Lake Railroad Company and the Utah Parks Company on September 10, 1928, is an excellent document for ascertaining how much property the Union Pacific System owned. Just prior to Bryce Canyon's national park status it owned:

- 1 Main pavilion (frame), 41'6" x 130'4", with extensions,
 - North wing, 43'6" x 31'
 - South wing, 53'10" x 31'
 - West wing, 77'4" x 112'
- 18 Guest cabins (frame), 12' x 24'
- 63 Guest cabins (frame), 12' x 26'4"
- 5 Deluxe cabins (stone and log), 16'4" x 40'
- 4 Tent cabins, 12' x 14'
- 1 Oil sales cabin (frame), 10' x 12'
- 2 Comfort stations (frame), 16' x 30'
- 1 Laundry (frame), 14' x 16'
- 1 Employees' pavilion (frame), 21' x 53'
- 1 Power house (Corr. Galv. Iron), 24' x 42'
- 2 Toilets (frame), 6' x 6'
- 1 Chlorine house (frame), 6' x 8'
- 1 Septic tank (concrete), 7' x 9' x 26'10"
- 2 Filter trench (concrete), 197' x 8'4"
- 1 Filter trench (stone), 191' x 9'
- 2 Garage (Corr. Galv. Iron), 24' x 92' with 2 wings each 24' x 146'
- 6 Drivers' quarters (frame), 16' x 20'

- 1 Lumber tent, 8' x 10'
- 1 Tent, 8' x 10'
- 1 D.C. & H. building (frame), 12'4" x 40'2"
- 1 D.C. & H. building (frame), 21' x 73'
- 1 D.C. & H. building (frame), 8' x 8'
- 2 Toilets (frame), 4' x 6'
- 1 Bunkhouse (frame), 14' x 14'
- 2 Bunkhouse (frame), 12' x 12'
- 6 Bunkhouse (frame), 16' x 20'
- 1 Material shed, 14' x 15'
- 1 Lattice fence, 8' x 118'
- 1 Open air fireplace, 18' diam.
 - 6" pipeline from Shaker Springs (portion in Bryce Canyon National Park, only)
- 1 Concrete reservoir, 26'9" x 48'4"
- 1 Automobile barrier
- 1 Underground gasoline storage tank
- 2 Observation platforms
 - Concrete paths and steps
 - Roads and trails
 - Lighting system
 - Water supply system
 - Sewer system
 - Fence around 373 acres in Section 35, Township 36 South, Range 4 West
 - D.C. & H. equipment in cabins and pavilions
 - Telephone line, 2.765 miles
 - Power plant
 - Powerline. [216]

Bryce Canyon

Historic Resource Study



NATIONAL PARK STATUS

CREATION OF BRYCE CANYON

Early in July 1927 discussions took place at the Canyon Hotel in Yellowstone Park between Union Pacific's President Gray and National Park Service Field Director Horace Albright. [217] Their subject was the means by which Bryce Canyon could achieve national park status. National Park Service Director Mather had given Albright full authority to conduct negotiations with Gray, and Gray made it clear to Albright the Union Pacific was vitally interested in immediate action. Omaha had developed deep concern over the deplorable condition of roads in northwestern Arizona, and was reluctant to go forward with its plans for the development of the North Rim until transportation was made more efficient to and from it. [218]

Basically, what came out of the discussions between Gray and Albright was an exchange proposal by Gray. Omaha wanted the Zion-Mt. Carmel road, and specifically wanted the National Park Service to authorize that portion of it within Zion to be completed within 2 years. In return the railroad agreed to deed the 11.69 acres owned by them at Bryce Canyon to the Federal Government. Additionally, Omaha consented to the transfer by the State of Utah to the Federal Government the balance of Section 36, upon which the railroad had a long-term lease. In order to operate at Bryce under National Park Service administration, the Union Pacific wanted a concessions agreement duplicating privileges it received at Zion by virtue of the June 9, 1923, contract.

Gray readily apprehended the fact that no one individual could conclude an agreement binding the Federal Government, so he suggested placing the deed of land in escrow until the conditions asked for by the railroad were fulfilled. [219] Union Pacific's Finance Committee in New York approved the escrow agreement on July 26, 1927. [220] Necessary papers were actually placed under deed to the Federal Government in Walker Brothers Bank of Salt Lake City on August 12, 1927. [221]

Gray and Albright well knew that Congressman Cramton of Michigan was the only individual who alone could block the achievement of national park status for Bryce Canyon. Cramton simply would not permit Congressional appropriations to the Interior Department for the Zion-Mt. Carmel road until terms creating "Utah National Park" had been met. [222] As early as July 5, 1927, Acting National Park Service Director Arno B. Cammerer was careful to tip-off Cramton that negotiations between the Union Pacific and Park Service were proceeding satisfactorily with respect to Bryce. [223] On July 22, 1927, Cramton responded to Cammerer as follows:

I have your letter of July 5 with enclosures mentioned concerning the Utah National Park, etc. I am delighted to know of the very encouraging prospect for the clearing up of the Utah National Park situation. If that is cleared up satisfactory [sic] and in time, I see no reason why the road construction work in

Zion should not be pushed as fast as Mr. Mather desires. [224]

Thereafter, Cramton, with the aid of Utah Senator Smoot and Utah's Congressmen, began to push for legislation creating Bryce Canyon.

Cramton's reply to Cammerer says much for the Park Service's attitude toward the Bryce Canyon negotiations. There was, in fact, whole-hearted agreement with Union Pacific's proposal. Nevertheless, the Service faced an immediate problem of substantial proportions: financing the Zion-Mt. Carmel road within Zion. By the middle of July 1927 plans for sections 1 and 2 of the tunnel were available through Assistant Chief Hewes of the Federal Bureau of Public Roads. [225] Estimates for the work approximated \$700,000, and it was this figure the Park Service had to make quickly available.

Exactly \$450,000 was already in the Zion allotment, so Cammerer began to assiduously seek funds that could be transferred from appropriations granted other parks. This was done in the following way:

Glacier	\$ 9,000
(saving on contract for Babb-Many Glacier project)	
Grand Canyon	50,000
(saving on contract for North Rim project)	
Mesa Verde	50,000
Mount Ranier	70,000
(saving on contract for Nisqually-Paradise project)	
Yosemite	24,000
(paving of Yosemite Village plaza deferred)	
Yellowstone	77,000
Total \$250,000 [226]	

Finishing the road within Zion would cost an additional \$740,000, but Cramton could be counted on to secure these funds in appropriations for the next fiscal year. At a major conference in Salt Lake City on July 20, 1927, attended by representatives of the three principal parties, Henry H. Blood of the Utah State Road Commission assured the National Park Service that Utah would have its 16-1/2 mile section between Zion and Mt. Carmel constructed at the same time the Service finished its section. [227]

The State of Utah's most critical role in the Bryce Canyon project, however, hinged on its willingness to relinquish the lion's share of Section 36. This the State was willing to do, as Governor Dern made clear to Congressman Cramton on July 20, 1927:

I am pleased to inform you that the State Land Board had a meeting today and . . . you are hereby advised that the State of Utah will exchange the school section in question for some other section of land in order that Bryce Canyon may be made a national park . . . [227]

Dern had another reason for writing Cramton. Salt Lake City was not happy with the condition in the June 7, 1924, law renaming Bryce "Utah National Park." Dern thus put forward three sound arguments for scrapping the name. First, Bryce Canyon had already received extensive advertising during its national monument status by the Union Pacific. Changing its name would do much to negate the railroad's expense and effort. Second, the name Utah National Park had no local significance. It could have been used for any other

scenic attraction in the State. Third, the title implied Utah had but one national park, and Bryce would in fact be the second. Dern urged that the 1924 law be amended to read "Bryce Canyon National Park." [229] Accordingly, Senate Bill 1312, introduced to the first session of the 70th Congress by Senator Smoot was titled a bill "To change the name of the Utah National Park . . . to the 'Bryce Canyon National Park,' and for other purposes." [230] By "other purposes" Smoot meant the acquisition of additional land.

<<< [Previous](#)

<<< [Contents](#) >>>

[Next](#) >>>

Bryce Canyon

Historic Resource Study



APPENDIX A

BRYCE CANYON NATIONAL PARK, UTAH

Civilian Conservation Corps and Emergency Relief Appropriation Act
Work Accomplished Under Supervision of the
National Park Service
April 1, 1933 to July 8, 1942

<u>Classification</u>	<u>Units of Work</u>		
	<u>CCC</u>	<u>ERA</u>	
110 Cabin	1		Frame Construction 28'8" x 21'8" three rooms
110 Residence		1	Remodel frame messhall into 22' x 44' three-room dwelling
110 Employee's Dormitory		1	Constructed according to Master Plan No. BC-3014E and working Plan No. BC-327 B most of the material being salvaged from other buildings
113 Comfort Station	2		Removed from campground and relocated and remodeled
113 Comfort Station	1		Log construction 13'6" x 24', two compartment
113 Pit Toilets	3		4' x 5' frame construction
113 Pit Toilets	2		6'6" x 5'6" native lumber for two occupants
115 Lookout-Rainbow Point	1		17'6" x 52' log construction, open front. Exhibit case back wall
120 Contact Station	1		Log construction 7' x 10'6" located on island 200' x 11' for landscaping
120 Move Messhall	1		Move building in sections and reassemble into five-room dwelling 23' x 44'7"
131 Boundary Fence	3204 rods	8.4 miles	5 strand barb wire cedar posts 10' spacing
134 Powerline	3.2 miles	.5 miles	Set posts for 7250 volt line in cooperation with Garkane Power Company, 1 mile of line in park
139 Sanitation Improvement		1	Excavating garbage pit 20' x 60' x 10'
139 Sewerline	700 linear feet		6" vitrified clay pipe
139 Sewer System	1		2800' vitrified clay pipe - 10 manholes connects to National Park System
140 Telephone lines	1.9 miles		Relocation of telephone lines to new location

141 Drinking Fountains	2		Rock Masonry pedestal 3'6" high
143 waterline	2300 linear feet		1100'- 2" galv. pipe 200'- 1" galv. pipe, 600'- 3/4" galv. pipe
148 Fireplaces	20		Rock masonry in accordance with standard plans.
149 Cattle Guard	1		8' x 22'—25' rails space 6-3/4" 8' underpass with 8'9" clearance reinforced concrete walls and beams
149 Cattle Guard	1		28'2" x 9'1" tread 40" rail concrete abutments
153 Road Signs	23		Yellow pine carved directional signs average 1'4" high. Posts yellow pine peeled and treated 3' high.
153 Monuments	1		Treated peeled yellow pine pillar 10' high supporting 8' x 4'9" entrance sign, 4'5" yellow pine pillar opposite
155 Tables	35		Table and bench combination in accordance with standard plans
155 Campground tables	51		Standard design, frame construction
157 Lecture Circle	1		Gravel surface, permanent log seats, timber platform with firepits
157 Miscellaneous Minor Improvements	1		Constructed museum exhibit cases
157 Fire Danger Weather Station	1		20' squared fenced enclosure housing hydrothermograph, fuel, moisture instruments and wind gauge, and specmeter
202 Minor Roads	3.05 miles		18' graded and graveled surfaced
206 Foot Trails	16 miles		.6 miles—4' gravel surface
206 Trail Improvement	12.5 miles		Reconditioning sections of trail widening to 4'
207 Horse Trails	45.2 miles		4' earth graded
304 Check dams	1000		1' to 5' permanent log check dams
603 Roadside Cleanup	7 miles		Remove dam timber, etc., on roadsides
609 Insect Pest Control	20745 acres	23100 acres	Spotting and treating acres beetle infected yellow pine and Douglas Fir
705 Landscaping	51 acres		Dressing and stabilizing road slopes
706 Moving and planting trees and shrubs	250	1150	Moving and planting native trees and shrubs around campground
710 Parking Areas	2250 square yards		300 square yards graded and gravel surfaced with rock masonry barrier, 1950 square yards with log barrier
711 Campground Development	.6 acres		Grading and surfacing for future development
713 Razing	1		

Undesirable Structure		Demolish and salvage of old contact station
713 Demolish Old Dormitory	1	Demolish building and salvage all usable material
713 Obliteration of Old Roads	4 miles	Change areas to original state with rock, trees, and brush
716 Footpaths— Rainbow Point	200 linear feet	6' path with 1/2" gravel surface
1004 Wood Eradication	14 acres	Eradication of poisonous and exotic weeds and plants
1012 Preparation and Transfer of Materials	55,458 F.B.M.	Windthrown logs salvaged and sawed into lumber
1012 Preparation and Transfer of Materials	84 logs	12', 14', and 16' lengths—average 24" diameter, salvage from insect control work
1012 Salvage Beetle Timber	94,000 F.B.M.	Salvage beetle infected timber which was sawed into lumber for future CCC use
1012 Stockpile- Road Maintenance	4500 Cubic Yards	Road material for highway maintenance
1023 Lineal Survey	50 miles	Surveys throughout the park
1025 Topographic Surveys	35 A	Surveys throughout the park.

[<<< Previous](#)

[<<< Contents >>>](#)

[Next >>>](#)

Bryce Canyon

Historic Resource Study



ENDNOTES

1. Herbert E. Gregory, "A Geologic and Geographic Sketch of Bryce Canyon National Park," Zion-Bryce Museum Bulletin No. 4 March 1940, p. 22, "Bryce Canyon National Park, Utah," pamphlet, U.S. Department of the Interior. Washington, D.C.: Government Printing Office, 1941, p. 8.
2. Wayne Bryant, "An Introduction to Bryce Canyon National Park." Unpublished essay, 1947. Zion History Files.
3. "Summary of Archeological Resources and Resource Management Needs for Bryce Canyon National Park." National Park Service. Midwest Archeological Center: Lincoln, Nebraska, June 1978, p. 1.
4. Gregory, "A Geologic and Geographic Sketch of Bryce Canyon National Park," p. 9.
5. Bryce Canyon, based on original of John Barnett, adapted by Don Follows. Bryce Canyon Natural History Association, 1972, p. 27.
6. Gregory, "The Geology and Geography of the Paunsaugunt Region, Utah." Geological Survey Professional Paper 226 Washington, D.C.: Government Printing Office, 1951, pp. 16-17.
7. Clifford C. Presnath, "The Legend of Bryce Canyon as Told to the Park Naturalist by Indian Dick," Zion and Bryce Nature Notes. V. 8, No. 1. March 1936. Quote cited by Gregory, "The Geology and Geography of the Paunsaugunt Region," p. 17. The source for the quote is erroneously ascribed to Gregory on page 3 of Bryce Canyon National Park. Wonderland of the Pink Cliffs published by the Zion-Bryce Nature Association in May 1953.
8. Presnath, p. 3. "Both Johnnie and Dick were raised in the Bryce region, Johnnie having been born near the site of Escalante between 1870 and 1875, and Dick being still older with no memory of his birth place. They belong to the Av-o-ats-in, a Paiute clan which once roamed over all the Pink Cliff country east of the East Fork of the Sevier River, a country which they called Av-o-av, and which we now call the Paria valley."
9. William R. Palmer's "Indian Names in Utah Geography," Utah Historical Quarterly. V. 1, No. 1. 1932, pp. 5-26.
10. Presnath, p. 3.
11. Regional Archeologist, Memorandum to Superintendent, Bryce Canyon/Zion. November 29, 1951. Zion History Files. This memo includes a discussion of H. E. Bolton's definitive article on the Escalante expedition, titled "Pageant in the Wilderness," Utah Historical Quarterly, v. 18, 1950.
12. One of the most comprehensive chronologies of park history to 1956 is included on pp.

19-20 of the Bryce Canyon National Park Master Plan, Chapter 1, "Basic Information, The Land," January 1965.

13. Gregory, "A Geologic and Geographic Sketch of Bryce Canyon National Park," p. 11.

14. Ibid.

15. The earlier study is titled Geology of the High Plateaus of Utah with Atlas. Both of Dutton's studies were published by the Government Printing Office, Washington, D.C.

16. Bailey's description is often erroneously cited as the earliest known of Bryce Canyon. Actually, this distinction rightfully belongs to Grove Karl Gilbert, based on the excerpt cited from his 1872 notebook. The source for Bailey's description can be traced to the files of the Public Survey Office in Salt Lake City. In the mid-1930s the District Cadastral Engineer in Salt Lake, G.D.D. Kirkpatrick, found the description and sent it to the Zion-Bryce Canyon Superintendent, P. P. Patraw, Zion-Bryce memorandum for the press; October 1935, Denver Federal Records Center, Accession 52-A-100, Container 746149-50.500, publicity, Bryce Canyon. Captain George M. Wheeler, for whom the Wheeler survey was named described Bryce as "a work of genii now chained up in a spell of enchantment while their structures fall in ruins." This statement, written in the mid-1870s, also antedates Bailey's. See America's Wonderlands. The Scenic National Parks and Monuments of the United States Washington, D.C., The National Geographic Society, 1959, p. 191. "Bailey 'lost' two days at Bryce... looking for his large meerschaum pipe, which was usually chained to him. The hunt was unsuccessful, but the pipe turned up several years later." Utah. A Guide to the State compiled by Workers of the Writer's Program of the Works Progress Administration for the State of Utah. American Guide Series, New York: Hastings House, 1941, p. 460.

17. Gregory's work on local Mormon settlement near Bryce Canyon has yet to be matched. Much of this section is abstracted from "The Geology and Geography of the Paunsaugunt Region...", " pp. 17-18. Also see Ida Chidester and Eleanor Bruhn's Golden Nuggets of Pioneer Days. A History of Garfield County, Garfield County Chapter of the Daughters of Utah Pioneers, 1949, pp. 107-34.

18. Bliss reputedly has the distinction of being the first person to cross the park in a wagon. He traversed the rough area, near the present highway which enters Tropic from the north, in 1875. Orley needed the help of "a good cow mule" to help lower his wagon into the Valley. Utah. A Guide to the State p. 459.

19. Elnora A. Bryce, Family Genealogist. "Biography of Ebenezer Bryce," assistance of Annie Larson, et al. n.d., received into Bryce Canyon History Files March 27, 1959, p. 2, William R. Ridgway appears to have abstracted this biography for the article "Bryce Canyon is Memorial to Pioneer Farmer." The Arizona Republic, Phoenix, July 12, 1953.

20. Two accounts detail the construction of Tropic Ditch and the early days of Tropic: (1) A. J. Hansen, "The Village of Tropic," and (2) Ole Ahlstrom, "The Early Days of Tropic." Both accounts were collected and edited by park Ranger/Naturalist Maurice Cope in September 1935. Bryce Canyon National Park History Files.

21. Cited from J. Cecil Alter's "The Temple of the Gods," Improvement Era, v. 22, no. 5, March 1919, p. 395. In the late teens Alter was a meteorologist working for the U.S. Department of Interior Weather Bureau in Salt Lake City. He played a significant role in popularizing Bryce Canyon.

22. Robert Sterling Yard, The New Zion National Park Its Relation to the Grand Canyon also the Relation of both and of Bryce Canyon to the brilliantly colored Plateau Country of

Southern Utah. "To the few resident farmers, the painted canyons in the plateau rim were but a part of the rugged landscape that characterizes all southern Utah. Of more direct concern to them was the fact that the great cliffs, narrow canyons, and the meager supply of water and tillable land made the region unsuitable for large-scale agriculture. To the stockman, the rougher parts of the terrace now admired as scenery were obstacles." Gregory, "A Geologic and Geographic Sketch of Bryce Canyon National Park," p. 12. "The sense of awe awakened today by such inspiring spectacles of nature's handiwork appears to have been largely lacking in the hard-working pioneers who spent all their energy in wringing a meager existence from the wilderness." Angus M. Woodbury, "A History of Southern Utah and Its National Parks," Utah Historical Quarterly, v. 12, nos. 3 and 4, July-October 1944, pp. 111-209, revised and reprinted 1950. This attitude, on the part of Mormon settlers, purportedly applies to other scenic areas of southern Utah, as the following excerpt makes clear. "...It is a marked example of our incurious absorption in the business of living that so vast a region of scenic sublimity is only now beginning to become publicly known. Its slender population seems to have taken its beauty for granted. One of the natives of Springdale, at the entrance to Zion Canyon, said to me last September, 'I've been in this canyon hundreds of times but I didn't know there was anything to see till people came in two or three years ago and raved about it. It is pretty, ain't it?' So it was with Bryce Canyon; people had to 'come in' before it was appreciated" Washington, D.C.: The National Park Association, 1919, p. 24. Yard was the Executive Secretary of the National Park Association.

23. Eivind T. Scoyen and Frank J. Taylor, "The early pioneers in this country were a hard-working, God-fearing group of people, and in their struggle for existence, with Indians, drought, and circumstances combined against them, they had very little time to enjoy or appreciate the magnificent scenery which in recent years has become the greatest asset of southern Utah." The Rainbow Canyons foreword by Horace M. Albright. Palo Alto, California: Stanford University Press, 1931, p. 86. Scoyen was the first Superintendent of Bryce Canyon.

24. History of Garfield County, p. 291.

25. Yard, The New Zion, p. 25.

26. History of Garfield County, p. 293.

27. *Ibid.*, p. 292.

28. J. W. Humphrey, "Notes, Comments, and Letters," taped at Bryce Canyon, September 1959, transcription revised by Humphrey and entered into the Bryce Canyon History File January 1960.

29. Mark Anderson, "Autobiography." Uintah National Forest Correspondence, September 2, 1946. Microfilm A-622. Utah State Historical Society, Salt Lake City. Humphrey stresses that the movie was taken in color. "Notes, Comments, and Letters." Also see: (1) History of Garfield County, p. 293, and (2) The Inverted Mountains: Canyons of the West, ed., Roderick Peattie. New York: Vanguard, 1948, p. 149. The latter publication does not note that a color movie was made. Anderson indicates that the Assistant District Forester criticized Humphrey and others "for wasting money on this project." "Autobiography."

30. Humphrey "Notes, Comments, and Letters." Also see History of Garfield County, p. 293.

31. *Ibid.* "As J. J. Drew was clerk [of the railroad] his name appeared as its [the article's] writer."

32. Humphrey, "Notes, Comments, and Letters."

33. Humphrey, "Notes, Comments, and Letters."

34. Horace M. Albright, p. 86.

35. Curt B. Howley, "Discover of Bryce Canyon." The Utah Magazine v. 2, no. 5 (1936), pp. 11 and 38. Howley's contention the Hawley "discovered" Bryce Canyon in 1917 is untenable. Grimes states that he first heard of Bryce about February 1917 from Seegmiller, who considered Bryce even more picturesque and unusual than Zion. Later, Grimes' memory was jogged into a recollection of Bryce by a chance encounter with a "traveling man" at Marysville. Salt Lake Tribune, August 25, 1918. I have attempted to reconcile both the Grimes and Howley accounts, but Grimes is undoubtedly the more reliable of the two.

36. Bamberger is reputed to have once said: "I will build no roads to rocks!"

37. Memorandum to Mr. Chatelain regarding Dr. A. M. Woodbury's historical work on Zion. The author was LeRoy Jeffers. Humphrey once showed Jeffers about the Canyon and includes this amusing anecdote in "Notes, Comments, and Letters"—"He [Jeffers] came into my office on his way to the North Rim of Grand Canyon, and wondered whether it was worth while to make the side trip from highway 89, over to Bryce. I assured him that by all means he should see Bryce Canyon, and as he still hesitated, I told him that if he would go over to the canyon, and was disappointed in what he saw, I would give him \$10 to cover the cost of the trip. The next day he came all the way back to Panguitch to thank me for insisting that he see Bryce Canyon." Horace M. Albright, the second Director of the National Park Service, has this to say about Jeffers: "As to Bryce Canyon, I heard of it on my trip in 1917 [to Zion] but could not get over to it. My recollection is, that during the summer LeRoy Jeffers, of the New York Public Library and Secretary of the Associated Mountaineering Clubs of America, who was afterwards killed in Yosemite Park in an airplane accident, also visited Southern Utah in 1917 and saw Bryce Canyon. He wrote an article about it, which appeared in Scientific American early [sic] in 1918 and which caused me to inquire then whether it would not be well to establish a national monument of it. Finding that this canyon was in a national forest I could not go ahead with the monument idea. I did not see Bryce Canyon until 1925." August 4, 1933, Zion History Files.

38. Gregory, cited from "A Geologic and Geographic Sketch of Bryce Canyon National Park," p. 13.

39. I have taken information regarding the Syrett family from the "Biography of Rueben (Ruby) Carlson Syrett and Clara Armeda (Minnie) Excell Syrett," anonymous, typed original loaned to Bryce Canyon by Mr. Lerande Farnsworth in February 1962, p. 10, Bryce Canyon History Files.

40. "Syrett Biography," p. 3.

41. A Panguitch editor, W. J. Peters, was an exception. He became a local booster for Bryce. History of Garfield County, p. 294.

42. Ibid., p. 296. "It was through the persuasion of Dr. W. H. Hopkins of Salt Lake City that he [Ruby] first started taking care of tourists at Bryce Canyon."

43. The State Land Board normally did not work this way. Written permission was granted, or a negative reply was sent to the applicant. The following documents prove that Syrett never had any kind of legal claim to the land on which the Tourists Rest complex was built. On June 18, 1921 Syrett wrote to John T. Oldroyd, State Land Commissioner, stating this position:

Dear Sir:

I am certainly surprised to get your letter of June 14th rejecting my lease at Bryce Canyon.

I wrote you the first of June stating that if you could not see fit to give me the lease as the Land Board had promised me, that is, to put up a three wire fence, that I would accept your offer and build a four wire fence.

You certainly do not know how it will work a hardship on me or you would never do it.

Praying that you will reconsider that proposition, I beg to remain

Resp Yours
R C Syrett (signed)

The letterhead on this piece of correspondence reads: "On the Rim of Bryce Canyon, Utah's Scenic Wonder, Tourists' Rest. Ruby Syrett, Manager." On March 6, 1922, Syrett directed another letter to O. D. Eliason, Chief Clerk of the State Land Board, which reads:

Dear Sir:

In my behalf Dr. W.H. Hopkins of S.L. City called at the commissioners office, but was unable to get an interview so left a letter which was answered on Feb 14th, stating that the commissioner would entertain and offer to lease a portion of the school section on the rim of Bryce Canyon running east & West. Would you please send my blanks, also tell me something of the terms and condition of the lease, so that I might send my application at once. What is the period of time the lease will cover?

Resp.
R C Syrett (signed)

On December 4, 1922, Syrett again wrote to the State Land Commissioner asking for two blank land loan application forms. Source: "Land Board, State Administration. Correspondence SE-24 00.4 SU-TAI 1896-1923. Utah State Archives. A Bill of Sale effected between Syrett and the Los Angeles and Salt Lake Railroad Company on September 25, 1923, makes no mention of land legally entailed by Syrett in the SE1/4 of Section 36, T. 36, R. 4 W., SLM. Only personal property on the school section and water rights located outside the section were purchased by the railroad. Source: Box 1324: Utah Parks, Hotels—Roads," microfilm, Union Pacific Archives, Omaha.

44. "Bill of Sale." September 25, 1923. Box 1324. Union Pacific Archives.

45. It is probably no exaggeration that these tourists included royalty, religious dignitaries and film stars. "Syrett Biography," p. 5.

46. E. A. Sherman, letter to Frank A. Waugh, June 22, 1922. Record Group 95, Records of the Forest Service, 86; Records of the Division of Recreation and Lands, 1906-51. Box 1659, General Correspondence, Dixie and Powell National Forests. National Archives.

47. Ibid.

48. "Recreation Problems in District 4 National Forests." Record Group 95:86. Box 1659.

National Archives. Waugh headed the Division of Horticulture at Massachusetts Agricultural College in Amherst. During the early 1920s he contracted out his services as a recreation engineer to the Forest Service for summer surveys, pp. 8-12.

49. Ibid., pp. 13-14.

50. Albright, memorandum to Chatelain, August 4, 1933, p. 5. Zion History Files.

51. Charles R. Mabey, correspondence. SE-1. 20.4. 1920-21. File: Creation of State Park Commission. Utah State Archives.

52. Alfred Runte's recent article contends that western railroads were the logical source of support for a development of national parks by early conservationists. "Pragmatic Alliance. Western Railroads and the National Parks," The Environmental Journal April 1974, pp. 14-21. This may be true, but the alliance between Union Pacific officials and policy-making National Park Service personnel was always an uneasy one. Forest Service officials in District 4, one of whose primary concerns was to maximize the recreational potential of southwestern Utah, readily accommodated the Union Pacific while Bryce Canyon was a National Monument. After 1928 the National Park Service was not so eager to please.

53. Humphrey, "Notes, Comments, and Letters."

54. Anderson, "Autobiography."

55. "James Bolitho, 90, who piloted the first train into Marysvale on August 7, 1890, will be unable to leave his bed at Rest Haven Home, 2171-5th East, to see the train's final run." Salt Lake Tribune August 27, 1949.

56. Agatha May, interview with Nick Scrattish July 30, 1979. "A Brief Resume of the History of Marysvale." Centennial Edition — "Piute County News." Junction, Utah, June 20, 1947. The depot was closed to the public on December 9, 1963, and demolished shortly thereafter. Irene Elder, "Marysvale history," n.d. unpublished essay. No photographs of the structure are known to exist.

57. Thomas C. Dawson, "Marysvale, The Potash City," The Railroad Red Book, v. 35, January 1918, pp. 276-77.

58. Elder, "Marysvale History."

59. Guena Allen, untitled and unpublished essay regarding the history of Piute County. n.d.

60. "The Denver & Rio Grande Western Railroad Company. Southern Utah and Northern Arizona Tours. Summer Excursion Fares and Automobile Rates. 1922 Season," advertisement, Railroad Collection 513. "Correspondence and Documents," Documentary Resources, State Historical Society of Colorado, Box 20. LeRoy Jeffers considered the Marysvale approach "the simplest" to Bryce Canyon, 1922, The Call of the Mountains, New York: Dodd, Mead, 1922, p. 177.

61. Denver and Rio Grande 1922 season advertisement. Box 20. Railroad Collection 513. Documentary Resources, State Historical Society of Colorado.

62. Union Pacific Archives, Box 1324.

63. Humphrey, "Notes, Comments, and Letters."

64. Railroad Collection 513. Boxes 15 (1915-16) through 23 (1930-35), in various places. Documentary Resources, State Historical Society of Colorado.

65. Union Pacific Archives, Box 1324.

66. This figure includes construction costs for a 32 mile stretch of track from Delta to Fillmore [south-central Utah]. Track laying then cost about \$50,000 per mile. "Utah Construction Program of the U.P. Involves \$5,000,000," The Union Pacific Magazine v. 1, November 1922, p. 15. Also see "The Deseret News," Salt Lake City, October 16, 1922.

67. Union Pacific Archives, August 14, 1922, Box 1324.

68. Union Pacific Archives, September 23, 1921, Box 1324. Four railroads transported passengers to Yellowstone Park. The Northern Pacific detrained tourists at the Gardiner, Montana, station. The Oregon Short Line—a Union Pacific subsidiary—used the West Yellowstone terminal. Both the Burlington Northern and Milwaukee Railroad dropped off passengers at Cody, Wyoming, who then rode busses to the park. In the early 1920s the Northern Pacific commanded approximately 40 percent of this carriage trade; the Oregon Short Line, 35 percent; the Burlington, 15 percent; and the Milwaukee about 10 percent. Estimates furnished by Dr. Berle Clemenson, National Park Service Historian. Interview with Nick Scrattish September 19, 1979. Why the Union Pacific wanted to establish competition between two of its subsidiaries—the Short Line and the Los Angeles and Salt Lake Railroad, which ran through Lund—is beyond the scope of this study.

69. Union Pacific Archives, September 23, 1921, Box 1324.

70. Union Pacific Archives, Box 1324, File 617.2.

71. The Los Angeles "Times" reported that these deposits were "said to be the greatest in the world." September 3, 1922, Cedar City itself was established c. 1831 when Brigham Young sent a company of English and Scottish settlers into the region to mine and manufacture iron. This project was known as the "Iron Mission," and resulted in the first smelter west of the Mississippi. See L. A. Borah, "Utah, carved by winds and waters," National Geographic Magazine, v. 69, May 1936, pp. 577-623.

72. This area of the State is still known as "Utah's Dixie." Cotton was once grown in Cedar City environs, but local agriculture is now publicized for its outstanding peaches.

73. "Columbia Steel Corporation." Appendix G in Building the Iron Mission Park, prospectus directed to the Union Pacific Railroad, Omaha, Nebraska, prepared by the Iron Mission Park Committee, Cedar City, Utah, n.d. (c. 1970-71[?]).

74. "Railroad Seeks Order to Build," Salt Lake Tribune August 12, 1922.

75. Los Angeles Times, September 3, 1922. The Iron County Railroad Company did not withdraw its application before the Utah Public Utilities Commission until mid-October 1922. Both the Interstate Commerce Commission and State agency were involved since construction of the Lund-Cedar City Spur could be legally construed to come under the protection of both interstate and intrastate commerce. Columbia probably did not want to withdraw its application with the State Commission until a definitive agreement had been worked out with Union Pacific. See "U.P. Now Has Open Way to Iron Ore Beds," Salt Lake Tribune, October 17, 1922.

76. "Extract from Minutes of Regular Meeting. Executive Committee, Los Angeles and Salt Lake Railroad Company, August 22, 1922." Box 1324, File 617.2. Union Pacific Archives.

77. "Golden Rail Laying, Cedar City, Utah," The Union Pacific Magazine, v. 2, October 1923, p. 15.
78. "Extract from Minutes of Regular Meeting, Executive Committee, Los Angeles and Salt Lake Railroad Company, August 22, 1922." Box 1324, File 617.2. Union Pacific Archives.
79. "Rails, Roads, Iron and Tourists." Appendix J in Building the Iron Mission Park, Also see Borah, "Utah, carved by winds and waters." esp., p. 579.
80. "Extract from Minutes of Regular Meeting. Executive Committee, Los Angeles and Salt Lake Railroad Company, August 22, 1911." Box 1324. File 617.2. Union Pacific Archives.
81. "Utah Parks Information File." January 1944, Union Pacific Archives.
82. Utah Historic Sites Survey Forms, filed by Fred C. Esplin, July 13, 1971. Utah State Historical Society, Salt Lake City, Utah.
83. "Utah Parks Information File." January 1944.
84. Letter to Mr. Hanchett, March 6, 1922. Box 1324, Union Pacific Archives. Mills was an influential lobbyist who labored indefatigably for conservationist interest. Veterans of Capitol Hill—possibly Mater himself—considered Mills a parasite. He did play a significant role in the establishment of Rocky Mountain National Park. See Robert C. Black's Island in the Rockies, Boulder, Colorado: Pruett, 1969, p. 311.
85. Letter to Hanchett, March 6, 1922. Box 1324. File 617.2, Union Pacific Archives.
86. Telegram. April 25, 1923. Box 1324. File 617.2, Union Pacific Archives.
87. "Articles of Incorporation of Utah Parks Company," p. 2. Box 3649. File 617.2. "Contracts, Conveyances, Permits, Franchises, etc., pertaining to Southern Utah Scenic Facilities and Tourist Traffic." Union Pacific Archives.
88. Ibid., p. 6.
89. Union Pacific Archives, Box 1324.
90. Ibid.
91. Ibid.
92. Smith, office memorandum and attendant documents to Gray, May 4, 1923. Box 1324, Union Pacific Archives.
93. Smith, office memorandum to Gray, May 10, 1923. Box 1324. Union Pacific Archives.
94. Union Pacific Archives, Box 1324.
95. Smith, office memorandum to Gray. Box 1324. Union Pacific Archives.
96. These individuals included: (1) L. B. Hampton, President, Chamber of Commerce; (2) Sam Smith, Assistant Secretary; (3) C. B. Hawley; (4) Frank H. Fisher; and (5) W. R. McKell. Adams to Gray. File A. May 24, 1923. Box 1324. Union Pacific Archives.
97. Smith, telegram to Gray, May 25, 1923. Box 1324. Union Pacific Archives.

98. "Lease from the State of Utah covering lands at Bryce Canyon," pp. 1 and 2. Box 3649. Union Pacific Archives.
99. "Deed from the State of Utah covering lands at Bryce Canyon." Box 3649. Union Pacific Archives.
100. "Patent from the State of Utah covering lands at Bryce Canyon." No. 13696. Box 3649. Union Pacific Archives.
101. "Lease from the State of Utah covering lands at Bryce Canyon." Articles III and IV, pp. 3 and 4, Box 3649. Union Pacific Archives.
102. Ibid. Article IX, p. 5.
103. Patent No. 13696. Box 3649. Union Pacific Archives.
104. Gray to Lovett. September 27, 1923. Box 1324. Union Pacific Archives.
105. Smith, memorandum to Omaha. June 8, 1923. Box 1324. Union Pacific Archives.
106. Smith, telegram to Gray and Adams. September 16, 1923. Box 1324. Union Pacific Archives.
107. Ibid. Also, Gray, office memorandum to Lovett. September 17, 1923. Box 1324. Union Pacific Archives.
108. Gray to Lovett. September 17, 1923. Union Pacific Archives.
109. Smith, telegram to Gray and Adams. September 16, 1923. Box 1324. Gray to Lovett. September 17, 1923. Box 1324. Union Pacific Archives.
110. Gray to Lovett. September 27, 1923. Box 1324. Union Pacific Archives.
111. Union Pacific Archives. Box 1324.
112. Union Pacific Archives. Bill of Sale. September 25, 1923. Box 1324.
113. Union Pacific Archives. Box 1324. October 18, 1923.
114. Union Pacific Archives. Bill of Sale. Box 1324. September 25, 1923.
115. Smith to Gray. October 18, 1923. Box 1324. Union Pacific Archives.
116. Telegram to R. L. Huntley. Box 1324. Union Pacific Archives.
117. "Lease from W. J. Henderson and wife for water from spring on Henderson's property near Bryce Canyon." June 20, 1925. Box 3649. Union Pacific Archives.
118. William C. Tweed, "Parkitecture: A History of Rustic Building Design in the National Park System: 1916-1942." Unpublished manuscript. Chapter III. "The Formative Decade: 1918-1927," p. 44.
119. Haugh, office memo to Gray. "The Park Service has been concerned about the plans for this building [Zion Lodge] and have asked that we secure the services of a competent architect and suggested Mr. Underwood, whose work has met their entire approval." May 2, 1923. Box 1324. Union Pacific Archives.

120. Tweed, "Parkitecture," p. 39.

121. E. E. Adams to Underwood. "It is understood that you will work through our organization in the matter of preparation of detail working plans, but that you will supervise the job from the beginning until completion.

"The agreed upon fee for such services is to be a lump sum of five thousand dollars (\$5,000), plus necessary traveling expenses in connection with this work, it is further understood that after the general design, perspectives, etc., have been completed, that if the project is not carried out, then the fee for services up to that point shall be two thousand dollars (\$2,000) plus necessary traveling expenses." May 1, 1923. Box 1324. Union Pacific Archives.

122. Haugh to Gray. May 2, 1923. Box 1324. Union Pacific Archives.

123. Lancaster, office memorandum to Gray. May 2, 1923. Box 1324. Union Pacific Archives.

124. Lancaster, office memorandum to Gray. May 12, 1923. Box 1324. Union Pacific Archives.

125. Ibid.

126. Lancaster, telegram to Gray. Union Pacific Archives. July 6, 1923. Box 1324.

127. Haugh to Gray. May 2, 1923. Gray to Lancaster. May 11, 1923. Box 1324. Union Pacific Archives.

128. "Preliminary Investigation and Arrangement for beginning work, Utah Parks," p. 5. Lancaster, report to Gray. April 18, 1923. Box 1324. Union Pacific Archives.

129. Ibid., p. 4.

130. Ibid., p. 5, Worthen was well known locally for his enormous hands. Harmon Shakespeare, interview with Nick Scrattish. July 30, 1979.

131. Shakespeare, interview with Nick Scrattish. "Contract" Box 1324. Union Pacific Archives. In the spring of 1923 the saw mill used to prepare lumber for Bryce Lodge was purchased from Leo Barton, Myron Bybee and Archie Adair. Purchasers were R. Syrett, Owen Orton, and Harmon Shakespeare. Subsequent to the purchase the mill was moved to East Creek and reassembled. A 30 H.P. Case tractor engine, No. 33,537, was used to actually saw the wood. East Creek furnished a ready supply of ponderosa (yellow) pine. After the wood had been sized, it was taken up by teams to the future lodge site and stacked. Shakespeare was responsible for sawing lumber, and became proficient at turning out "deluxe slabs." His overseer was Bert Wood. July 30, 1979.

Melford Ahlstrom, interview with Nick Scrattish. Lumber for the lodge came out of East Creek, between Whiteman's Bench and Tropic Reservoir. Ruby Syrett was part owner of the sawmill. Archie Burchanan, a foreman for the Utah Parks Company, was associated with the project. Bert Wood directly supervised the sawmill. July 30, 1979.

132. Lancaster to Gray. April 18, 1923, p. 6. Box 1324. Union Pacific Archives.

133. Ibid, pp. 67.

134. Union Pacific Archives. Box 1324.

135. Union Pacific Archives. Box 1324. July 25, 1923.

136. Ibid. Lancaster to Gray. An additional reason for the use of stone was cited by Lancaster, who once remarked that sand for cement was difficult to find in the vicinity of Bryce Canyon. May 2, 1923. Box 1324. Union Pacific Archives.

137. Union Pacific Archives. Box 1324.

138. Ibid.

139. Ibid.

140. Lovett, telegram to Gray. October 5, 1923.

141. Union Pacific Archives. Box 1324, pp. 2-3.

142. Ibid., p. 3.

143. Ibid., p. 4.

144. Building the Iron Mission Park, p. 10.

145. Smith, telegram to Gray. April 12, 1923. Box 1324. Union Pacific Archives.

146. Ibid. These words are Smith's. It appears he saw the certificate.

147. Arno B. Cammerer, Director, National Park Service. Letter to A. M. Woodbury. October 17, 1933.

148.

149.

150. Smith to Gray. April 12, 1923. Box 1324. Union Pacific Archives.

151. Ibid.

152. The Parrys' Utah and Grand Canyon Transportation Company, which operated from Cedar City and Marysville to the North Rim, was not controlled by the Utah Parks Company until April 1927. "Utah Parks Company," in Motor Coach Age, p. 4. February 1970.

153. "Contract between Utah Parks Company. . .and. . .Parry Brothers, A Co-Partnership. . ." March 4, 1924. Article I, Section 1, "Partnership to Continue Present Transportation Service," p. 2, and Article VI, Section 1, "Sale of Partnership Franchises," p. 14. Box 1324. Union Pacific Archives.

154. Ibid. Article II, Section 4, "Salary," p. 5. Box 1324. Union Pacific Archives.

155. Ibid. Article I, Section 4, "Parks Company to Purchase Certain Motor Equipment from Partnership," p. 3. Box 1324. Union Pacific Archives.

156. "Utah Parks Company," in Motor Coach Age, p. 4.

157. 11. M. Adams to Gray. May 15, 1923. Box 1324. Union Pacific Archives.

158. "Utah Parks Company," in Motor Coach Age, p. 4.

159. Ibid., p. 5.

160. Ibid., p. 6.

161. Gray, telegram to Omaha. "I am opposed to participation in road construction. Believe that it would create a most unfortunate precedent. We will simply have to hold back on Bryce Canyon and Cedar Breaks development until this road question is satisfactorily disposed of." September 19, 1923. Box 1324. Union Pacific Archives.

162. Lancaster to Gray. October 13, 1923. Box 1324. Union Pacific Archives.

163. Ezra C. Knowlton, History of Highway Development in Utah. Reproduction and printing by Utah State Department of Highways. n.d., p. 234.

164. Ibid., Smith to Gray, pp. 208-09. October 24, 1923. Box 1324. Union Pacific Archives.

165. Lancaster to Gray. October 13, 1923. Box 1324. Union Pacific Archives.

166. Ibid.

167. H. M. Adams to Gray. January 18, 1924. Box 1324. Union Pacific Archives.

168. "Summary of Road Development to Southern Utah Parks." Jones to H. M. Adams. April 10, 1924. Box 1324. Union Pacific Archives.

169. This rating implies the road was in a comparatively undeveloped condition. "Comparative Condition of Roads." Assistant Chief Engineer's Office. Oregon Short Line Railroad. January 26, 1922. Mabey correspondence, United States Archives.

170. Jones to H. M. Adams. April 10, 1924. Box 1324. Union Pacific Archives.

171. Jones to H. M. Adams. "Development of Roads to Southern Utah Parks." May 31, 1924. Box 1324. Union Pacific Archives.

172. Ibid.

173. H. M. Adams to Gray. September 14, 1923. Box 1324. Union Pacific Archives.

174. Lancaster to Gray. October 13, 1923. Box 1324. Union Pacific Archives.

175. H. M. Adams to Gray. September 14, 1923.

176. H. M. Adams to Gray. February 12, 1924. Box 1324. Union Pacific Archives.

177. Knowlton, History of Highway Department, p. 245.

178. Lancaster to Gray. October 13, 1923.

179. "When the engineers found that it was impractical to start the tunnel at either end [of the mountain range], they did the next best thing. They started in between, and eventually at five points in between. They erected a scaffold, an eerie looking but perfectly safe scaffold high up the face of the cliff, and started drilling in. When they had got in to the point where the tunnel was to be, as determined by the survey from the footpath, they began boring in either direction from that point, on the tunnel proper. "Then they drilled into the face of the cliff at other points and started similar "headings," as the different sections of a tunnel are called,

and after months of labor all these headings were brought together into a consecutive tunnel, with never more than 3-100 of a foot of variation from where they should be. Presently also—from inside the cliff in both instances—the east and west entrances to the tunnel were opened up." "New Zion-Mount Carmel Road One of World's Great Highways," The Union Pacific Magazine, v. 8. April 1929, pp. 5 and 32. Also see: (1) Borah, "Utah, carved by winds and water," p. 590; (2) Eivind T. Scoyen, interview with Lucy C. Schiefer, January 28, 1971, pp. 6 and 7, Zion History Files; and (3) "The East Rim Road," Zion-Bryce Nature Notes, v. 4, no. 1, April 1932.

180. Speech given by B. J. Finch, District Engineer, U.S.D.A. Bureau of Public Roads, Ogden. Zion-Mount Carmel Highway Dedication. July 4, 1930. Zion History Files.

181. Not everyone agreed the project was a good thing. For a negative view, based on conservationist principles, see Dorr G. Yeager's "Comments on the Impairment of Park Values in Zion National Park," unpublished essay. March 23, 1944. Zion History Files.

182. Smoot's motivation is not clear, but was probably tied to improving Utah's business climate and his chances for reelection. The following statement from Mark Anderson certainly indicates Smoot was no conservationist: "Senator Smoot had little knowledge or interest in public land and conservation problems. I would hesitate to write this about our venerable Senator Smoot without first checking my old files. The record supports my conclusion. . . [Congressman] Don B. Colton was well informed on public land and conservation problems. We could always agree." Anderson to C. C. Anderson, Editor in Charge, "History of Grazing," Utah Writer's Project. January 6, 1941. Forest Service Correspondence. Microfilm A-622. Utah State Historical Society, Salt Lake City, Utah.

183. Yard, The New Zion National Park, p. 26. Legislative summary of Bryce Canyon history from April 22, 1920 to September 11, 1931. Record Group 79:7. 601. Lands (general). Box 842. National Archives.

184. Payne to Smoot. April 22, 1920, correspondence regarding Bryce Canyon's general legislation, April 22, 1920, to March 16, 1942, pp. 52, Record Group 79:7. 101-01. Dedication. Box 840. National Archives.

185. Gregory, "A Geologic and Geographic Sketch of Bryce Canyon National Park," p. 13.

186. General legislation. Record Group 79:7. 101-01. Box 840. National Archives. Legislative summary. Record Group 79:7. 601. Box 842, National Archives.

187. Fall to Smoot. June 16, 1921. General legislation. Record Group 79:7. 101-01. Box 840. National Archives.

188. The Powell National Forest was originally the "East Division" of the Sevier National Forest, established by Presidential Proclamation on October 24, 1903. A consolidation of the Dixie, Sevier, and Powell Forests on July 1, 1919, to June 30, 1922, the eastern edge of the Paunsaugunt Plateau was part of the Powell-Sevier National Forest. President Harding's Executive order, dated February 14, 1922, instructed that the "Sevier" be dropped from Powell-Sevier National Forest, and this was made effective from July 1, 1922. "Powell National Forest," unpublished essay. n.d. Zion History Files. Chapter XXXII: "History of National Forests as Pertaining to Garfield County, Utah," in History of Garfield County, pp. 250-60.

189. Sherman to Waugh. January 3, 1923. "General correspondence, Dixie and Powell National Forests." Record Group 95. Box 1659. National Archives. Secretary Wallace (Agriculture) to Secretary Fall (Interior). April 28, 1923. Boundary extension correspondence,

April 28, 1923, to July 16, 1930, pp. 34. Record Group 79:7, 602-01. Boundary extensions. Box 842. National Archives.

190. Wallace to Fall. April 8, 1923. Record Group 79:7. 60201. Box 842. National Archives.

191. General legislation. Record Group 79:7. 101-01. Box 840. National Archives.

192. Lancaster, telegram to Gray. July 6, 1923. Box 1324. Union Pacific Archives.

193. Congressional Record, April 18, 1924.

194. Ibid.

195. There is no evidence bearings on Senate Bill 668, 68-1, were published in: (1) the Index of Congressional Committee Hearings, (2) the Monthly catalogue of Government Publications, or (3) Congressional Document Catalogue, 1774-1940.

196. A. W. Burney, National Park Service Maintenance, Engineer, report on Bryce Canyon, to F. A. Kittredge, Chief Engineer, National Park Service. October 1, 1927, pp. 22. Record Group 79:7. 631-02. Roads budget. National Archives. Brown's relationship to Maurice Cope, who also worked in Bryce at the time, is unknown.

197. Secretary Wallace, Agriculture, to I. L. Lenroot, Chairman, Committee on Public Lands and Surveys. February 26, 1924. Appendix B, "Public Documents Relating to Legislation (68th Congress)," in History of legislation relating to the National Park System through the 82nd Congress, compiled by Edmund B. Rogers, Denver, 1958.

198. Ibid.

199. Burney report, p. 8. Record Group 79:7. 631-02. National Archives.

200. Wallace to Lenroot. February 24, 1924. Appendix B. History of legislation...through the 82nd Congress.

201. Burney report, p. 2. "Some repairing was done on trails, four new tables built in the automobile camp, and a small amount of lime and creosote purchased for use in the dry toilets." Record Group 79:7 631-02. National Archives.

202. Ibid., p. 3.

203. Ibid., p. 1.

204. Union Pacific Archives. Box 1324.

205. Gray to Lovett, April 13, 1923. Box 1324. Union Pacific Archives.

206. Union Pacific Archives. Box 1324.

207. Union Pacific Archives. Box 1324.

208. Lancaster to Gray, October 13, 1923. Box 1324. Union Pacific Archives.

209. Lodge plans, as well as those for other Utah Parks Company buildings drawn up by Underwood, were sent to the author in August 1979, courtesy of Union Pacific's Engineering and Public Relations Departments, 1416 Dodge Street, Omaha.

210. Ahlstrom and Shakespeare, interviews with Nick Scrattish. July 30, 1979.

211. Burney report, "The main lodge building is substantially constructed of native stone and timber, architecturally pleasing to the eye and generously proportioned." P. 12. Record Group 79:7. 631-02. National Archives.

212. Ibid., p. 12.

213. Shakespeare, interview with Nick Scrattish. July 30, 1979.

214. Burney report, p. 13. National Archives. Record Group 79:7. 631-02.

215. Ibid., p. 13.

216. The Los Angeles and Salt Lake Railroad Company had original title to the buildings at Bryce for obscure corporate reasons. In order to emphasize the Utah Parks Company's role as the exclusive agent of the Union Pacific System in the construction and operation of hotels, camps, and other facilities in Bryce, the September 10, 1928, Bill of Sale was drawn up.

217. H. M. Albright, memorandum for the files, July 9, 1927. Record Group 79:7. 900-02. Part 1. "Bryce Canyon, Public Utility Operators, Utah Parks Company Contracts." Box 209. National Archives.

218. Gray, telegram to Governor George H. Dern, Utah. July 9, 1927. Record Group 79:7. 900-02. Part 1. Box 209. National Archives.

219. Gray, telegram to Dern.

220. Smith, telegram to Albright. Record Group 79:7. 900-02. Part 1. Box 209. National Archives.

221. Ibid. August 12, 1927.

222. Gray, telegram to Dern. July 9, 1927.

223. Record Group 79:7. 900-02. Part 1. Box 209. National Archives.

224. Ibid.

225. Albright, telegram to Director, National Park Service. July 21, 1927. Record Group 79:7. 900-02. Part 1. Box 209. National Archives.

226. Cammerer, memorandum for the Secretary of the Interior. July 21, 1927. Record Group 79:7. 900-02. Part 1. Box 209. National Archives. "In the original Expenditure Program it was proposed to let a contract of approximately \$100,000 for work in Mesa Verde. Surveys and plans have not yet been completed by the Bureau in order that a contract of this size can be let. It is therefore recommended that force account work be authorized at Mesa Verde to the extent of \$50,000, to be done under the direction of Superintendent Nusbaum but a Bureau engineer to be in charge of the work. (paragraph) "Proposed force account work in Yellowstone under Bureau direction will be deferred to permit of the recommended transfer to Zion."

227. "Utah Will Turn Bryce To U.S.," p. 22, Salt Lake Tribune, July 21, 1927.

228. Record Group 79:7. 900-02. Part 1. Box 209. National Archives. The State of Utah did not relinquish mineral rights to Section 36 until 1937. See Record Group 79:7. 605-02. Part 1.

"Bryce Canyon Entries, School Lands." August 17, 1928, to May 26, 1937, p. 45. National Archives.

229. Record Group 79:7. 900-02. Part 1. Box 209. National Archives.

230. When this bill became public law on February 25, 1928, Ebenezer Bryce received the distinction of being the only individual for whom a national park is named. Union Pacific Press Release. April 15, 1952. Union Pacific Archives.

231. The February 25, 1928, Act erroneously described land acquired in Section 20 of T. 36 S., R. 3 W. as "the east half southwest quarter." This was amended in the May 14, 1928, Act to read "the east half and southwest quarter." Unsurveyed Sections 28 and 33 in T. 36 S., R. 3 W., as well as, Section 20 in T. 37 S., R. 3 W. were included in the February 25, 1928, and May 14, 1928, Acts. See Part 1, p. 5 and Appendix A, Senate Bill 1312 and House Report 12487 in History of legislation. . .through the 82nd Congress.

232. Mather, memorandum for Demaray. August 22, 1927. Record Group 79:7. 900-02. Part 1. Box 209. National Archives.

233. Albright to the Director, National Park Service, p. 2. August 1, 1927. Record Group 79:7. 900-02. Part 1. Box 209. National Archives.

234. Legislative summary, p. 3. Record Group 79;7. 601. Box 842. National Archives.

235. Appendix A. History of legislation relating to the National Park System through the 82nd Congress.

236. "Be it enacted by the Senate and House of Representatives of the United States of America in Congress assembled, That for the purpose of preserving in their natural state the outstanding scenic features to the south and west of Bryce Canyon National Park, the President of the United States be, and he is hereby, authorized, upon the joint recommendation of the Secretaries of Interior and of Agriculture, to add to the Bryce Canyon National Park, in the State of Utah, by Executive proclamation, any or all of unsurveyed townships 37 and 38 south, range 4 west, Salt Lake meridian, not now included in said park, and all the lands added to said park pursuant hereto shall be, and are hereby made, subject to all laws, rules, and regulations applicable to and in force in the Bryce Canyon National Park." From House Record 11698 in Appendix A. History of legislation relating to the National Park System through the 82nd Congress.

237. The addition of land actually totaled 7,470 acres.

238. Appendix B in History of legislation relating to the National Park System through the 82nd Congress.

239. Eli F. Taylor, Register, General Land Office, to Marian Frost. September 25, 1930. Record Group 79:7. 609-1. Part 1. "Bryce Canyon Leases (General) Mining Claims." Box 843. National Archives.

240. Maurice Cope, Park Ranger, to E. T. Scoyen, Bryce Canyon/Zion Superintendent. September 29, 1930. Record Group 79:7. 609-1. Part 1. Box 843. National Archives. Frost received a letter from Mary L. Jolley dated November 24, 1930. This he forwarded to Taylor. In the letter Mary Jolley stated she was the purchaser of Frost's interests and had taken possession of the land after paying Frost \$1,000 "cash down." Mrs. Jolley was under the impression the Jolleys had a right to the unsurveyed land, and that Frost would deliver deeds when he obtained them. T. C. Havell, "Settlement claim in national park," to Albright.

January 9, 1931. Record Group 79:7. 609-1, Part 1. Box 843. National Archives.

241. Moskey to Scoyen. October 7, 1930. Record Group 79:7. 6091. Part 1. Box 843. National Archives.

242. Ibid. The letter's context suggests Scoyen came to this conclusion independently of information he received from the General Land office in Salt Lake City. Record Group 79:7. 609-1. Part 1, Box 843. National Archives.

243. "You state that a letter from Frost addressed to the State Land Board, complaining of an order by the Park Service that he move his buildings and improvements from the land, has been referred to your office for answer, and that you have called upon him to furnish corroborated affidavits as to his settlement and the purported transfer of his interest in the land. Nothing of record has been found in regard to the settlement claim and it does not appear that any investigation was ever made to determine its validity." (Paragraph) "You will make report in due course by special letter, showing whether the showing required by you has been made and, if made, you will transmit same to this office for appropriate action." Record Group 79:7. 609-1. Part 1. Box 843. National Archives.

244. Havell to Albright. January 9, 1931. Record Group 79:7. 609-1. Part 1. Box 843. National Archives.

245. Scoyen to National Park Service Director Cammerer. December 17, 1927. Record Group 79:7. 900-1. Part 1. "Bryce Canyon. . .Privileges Grazing." Box 846. National Archives.

246. Harold M. Ratcliff, Forester, "History of Grazing, Bryce Canyon," to Regional Forester. March 18, 1954. Record Group 79. Accession 66-A-691. ACN 3. Federal Record Center 36474. File L3019. Denver Federal Record Center. Also see History of Garfield County, p. 261.

247. See "History of National Forests ad Pertaining to Garfield County, Utah," in History of Garfield County, pp. 250-60.

248. Ratcliff to Regional Forester. March 18, 1954. Record Group 79. Accession 66-A-691.3. 36474. File L3019. Denver Federal Record Center.

249. A History of Garfield County, "The total allowance for 1907 on both the Powell and Sevier was 21,463 cattle and 178,790 sheep. The total allowance for the Powell and Sevier Division. . . in 1940 was 13,933 cattle and horses for 69,730 cow months and 100,050 sheep for 352,438 sheep months. The above shows that the total forage produced per annum has been slowly but surely decreasing." P. 261.

250. Maurice Cope, Bryce Canyon Park Ranger, "Stock Grazing upon our National Parks." Unpublished essay. March 16, 1936. Zion History Files.

251. Acting National Park Service Director Demaray to Scoyen. March 14, 1928. Record Group 79:7. 900-1. Part 1. Box 846. National Archives.

252. Ibid.

253. Ratcliff to Regional Forester. March 18, 1954.

254. History of legislation relating to the National Park System through the 82nd Congress, "Nothing herein shall affect. . . the rights of stockmen to continue to drive stock over the lands now under an existing stock-driveway withdrawal . . ." From Proclamation No. 1952.

Part II.

255. Ratcliff to Regional Forester. March 18, 1954.

256. Ibid.

257. Ibid.

258. Joseph G. Rumburg, Acting Assistant Superintendent, Bryce Canyon, "Corrected Annual Summary of Livestock Grazing. . ." to Paul R. Franke, Superintendent, Bryce Canyon/Zion. January 10, 1956. Record Group 79. Accession 66-A-691.3. 36474. File L3019. Denver Federal Record Center.

259. Ibid.

260. Wayne R. Howe, Acting Superintendent, Bryce Canyon, "Annual Summary of Livestock Grazing. . ." to Regional Director, Region Three. February 8, 1957. Record Group 79. Accession 66-A-691.3. Federal Record Center 36474. File L3019. Denver Federal Record Center.

261. Louis W. Hallock, Superintendent, Bryce Canyon, "Summary of Livestock Grazing. . ." to Regional Director, Southwest Region. January 14, 1963. Record Group 79. Accession 66-A-691.3. 36474. File L3019. Denver Federal Record Center.

262. Bryce Canyon Master Plan, Chapter 1, "Basic Information, The Land," p. 6. "In the spring of 1964, water was piped from Riggs Spring to a tank just outside the park boundary between the mouths of Horse Hollow and Corral Hollow . . ." January 1965. Bryce Canyon History Files.

263. Hallock, "Summary of Livestock Grazing. . ." to Regional Director, Southwest Region. December 17, 1963. Record Group 79. Accession 66-A-691.3. 36474. File L3019. Denver Federal Record Center. Available evidence suggests the Utah Parks Company quit grazing its pack and saddle stock after the 1957 season. Record Group 79. Accession 66-A-691.3. 36474. File L3019. In various places. Denver Federal Record Center.

264. "Bryce at present is a seasonal park, open six to eight months of the year, and must remain so until prospective winter visitation has increased to the point where the expense of snow removal on roads and footpaths becomes justifiable. This situation would make the need for a separate administration all the more difficult to substantiate." P. P. Patraw, Superintendent of Bryce Canyon/Zion. "Memorandum for Associated Civic Clubs of Southern Utah." December 28, 1934. Record Group 79:7. 201. Part 1. "Bryce Canyon Administration and Personnel." Box 840. National Archives.

265. August 1, 1927. Record Group 79:7. 900-02. Box 840. National Archives.

266. "Pursuant to the authority conferred by the Act of Congress approved August 25, 1916 (39 Stat. 535), establishing the National Park Service, as amended June 2, 1920, (41 Stat. 732). . .the "General Regulations" of the rules and regulations for the government of Zion National Park are hereby extended and made applicable in the Bryce Canyon National Park." Signed, John H. Edwards, Assistant Secretary of the Interior. Record Group 48. Records of the Department of Interior. Office of the Secretary. Central Classified Files 1907-36. File 12-1. Part 1. "Bryce Canyon." Box 1989. National Archives.

267. "List of all permanent and temporary departmental appointed positions," fiscal year 1930. Undated. Record Group 79:7. 201-013.2. Part 1. "Bryce Canyon. . .Organization Lists

(Per Annum)." Box 840. National Archives.

268. Vita of Maurice Newton Cope (April 1900 to November 1930) in the Cope Family Papers. A copy of this document and other family papers are now in the possession of the Utah State Historical Society, Salt Lake City, Utah, with the Cope Family's permission.

269. From September 1927 to May 1928 Cope helped build the Mormon Temple in McGill, Nevada. Similarly, from September 1928 to May 1929, he was in the trucking business. Cope Vita. Cope Family Papers.

270. Ibid.

271. Ibid.

272. "Autobiography of Maurice Newton Cope," p. 10. Cope Family Papers.

273. Mrs. Maurice Cope, n'ee Olive De Esta Stewart. Interview with Nick Scrattish. August 30, 1979.

274. Ibid.

275. "Autobiography of Maurice Newton Cope," p. 10.

276. Bryce Canyon Superintendent's Annual Report, 1933, p. 2. 207-01.4. Bryce Canyon History Files.

277. Patraw, memorandum of December 28, 1934. Record Group 79:7. 201. Part 1. Box 840. National Archives.

278. Committee Report, Associated Civic Clubs of Southern Utah. Undated (c. January 1935). Record Group 79:7. 201. Part 1. Box 840. National Archives.

279. Patraw, memorandum of December 28, 1934. Record Group 79:7. 201. Part 1. Box 840. National Archives.

280. These and additional visitation statistics through 1954 were taken from page 5 of Bryce Canyon's Master Plan Developmental Outline, dated March 1955. Record Group 79. Accession 61-A-499. Federal Record Center 745090 ACN 1. "Planning Program (General Correspondence), Bryce Canyon." Denver Federal Record Center.

281. Bryce Canyon, Superintendent's Annual Report, 1941, p. 1. 207-01.4. Bryce Canyon History Files.

282. Eighteen visitors did not enter the park by automobile or bus.

283. Superintendent's Monthly Report, July 1942. Record Group 79. Accession 55-A-269. Federal Record Center 932218. 207-02.3. Denver Federal Record Center.

284. Superintendent's Monthly Report, September 1945. Record Group 79. Accession 55-A-269. 932218. 207-02.3. Denver Federal Record Center.

285. This is not to imply that during the war no consideration was given to the postwar era. As early as August 1944, representatives from Region III's Branch of Plans and Design sketched a "Postwar Rehabilitation Program" for Bryce. After the war nothing came of this proposal. Superintendent's Monthly Reports, August 1944 and May 1945. Record Group 79. Accession 55-A-269. 932218. 207-02.3. Denver Federal Record Center.

286. Record Group 79. Accession 55-A-269. 932218. 207-02.3. Denver Federal Record Center.

287. Ibid.

288. Ibid.

289. Ibid.

290. Apparently, 649 visitors did not enter the park by automobile or bus.

291. The one significant exception was a filling station begun in the summer of 1947. It is discussed in the section on Isolated Construction.

292. Superintendent's Monthly Report, June 1947. Record Group 79. Accession 55-A-269. 932218. 207-02.3. Denver Federal Record Center.

293. Thirty visitors did not enter the park by automobile or bus.

294. Bryce Canyon Monthly Narrative Report, January 1957, pp. 1 and 2. File A2823. Bryce Canyon History Files. "Campground usage increased from 26,045 in 1955 to 27,404 in 1956 or a 5 percent increase." Ibid. I am indebted to Viola B. Rose of the Bryce Canyon administrative staff for locating and making available File A2832.

295. Bryce Canyon, Monthly Narrative Report, June 1954, p. 3. A2823. Bryce Canyon History Files.

296. "New Construction," Bryce Canyon Report 1AL, undated (c. 1954). Bryce Canyon History Files.

297. Bryce Canyon Monthly Narrative Report, June 1954, p. 2. A2823. Bryce Canyon History Files.

298. "Let's Look at Our Parks" by Don Howard. Salt Lake Tribune, July 30, 1955.

299. "MISSION 66 is a Federal Government program, personally sponsored by President Eisenhower in 1956, and passed with welcome bipartisan support by the Congress. It is designed to rehabilitate and improve the public scenic facilities in every area included in the National Park System." Department of Interior Information Service Release for 2:30 p.m., MST, Saturday June 18, 1960. Record Group 79. Accession 66-A-98. Federal Record Center 211620. "Dedication, Bryce Canyon Visitor Center." Denver Federal Record Center.

300. Glen T. Bean, Rocky Mountain Regional Director. Interview with Nick Scrattish and John Albright. August 8, 1979.

301. Ibid. Bean was Assistant Superintendent of Bryce Canyon/Zion until the split. On July 1, 1956, he was promoted to the Superintendent of Bryce Canyon. Bryce Canyon Monthly Narrative Report, July 1956, p. 2. File A2823. Bryce Canyon History Files.

302. Bryce Canyon, Monthly Narrative Report, August 1956, p. 2. File A2823. Bryce Canyon History Files.

303. Bean, interview with Scrattish and Albright, August 8, 1979.

304. "Administrative Independence for Bryce Canyon." Bryce Canyon Report 1AL,

submitted June 26, 1957. File A-26. Bryce Canyon History Files.

305. "Contracts. Bryce Canyon." Article VII., (b). Record Group 79:7. 900-02. Box 209. National Archives.

306. Ibid., Article I.

307. Ibid., Article I. Providing food included the operation of a general merchandise store. Article III. Two subsidiary provisions deserve mention. Park Company employees coming into direct contact with the public were required to wear a uniform or company badge. Article VII., (d). The company was to furnish free accommodations to employees of the Department of Interior, or "other persons visiting [the] Park" who were conducting official government business. Article VII., (f).

308. Ibid., Article II.

309. W. B. Burt Report, p. 41. Record Group 79:7. 204.20. Part 1. Box 840, National Archives.

310. Ibid., p. 35.

311. Ibid., cover sheet.

312. Ibid., p. 16.

313. Ibid., pp. 14-15.

314. Ibid., cover sheet. "Concessionaire operations are in accordance with its contract."

315. Ibid., p. 36.

316. W. H. Hulsiger to G. F. Ashby. Box 3649. Union Pacific Archives.

317. "Utah Parks Company: Facilities." p. 8, April 15, 1945. Box 3649. Union Pacific Archives.

318. "At one time last year I briefly discussed with Mr. Ashby the possible sale of the Utah Parks Company to a corporation or a group financially able to purchase the Utah Parks Company's properties at a figure of approximately \$2,000.000, net. . . When in Los Angeles recently attending the Park Operators meeting, I contacted Joe Minster, Owner and Publisher of the Pacific Coast Record, a hotel magazine. He is also a Hotel Broker. . .Mr. Minster did not believe he would have any difficulty in finding a prospective purchaser for the Utah Parks holdings as he has several parties who are anxious to invest surplus money. Nothing further will be done until I have discussed this with you." W. P. Rogers to W. M. Jeffers, p. 1 (p. 3), May 21, 1945. Box 3649. Union Pacific Archives.

319. Ibid., p. 2.

320. Ibid., p. 2.

321. Ibid., p. 3.

322. Ibid., p. 3.

323. Ibid., p. 3. "Utah Park Company: Facilities," p. 1, May 15, 1945. Box 3649. Union Pacific Archives. The proposal to buy fifteen 29-passenger GMC sightseeing buses at \$9,500

each was first made in this document. These vehicles constituted the backbone of Utah Parks Company's postwar transportation fleet. p. 1.

324. "The Utah Parks Company Camp Center and Lodge continue to serve capacity crowds. With the exception of Mondays and Tuesdays, all accommodations are fill by 5:00 p.m." Superintendent's Monthly Report, June 1947. Record Group 79. Accession 55-A-269. 932218. 207-02.3. Denver Federal Record Center.

325. "Both Bryce Lodge and the Camp Center have operated to capacity since the weather became warm the latter part of the month." Superintendent's Monthly Report, June 1949. Record Group 79. Accession 55-A-269. 932218. 207-02.3. Denver Federal Record Center.

326. "Statement of W. R. Rouse. . . with Respect to National Park Service Policy Towards Park Operators and Their Contracts." July 20, 1949, p. 3 (p. 12). Box 3649. Union Pacific Archives.

327. Following hearings at Denver on November 30 and December 1, 1948, the Act was amended. Thence, paragraph (b) of section 28.5 read as follows: "(1) Until December 31, 1949, no less than one and one-quarter times the regular rate of pay at which the employee is employed shall be paid for all hours worked in excess of 48 per week. (2) From January 1, 1950, to and including December 31, 1951, no less than one and one-half times the regular rate of pay at which the employee is employed shall be paid for all hours worked in excess of 44 per week. (3) On and after January 1, 1952, no less than one and one-half times the regular rate of pay at which the employee is employed shall be paid for all hours worked in excess of 40 per week." Rouse statement, p. 5.

328. Rouse statement, p. 4a.

329. Ibid, p. 6, from "Statement of F. E. Warner. . . ." undated, p. 10. The Warner statement is preserved on microfilm in Box 3649. Union Pacific Archives.

330. Rouse statement, p. 9.

331. Ibid., p. 7, from Warner statement, p. 7.

332. "Union Pacific Attorney Cites Losses in Utah Parks." Salt Lake Tribune, July 29, 1949.

333. Bryce Canyon History Files, File A2823.

334. Union Pacific Press Release for July 19, 1977. Utah Parks Company Information File. Union Pacific Archives.

335. Ibid. The last timetable for this service was April 26, 1970.

336. Tom E. Murray interview with Scrattish, July 12, 1979.

337. "S. Utah Parks May Be In for Facility-Lifting," by Frank Hewlett, Salt Lake Tribune, December 25, 1969.

338. Bryce Canyon, Monthly Narrative Report, July 1964, p. 3. Bryce Canyon History Files. File A2823.

339. From Bryce Canyon Master Plan, Chapter III, section 3. October 1965. Bryce Canyon History Files. Bryce Canyon, Monthly Narrative Report, December 1964. Bryce Canyon History Files, File A2823.

340. Ibid., section 3.

341. Ibid., section f.

342. Ibid.

343. General Host Corp., prime concessionaire in Yellowstone National Park, wants to purchase the Utah Parks Co., and has offered to invest all money made in the southern Utah parks on upgrading the tourist facilities. "S. Utah Parks May Be In for Facility-Lifting." Salt Lake Tribune, December 25, 1969.

344. Murray interview with Scrattish, July 12, 1979.

345. William C. Everhart, The National Park Service (New York: Praeger, 1972), p. 128.

346. Murray interview with Scrattish, July 12, 1979.

347. Union Pacific Press Release, Utah Parks Company Information File, March 10, 1972, Union Pacific Archives.

348. National Park Service Press Release, Utah Parks Company Information File, March 10, 1972. Union Pacific Archives.

349. Ibid.

350. Murray interview with Scrattish, July 12, 1979.

351. The luncheon pavilion and cabins at Cedar Breaks were dismantled in the mid-1970s.

352. Murray interview with Scrattish, July 12, 1979. Murray subsequently became Assistant Manager of Union Pacific's Commissary Services Department until his retirement in 1976. H. H. Noar, Manager of Commissary Service to Marray, February 11, 1976. Utah Parks Company Information File. Union Pacific Archives.

353. Finch to Chief, Bureau of Public Roads. June 4, 1931. Record Group 79:7. 631-2. "Bryce Canyon, Union Construction Co." Box 209. National Archives.

354. John H. Edwards, Assistant Secretary of the Interior, to Union Construction Company July 11, 1931. Record Group 79:7. 631-2. Box 209. National Archives.

355. "The Superintendent and the Assistant Landscape Architect have been instructed to study a possible new road approach from the rear of the Lodge. ." H. M. Albright, National Park Service Director, to T. J. Allen, Bryce Canyon/Zion Superintendent, July 6, 1931. Record Group 79:7, 631-2. Box 209. National Archives.

356. H. K. Bishop, Chief, Division of Construction, Bureau of Public Roads, to A. E. Demaray, Senior Assistant Director, National Park Service, May 31, 1932. Record Group 79:7. 631-2. Box 209. National Archives.

357. Patraw to National Park Service Director, July 14, 1932. Record Group 79:7, 631-2. Box 209. National Archives.

358. "Plans, Route I-B1, Bryce Canyon," photostat. Record Group 79:7, 631-2. Box 209. National Archives.

359. Patraw, telegram to District Engineer, Bureau of Public Roads, August 18, 1932. Record

Group 79:7. 631-2. Box 209. National Archives.

360. Finch, telegram to Patraw, August 18, 1932. Record Group 79:7, 631-2. Box 209. National Archives.

361. Secretary of the Interior to Union Construction Company, undated. Record Group 79:7, 631-2. Box 209. National Archives.

362. "Final Estimate, Contract No. I-1p-1110," undated. 79:7, 631-2. Box 209. National Archives.

363. Ibid.

364. Patraw to National Park Service Director, June 6, 1933. Record Group 79:7, 631-2. Box 209. National Archives.

365. Bryce Canyon Superintendent's Annual Report, 1933, p. 6. 207-01.4, Bryce Canyon History Files.

366. Bryce Canyon, Superintendent's Annual Report, 1934, p. 3. 20702.4, Bryce Canyon History Files.

367. Bryce Canyon, Superintendent's Annual Report, 1935, p. 3. 20702.4. Bryce Canyon History Files.

368. Bryce Canyon History Files, 207-01.4, pp. 34.

369. Ibid.

370. Ibid., p. 4.

371. Bryce Canyon, Superintendent's Annual Report. 1936, pp. 3-4. 207-01.4. Bryce Canyon History Files.

372. Bean interview with Scrattish and Albright, August, 8, 1979. "Design and Construction" in Bryce Canyon, August 1956. File A2823. Bryce Canyon History Files.

373. "Monthly Progress Report" in Bryce Canyon, Monthly Narrative Report, May 1957. File A2823. Bryce Canyon History Files.

374. Ibid. The by-pass received the MISSION 66 designation "NP-BC-3122. "

375. "Design and Construction" and "Monthly Progress Report" in Bryce Canyon, May 1957. File A2823. Bryce Canyon History Files. The park's Monthly Narrative Reports do not include the name of the contracting company for the by-pass.

376. "Monthly Progress Report" in Bryce Canyon, Monthly Narrative Report, June 1957. File A2823. Bryce Canyon History Files.

377. "Monthly Progress Report" in Bryce Canyon, Monthly Narrative Report, August 1957. File A2823. Bryce Canyon History Files.

378. Ibid. "Design and Construction."

379. "Construction" in Bryce Canyon, Monthly Report by Administrative Assistant, September 1958. File A2823. Bryce Canyon History Files.

380. Tweed, "Parkitecture," pp. 58-66, in various places.

381. "Construction" in Bryce Canyon, Superintendent's Annual Report for 1929. 207-01.4, Bryce Canyon History Files.

382. "Construction" in Bryce Canyon, Superintendent's Annual Report for 1930, 207-04.4. Bryce Canyon History Files.

383. Ibid. Extant correspondence (June 18, 1930) from Acting National Park Service Director Demaray to Bryce Canyon/Zion Superintendent Scoyen makes clear the park normally forwarded original tracings for a proposed building to Washington for approval. Upon approval, these were returned to San Francisco, but blue prints were retained in the Washington office. Record Group 79:7, 620. Part 1, "Bryce Canyon Buildings (general)." Box 843. National Archives.

384. "Buildings" in Bryce Canyon, Superintendent's Annual Report for 1932, 207-04.4. Bryce Canyon History Files. The disposition of the messhouse is unknown.

385. Patraw to National Park Service Director, August 8, 1932. Record Group 79:7, 620-01. "Bryce Canyon Buildings Administration Building." Box 843. National Archives.

386. August 13, 1932. Record Group 79:7, 620-01. Box 843. National Archives.

387. Demaray, Senior Assistant National Park Service Director, to Patraw, September 17, 1932. Record Group 79:7, 620-01. Box 843. National Archives.

388. "Public Service Operator" in Bryce Canyon, Superintendent's Annual Report for 1932, 207-01.4. Bryce Canyon History Files.

389. R. O. Jennings, Acting Assistant National Park Service Director, memorandum to Wirth, Demaray, and Cammerer, April 30, 1937. Record Group 79:7, 620. Part 1. Box 843.

390. "Utah Parks Company" in Bryce Canyon, Superintendent's Annual Report for 1938. 207-04.4. Bryce Canyon History Files. National Archives.

391. Richard S. Morris, ed. Encyclopedia of American History. A fund of \$3,300,000,000 was authorized. New York: Harper and Row, 1965, p. 346.

392. Edward A. Nickel, Report on Public Works Building Program National Park Service Branch of Plans and Design Western Division 1933 to 1937. San Francisco: Western Division, National Park Service, 1938, p. 1.

393. Tweed, "Parkitecture," p. 74.

394. Ibid., pp. 74-75. Tweed attributes the term "master plan" to Horace Albright.

395. Tweed, "Parkitecture," p. 75. Report on Public Works Building Program, pp. 2-5.

396. "Public Works" in Bryce Canyon, Superintendent's Annual Report, 1933, 201-01.4. Bryce Canyon History Files.

397. "Public Works" in Bryce Canyon, Superintendent's Annual Report, 1934, 207-01.4. Bryce Canyon History Files.

398. "Physical Improvements" in Bryce Canyon, Superintendent's Annual Report, 1935, 207-

01.4. Bryce Canyon History Files.

399. Caption to photograph of F.P. 8 in Report on Public Works Building Program

400. "Physical Improvements" in Bryce Canyon, Superintendent's Annual Report, 1935, 207-01.4. Bryce Canyon History Files.

401. "Public Works" in Bryce Canyon, Superintendent's Annual Report, 1933, 207-01.4. Bryce Canyon History Files.

402. Caption to photograph of F.P. 9 in Report on Public Works Building Program.

403. "Physical Improvements" in Bryce Canyon, Superintendent's Annual Report, 1935, 207-01.4. Bryce Canyon History Files.

404. "Public Works" in Bryce Canyon, Superintendent's Annual Report, 1933, 207-01.4. Bryce Canyon History Files.

405. "Physical Improvements" in Bryce Canyon, Superintendent's Annual Report, 1935, 207-01.4. Bryce Canyon History Files.

406. Caption to photograph of F.P. 11 in Report on Public Works Building Program.

407. "Public Works" in Bryce Canyon, Superintendent's Annual Report, 1933, 207-01.4. Bryce Canyon History Files.

408. "Public Works" in Bryce Canyon, Superintendent's Annual Report, 1934, 207-01.4. Bryce canyon History Files.

409. "Physical Improvements" in Bryce Canyon, Superintendent's Annual Report, 1935, 207-01.4. Bryce Canyon History Files.

410. Caption to photograph of F.P. 14 in Report on Public Works Building Program.

411. "Physical Improvements" in Bryce Canyon, Superintendent's Annual Report, 1935. Additional Public Works Administration funds, however, were received for a number of miscellaneous physical improvements. A telephone line to Rainbow Point was constructed with allotment F.P. 331, and completed in October 1934. Allotments F.P. 10, 12, and 13 permitted improvements to the water and sewer systems in the public campground. F.P. 15A financed the construction of a cattle guard at the park's north entrance. "Minor Projects (Roads and Trails)." The park's roads and trails similarly benefitted from four allotments during the 1935 fiscal year.

412. "Emergency Conservation Work (ECW)" in Bryce Canyon, Superintendent's Annual Report, 1936. 207-01.4. Bryce Canyon History Files.

413. "Emergency Conservation Work" in Bryce Canyon, Superintendent's Annual Report, 1937. 207-01.4. Bryce Canyon History Files.

414. "Civilian Conservation Corps" in Bryce Canyon, Superintendent's Annual Report, 1940. 207-01.4. Bryce Canyon History Files.

415. "Utah Parks Company" in Bryce Canyon, Superintendent's Annual Report, 1938. 207-01.4. Bryce Canyon History Files.

416. Bryce Canyon, Superintendent's Annual Report, 1941, p. 1. 207-01.4. Bryce Canyon

History Files.

417. Encyclopedia of American History, pp. 350-51.

418. "Emergency Relief Appropriations Act" in Bryce Canyon, Superintendent's Annual Report, 1938. 207-01.4. Bryce Canyon History Files.

419. Bryce Canyon, Superintendent's Annual Report, 1939, p. 2. 207-01.4. Bryce Canyon History Files.

420. "Emergency Relief Appropriations Act" in Bryce Canyon, Superintendent's Annual Report, 1940. 207-01.4. Bryce Canyon History Files.

421. Ibid. The comfort station at Rainbow Point—completed in early September 1940—was not constructed with Emergency Relief Appropriations Act funds. "Contract for the construction of a comfort station at Rainbow Point was approved by the Director's office on June 5 [1940], and construction was started shortly afterward by contractor Harvey Rosenberg of Cedar City, Utah. Funds are provided for this building in the park's annual appropriation."

422. Bryce Canyon, Superintendent's Annual Report, 1941. "Presidential approval of park-sponsored Works Projects Administration project calling for the expenditure of \$77,915 for improvements in Bryce Canyon National Park and Capitol Reef National Monument was received during February 1941." 207-01.4. Bryce Canyon History Files.

423. "Protection" in Bryce Canyon, Superintendent's Annual Report, 1942. "In October 1941, 1382 linear feet of logs which had been cut by a park-sponsored Works Projects Administration crew under permit from the Forest Service, were stolen while still lying in piles on Forest Service land." 207-01.4. Bryce Canyon History Files.

424. John A. Salmond, The Civilian Conservation Corps, 1933-1942, Durham, North Carolina: Duke University Press, 1967, p. 9.

425. Ibid., p. 12. Encyclopedia of American History, p. 342.

426. The Civilian Conservation Corps, p. 12. Encyclopedia of American History, p. 342.

427. The Civilian Conservation Corps, pp. 83-84.

428. Ibid., p. 12.

429. Ibid., p. 87.

430. The Civilian Conservation Corps, p. 84.

431. "Emergency Construction Work," p. 3. Record Group 79. Assession 52-A-100. Federal Record Center 746149. "Resident Landscape Architecture Reports 1929-35." Denver Federal Record Center.

432. Ibid.

433. "Emergency Construction Work" in Bryce Canyon, Superintendent's Annual Report, 1935. Bryce Canyon History Files.

434. "Emergency Construction Work" in Bryce Canyon, Superintendent's Annual Report, 1936. Bryce Canyon History Files.

435. Harlan B. Stephenson, Assistant Landscape Architect, "Report on Landscape Work, Bryce Canyon, Utah," October 1934, p. 1. Record Group 79. Accession 52-A-100. 746149. Denver Federal Record Center.
436. The date was May 13, 1935, "Emergency Construction Work" in Bryce Canyon, Superintendent's Annual Report, 1935. Bryce Canyon History Files.
437. Harry Langley, Resident Landscape Architect, "Report to the Chief Architect. . .," May 1935. Record Group 79. 52-A-100. 746149. Denver Federal Record Center.
438. "Emergency Construction Work" in Bryce Canyon, Superintendent's Annual Report, 1936. Bryce Canyon History Files.
439. A. M. Doerner, Assistant Landscape Architect, "Report on Landscape Work, Bryce Canyon," August 1935. Record Group 79. Accession 52-A-100. 746149. Denver Federal Record Center.
440. Doerner, "Report on Landscape Work, Bryce Canyon," September 1935. Record Group 79. Accession 52-A-100. 746149. Denver Federal Record Center.
441. "Emergency Construction Work" in Bryce Canyon, Superintendent's Annual Report, 1936. Bryce Canyon History Files.
442. "Emergency Construction Work" in Bryce Canyon, Superintendent's Annual Report, 1937. Bryce Canyon History Files.
443. "Forestry and Wildlife" in Bryce Canyon, Superintendent's Annual Report, 1936. Bryce Canyon History Files. Report submitted on September 5, 1936.
444. "Forestry and Wildlife" in Bryce Canyon, Superintendent's Annual Report, 1937. Bryce Canyon History Files.
445. Ibid., "Emergency Construction Work."
446. Zion vault, miscellaneous history files.
447. "Emergency Construction Work" in Bryce Canyon, Superintendent's Annual Report, 1938. Bryce Canyon History Files.
448. Zion vault, miscellaneous history files.
449. "Narrative report for Zion. . . Bryce. . . and Cedar Breaks. . . July 1937. Zion vault.
450. "Narrative report for Camp NP-3," August 1937. Zion vault.
451. The Civilian Conservation Corps, p. 34.
452. "Narrative report for Camp NP-3," September 1937. Zion vault.
453. "Emergency Construction Work," in Bryce Canyon, Superintendent's Annual Report, 1938.
454. Warren's transfer date was July 17. ". . . Narrative Report of Project Superintendent. . . Camp NP-3. . .," July 1938. Record Group 79. Accession 52-A-100. 746149. File 200. "Civilian Conservation Corps, Administration and Personnel, Bryce Canyon." Denver

Federal Record Center.

455. Ibid., Hazzard's transfer data was July 25.

456. Bryce Canyon, "Briefed Annual Report," 1939, Bryce History Files.

457. ". . . Narrative Report. . .Camp NP-3. . .," July 1938.

458. Bryce Canyon, "Briefed Annual Report," 1939.

459. "Civilian Conservation Corps," in Bryce Canyon, Superintendent's Annual Report, 1940.

460. Bryce Canyon, Superintendent's Annual Report, 1940, pp. 6-7.

461. Bryce Canyon, Superintendent's Annual Report, 1941, p. 1.

462. "Civilian Conservation Corps," in Bryce Canyon, Superintendent's Annual Report, 1940.

463. Ibid. "Forest Protection."

464. "Utah" file, Civilian Conservation Corps District Headquarters, Pocatello, Idaho, Record Group 79. Accession 55-A-177. Federal Record Center 62794. Denver Federal Record Center.

465. Unfortunately, there is no information regarding the location of these stub camps.

466. Bryce Canyon, Superintendent's Annual Report, 1941, p. 1.

467. Bryce Canyon, Superintendent's Annual Report, 1942, p. 1.

468. "Construction," in Bryce Canyon, Superintendent's Annual Report, 1931, and "Trails," in Bryce Canyon, Superintendent's Annual Report, 1932.

469. "Construction," in Bryce Canyon, Superintendent's Annual Report, 1931,

470. "Maintenance," in Bryce Canyon, Superintendent's Annual Report, 1932. "Maintenance, Improvement, and Construction," in Bryce Canyon, Superintendent's Annual Report, 1933. "Maintenance," in Bryce Canyon, Superintendent's Annual Report, 1934.

471. "Maintenance" in Bryce Canyon, Superintendent's Annual Reports, 1936 and 1937.

472. "Maintenance," in Bryce Canyon, Superintendent's Annual Report, 1938.

473. "Civilian Conservation Corps," in Bryce Canyon, Superintendent's Annual Report, 1940.

474. The Civilian Conservation Corps, pp. 207, 211-12, 216.

475. M. R. Tillotson, Region III Director, memorandum for Bryce Canyon/Zion Superintendent Franke, August 24, 1942. Record Group 79. Accession 55-A-177. 62794. Group.

476. "Civilian Conservation Corps Property Inventory," September 4, 1942. Record Group 79, Accession 55-A-177. 62794. Bryce Canyon file. Denver Federal Record Center.

477. Tillotson, memorandum for Franke, August 24, 1942.

478. "Civilian Conservation Corps." Record Group 79. Accession 52-A-100. 746150. File 620 "Buildings (general), Bryce." Denver Federal Record Center. "Bryce Canyon" file. Denver Federal Record
479. Ibid.
480. Bryce Canyon, Superintendent's Monthly Report for October 1943. Record Group 79. Accession 55-A-269. 932218. 207-02-3. Denver Federal Record Center.
481. Record Group 79. Accession 55-A-269, 932218. 207-02.3. Denver Federal Record Center.
482. "Monthly Maintenance Report for August 1961 by Maintenance Supervisor to Superintendent, Bryce Canyon/Zion." Monthly Reports, Other. File A2827. Bryce Canyon History Files.
483. "Concessioners," in Bryce Canyon, Superintendent's Monthly Report, June 1947. Record Group 79. Accession 55-A-269. 932218. 207-02.3. Denver Federal Record Center.
484. "Concessioners," in Bryce Canyon, Superintendent's Monthly Report, July 1947. Record Group 79. Accession 55-A-269. 932218. 207-02.3. Denver Federal Record Center.
485. "Concessioners," in Bryce Canyon, Superintendent's Monthly Report, August 1947. Record Group 79. Accession 55-A-269. 932218. 207-02.3. Denver Federal Record Center.
486. Building Number 602 in "Building Inventory, Park Summary," p. 13 (13p.), undated (c. 1972). Bryce Canyon, Administrative Records.
487. Assistant Superintendent Kennedy made this clear to Don Howard in July 1955. "Let's Look at Our Parks," Salt Lake Tribune, July 30, 1955.
488. "New Construction," in Bryce Canyon, Monthly Narrative Report, for August 1957. File A2823. Bryce Canyon History Files.
489. "New Construction," in Bryce Canyon, Monthly Narrative Report, October 1957. File A2823. Bryce Canyon History Files.
490. "Maintenance," in Monthly Report to Park Superintendent from Maintenance Supervisor for June 1961. File A2827. Bryce Canyon History Files.
491. The two-bedroom residence totaled \$19,027, while the apartment building cost \$41,939. "Building Inventory, Park Summary," p. 5.
492. "Design and Construction," Bryce Canyon, Monthly Narrative Report, June 1963. File A2823. Bryce Canyon History Files.
493. "Construction," in Bryce Canyon, Monthly Narrative Report, February 1964. File A2823. Bryce Canyon History Files.
494. Bean, interview with Scrattish and Albright, August 8, 1979.
495. Bryce Canyon, Monthly Narrative Report, September 1956. File A2823. Bryce Canyon History Files.
496. Bean, interview with Scrattish and Albright, August 8, 1979. Bean still feels the visitors center was built in the wrong direction.

497. "Administrative Assistant's Narrative Report to park Superintendent for June 1959." File A2827. Bryce Canyon History Files.
498. "Building Inventory, Park Summary," p.2.
499. "Maintenance Supervisor's Monthly Narrative Report to park Superintendent for June 1960." File A2827.
500. "Building Inventory, Park Summary," p.3. Bryce Canyon History Files.
501. Bryce Canyon, Completion Reports, January 1, 1965, to December 31, 1966. File D2623. Record Group 79. Accession 74-A-16. 10001. Denver Federal Record Center.
502. "Building Inventory, Park Survey," p.3.
503. "Monthly Progress Report," in Bryce Canyon, Monthly Narrative Report, December 1956. File A2823. Bryce Canyon History Files.
504. "Monthly Progress Report," in Bryce Canyon, Monthly Narrative Report, April 1957. File A2823. Bryce Canyon History Files.
505. "Monthly Progress Report," in Bryce Canyon, Monthly Narrative Report, September 1957. File A2823. Bryce History Files. Through August 1957 the amount allotted for this project increased to \$29,495. The park's building inventory (1972) lists the cost of each at \$13,835. "Building Inventory, Park Summary," p. 2.
506. "The comfort station contractor is progressing very well and his workmanship is excellent." "Design and Construction," in Bryce Canyon, Monthly Narrative Report, June 1957.
507. "Building Inventory, Park Summary," p. 2.
508. "Completion Report Narrative." B-10. Bryce Canyon, Completion Reports, January 1, 1965, to December 31, 1966. File D2623. Record Group. Accession 74-A-16. 10001. Denver Federal Record Center.
509. "Completion Report, Numbers M-12 and 17." Bryce Canyon, Completion Reports, January 1, 1955, to December 31, 1966, D2623. Record Group. Accession 74-A-16. 10001. Denver Federal Record Center.
510. Regional Director, memorandum to Superintendent, Bryce Canyon. November 13, 1963. File A9815. Record Group 79. Accession 68-A688. T20513. Denver Federal Record Center.
511. If enough money and time had been available, Glen Bean believes Cecil Doty would have designed rustic buildings for Bryce Canyon. Interview with Scrattish and Albright, August 8, 1979.
512. Tweed, "Parkitecture," pp. 12324.
513. Ibid., p. 127.
514. Bryce Canyon, Superintendent's Monthly Report for July 1945. Record Group 79. Accession 55-A-269. 932218. 207-02.3. Denver Federal Record Center.
515. Regional Director, memorandum to Superintendent, Bryce Canyon, November 13, 1963.

File A9815. Record Group 79. Accession 68-A-688. T20513. Denver Federal Center.

516. "MISSION 66 for Bryce Canyon National Park," prospectus, undated (c. 1957), p. 3 (8p.). "Master Plan" File. Bryce Canyon History Files.

517. Regional Director, memorandum to Superintendent, Bryce Canyon, August 28, 1963, p. 4 (7p.). File A9815. Record Group 79. Accession 68-A-688. T20513. Denver Federal Record Center.

518. Ibid., p. 7. By June 30, 1963, 1,500 feet of these had been constructed at a cost of \$19,715.42.

519. Bean, interview with Scrattish and Albright, August 8, 1979.

<<< [Previous](#)

<<< [Contents](#) >>>

[Next](#) >>>

brca/hrs/hrsn.htm
Last Updated: 25-Aug-2004

Bryce Canyon

Historic Resource Study



BIBLIOGRAPHY

A. PRIMARY SOURCES

1. Institutions

Bryce Canyon, History and Administrative Plans

Information obtained from park files is classified as historical, with the exception of a buildings survey compiled in 1972. The most important collection of documents proved to be the Superintendents' Annual Reports for the years 1929 to 1942 (File 207-03.2). These are invaluable for a detailed understanding of the park's establishment and early operation. The Superintendent's Annual Reports also contain visitation statistics, photographs—and a wealth of information for the road system, rapid construction phase and the Depression-era agencies.

Monthly Narrative Reports (File A2823) for the years 1956 to 1958 contribute data germane to the interrelated themes of Bryce Canyon's movement toward administrative independence from Zion, and the inception of the park's MISSION 66 program. By extension, Monthly Narrative Reports for the early 1960s say much about the recent construction phase. Data peripheral to this issue is also found in File A2827, "other reports." For a time reports were submitted to the Superintendent on a monthly basis by the park's Maintenance Supervisor and Administrative Assistant.

Bryce Canyon's comprehensive and well catalogued photograph collection was canvassed. Many illustrations in the study were taken from it.

Denver Federal Record Center

Accession 66-A-691 contains seminal documents for the history of grazing at Bryce. Superintendent's Monthly Reports for the years 1942 to 1949 (Accession 55-A-269) reveal the character of the war years and the post-war period. The disposition of the park's Civilian Conservation Corps campsite became clear after a perusal of scattered documents in Accessions 52-A-100 and 55-A-177. Both Accessions 66-A-98 and 74-A-16 yielded fragmentary but useful information for a better understanding of the MISSION 66 program.

Denver Public Library, Western History Collection

A near-complete set of The Railroad Red Book, sponsored by the Denver and Rio Grande Western Railroad, is found in the collection—as well as early Bryce Canyon brochures, distributed by the Union Pacific's Publicity Department. The earliest of these dates back to 1925 and includes a map of the region's road system.

National Archives, Washington, D.C.

Record Group 95 furnished enough data to elucidate the role of the Forest Service at Bryce from 1923-28. Record Group 79 was indispensable for the completion of this study. A

detailed legislative summary for the years 1920 to 1942 was a real find. Numerous documents were located for a fuller understanding of; (1) boundary extensions, (2) the character of Bryce Canyon as a national monument, (3) land acquisition, (4) the establishment and early operation of Bryce Canyon, (5) contracts between the Utah Parks Company and the National Park Service, (6) the park's road system, and (7) the rapid construction phase.

Nebraska State Historical Society, Lincoln, Nebraska

A number of photographs were recently donated to the society by the Union Pacific. One set shows Bryce Lodge nearing completion in the spring of 1925. Another contains interior photographs of the lodge, and several dozen snapshots of deluxe cabins under construction at North Rim in the fall of 1927. Photographs from both sets are included in the study.

State Historical Society of Colorado—Denver

Railroad Collection 513 is housed in the Division of Documentary Resources. It contains papers donated to the society by the Denver and Rio Grande Western Railroad. Boxes 15 (1915-16) through 23 (1930-35) were examined to gauge the role of Marysville in the regional development of southwestern Utah. Several illustrations in the study were found in this collection.

Union Pacific Archives, Omaha, Nebraska

Boxes 1324 and 3649 contain several hundred Union Pacific Archives documents on microfilm. Intracorporate correspondence pertaining to Utah Parks Project in the early 1920s characterizes the contents of Box 1324. Four topics in the study were derived from this correspondence; (1) the Lund-Cedar City spur, (2) the Cedar City complex, (3) the National Monument period, and (4) Utah Parks Company's initial construction phase at Bryce. Box 3649 contains invaluable documents regarding the incorporation, operation, and liquidation of the Utah Parks Company.

Union Pacific Archives' "Utah Parks Information File" was canvassed for pertinent press releases. A complete set of The Union Pacific Magazine, is also on file.

Utah State Archives, Salt Lake City

Information for Ruby Syrett's Tourists' Rest complex, and a regional road map dated January 1922 are located in the Charles R. Mabey Correspondence, 1920-22 (SE-1.20.4).

Utah State Historical Society, Salt Lake City

Worthwhile finds: (1) the Iron Mission prospectus, and (2) Mark Anderson's papers on microfilm a-622.

Zion History Files

Several documents used in the study are found in the park's library. The most important of these is Horace Albright's memorandum to Mr. Chatelain, dated August 4, 1933. Narrative Reports for Bryce's Civilian Conservation Corps camp—dated 1937-38—are outstanding documents, whose repository is the park's vault.

2. Interviews

All interviews were conducted by the author unless otherwise noted.

Melford Ahlstrom—July 30, 1979

Glen Bean, National Park Service Regional Director, Rocky Mountain Region, with Nick Scrattish and John Albright—August 8, 1979

Dr. Berle Clemenson—September 19, 1979

Mrs. Maurice Cope—August 30, 1979

Agatha May—July 30, 1979

Tom F. Murray—July 12, 1979

Eivind T. Scoyen, with Lucy C. Schiefer—January 28, 1971. Zion History Files

Harmon Shakespeare—July 30, 1979.

3. Newspapers

Los Angeles "Times," September 3, 1922

"Piute County News" (Junction, Utah), June 20, 1947.

Salt Lake "Tribune," August 25, 1918

_____, August 12, 1922

_____, October 17, 1922

_____, July 21, 1927

_____, July 29, 1949

_____, July 30, 1955

_____, December 25, 1969

"The Arizona Republic" (Phoenix), July 12, 1953

"The Deseret News" (Salt Lake City), October 1922.

4. Unpublished Material

Autobiography

Anderson, Mark. "Autobiography," dated September 2, 1946. Uintah National Forest Correspondence. Utah State Historical Society, Salt Lake City, Utah, microfilm a-622.

Biographies

"Biography of Rueben (Ruby) Carlson Syrett and Clara Armeda (Minnie) Excell Syrett." Bryce Canyon History Files, anonymous. n.d.

Bryce, A. Elnora Family Genealogist. "Biography of Ebenezer Bryce." Assistance of Annie

Larson et al. Bryce Canyon History Files. n.d.

Essays

Ahlstrom, Ole. "The Early Days of Tropic." n.d. Bryce Canyon History Files.

Allen, Guena. Untitled essay re: the history of Piute County. n.d. May Papers.

Bryant, Wayne. "An Introduction to Bryce Canyon National Park." 1947, Zion History Files.

Cope, Maurice. "Stock Grazing upon our National Parks." March 16, 1936. Zion History Files.

Elder, Irene. "Marysvale history." n.d. May Papers.

Hansen, A. J.. "The Village of Tropic." n.d. Bryce Canyon History Files

"Powell National Forest." Anonymous. n.d. Zion History Files.

Yeager, Dorr O. "Comments on the Impairment of Park Values in Zion National Park." March 23, 1944. Zion History Files.

Family Collections

Maurice Newton Cope Family Papers. 1339 Beldon Place, Salt Lake City, Utah.

Agatha May Papers. Circleville, Utah.

Speech

Finch, B. J. Zion-Mt. Carmel Highway Dedication. July 4, 1930. Zion History Files.

Tape

Humphrey, J. W. "Notes, Comments, and Letters." Taped September 1959. Bryce Canyon History Files.

B. SECONDARY WORKS

1. Articles Pamphlets and Papers

Alter, J. Cecil. "The Temple of the Gods," The Improvement Era Vol. 22, no. 5. March 1919.

Belknap, William, Jr. "Nature Carves Fantasies in Bryce Canyon," National Geographic Magazine, Vol. 114, no. 4. October 1958.

Bolton, H. E. "Pageant in the Wilderness," Utah Historical Quarterly, Vol. 18. 1950.

Borah, L. A. "Utah, carved by winds and waters," National Geographic Magazine, Vol. 69. May 1936.

"Bryce Canyon National Park, Utah." U.S. Department of Interior pamphlet. Washington, D.C.: Government Printing Office, 1941.

Dawson, Thomas G. "Marysvale, The Potash City," The Railroad Red Book, Vol. 33. January

1918.

"Golden Rail Laying, Cedar City, Utah," The Union Pacific Magazine, Vol. 2. October 1923.

Gregory, Herbert E. "A Geologic and Geographic Sketch of Bryce Canyon National Park," Zion-Bryce Museum Bulletin, No. 4. March 1940.

_____, "The Geology and Geography of the Paunsaugunt Region, Utah," Geological Survey Professional Paper 226, Washington, D.C.: Government Printing Office, 1951.

Hintze, Lehi F. "Geologic History of Utah," Brigham Young University Geology Studies, Vol. 20, part 3. July 1973.

Howley, Curt B. "Discoverer of Bryce Canyon," The Utah Magazine, Vol. 2, no. 5. 1936.

Jeffers, LeRoy. "The Temple of the Gods in Utah," Scientific American, Vol. 119, no. 14. October 1918.

"New Zion-Mount Cannel Road One of World's Great Highways," The Union Pacific Magazine, Vol. 8. April 1929.

Palmer, William H. "Indian Names in Utah Geography," Utah Historical Quarterly, Vol. 1, no. 1. 1932.

Presnath, Clifford D. "The Legend of Bryce Canyon as Told to the Park Naturalist by Indian Dick," Zion and Bryce Nature Notes, Vol. 8, no. 1. March 1936.

Runte, Alfred. "Pragmatic Alliance. Western Railroads and the National Parks," The Environmental Journal, April 1974.

"The East Rim Road," Zion-Bryce Nature Notes, Vol. 4, no. 1. April 1932.

"Utah Construction Program of U.P. Involves \$5,000,000," The Union Pacific Magazine, Vol. 1. November 1922.

"Utah Parks Co.," Motor Coach Age, February 1970.

"Utah's Fabled Color Country," Sunset Magazine, August 1953.

Woodbury, Angus M., "A History of Southern Utah and Its National Parks," Utah Historical Quarterly, Vol. 12, nos. 3 and 4. July-October 1944. Revised and reprinted, 1950.

2. Books, Monographs, and Prospecti

America's Wonderlands. The Scenic National Parks and Monuments of the United States, Washington, D.C.: The National Geographic Society, 1959.

Black, Robert C. Island in the Rockies, Boulder, Colorado: Pruett, 1969.

Bryce Canyon. Based on original of: John Barnett. Adapted by: Don Follows. Bryce Canyon Natural History Association, 1972.

Bryce Canyon National Park Wonderland of the Pink Cliffs, Bryce Canyon Natural History Association. May 1953.

Building the Iron Mission Park. Prospectus. Iron Mission Park Committee, Cedar City, Utah. n.d.

Buss, Walter R. Bibliography of Utah Geology (to December 31, 1950), University of Utah Press, August 1951.

Chidester, Ida and Eleanor Bruhn. Golden Nuggets of Pioneer Days A History of Garfield County, Garfield County Chapter of the Daughters of Utah Pioneers. 1949.

Congressional Record, April 18, 1924.

Dutton, Clarence H. Geology of the High Plateaus of Utah with Atlas, Washington, D.C.: Government Printing Office, 1880.

_____, Tertiary History of the Grand Canon District with Atlas Washington, D.C.: Government Printing Office, 1882.

_____, Encyclopedia of American History, ed. Richard B. Morris. New York: Harper and Row, 1965.

Everhart, William C. The National Park Service, New York Praeger, 1972.

Grater, Russell K. Grater's Guide to Zion Bryce Canyon Cedar Breaks, Portland, Oregon: Binfords and Mort, 1950.

History of legislation relating to the National Park System through the 82nd Congress, Compiled by Edmund B. Rogers. Denver. 1958.

Jeffers, LeRoy. The Call of the Mountains, New York: Dodd, Mead, 1922.

Knowlton, Ezra. History of Highway Development in Utah. Issued by the Utah State Department of Highways. n.d.

McKee, Edwin D. Ancient Landscapes of the Grand Canyon Region - The Geology of Grand Canyon Zion Bryce Petrified Forest and Painted Desert, 10th ed. Atchinson, Kansas: Lockwood Hazel, 1948. First published in 1931.

Matthew, William Henry. A Guide to the National Parks Their Landscape and Geology, Garden City, New York: Doubleday, 1973.

MISSION 66 for Bryce Canyon National Park, Prospectus. n.d.

Nickel, Edward A. Report on Public Works Building Program National Park Service Branch of Plans and Design. Western Division 1933 to 1937, San Francisco: Western Division, National Park Service, 1938.

Salmond, John A. The Civilian Conservation Corps 1933-1942. Durham, North Carolina: Duke University Press, 1967.

Scoyen, Eivind T. and Frank J. Taylor. The Rainbow Canyons. Foreword by Horace M. Albright. Palo Alto, California: Stanford University Press, 1931.

The Inverted Mountains Canyons of the West, ed. Roderick Peattie. New York: Vanguard, 1948.

Utah. A Guide to the State, Compiled by workers of the Writer's Program of the Works

Progress Administration for the State of Utah. American Guide Series. New York: Hastings House, 1941.

Yard, Robert Sterling. The New Zion National Park Its Relation to the Grand Canyon to the brilliantly colored Plateau Country of Southern Utah, Washington, D.C.: The National Park Association, 1919.

3. Plans National Park Service

"Basic Information: The Land." Chapter 1 in the Master Plan, Bryce Canyon. Office of Resource Planning. San Francisco. January 1965.

"Basic Information: The Land." Chapter 1 in the Master Plan, Bryce Canyon. Office of Resource Planning. San Francisco. August 1967.

"Summary of Archeological Resources and Resource Management Needs for Bryce Canyon National Park." Midwest Archeological Center. Lincoln, Nebraska. June 1978.

4. Unpublished Manuscript


Tweed, William C. "Parkitecture: A History of Rustic Design in the National Park System: 1916-1942."

<<< [Previous](#)


<<< [Contents](#) >>>


[Next](#) >>>




























































































































BRYCE CANYON NATIONAL MONUMENT.

Map to accompany report dated October 1 1927.

Scale 1" = 1/2 Mile



Bryce Canyon

Historic Resource Study



MODERN DISCOVERY



Illustration 1. Ebenezer Bryce and his wife, date unknown. (*Bryce Canyon National Park History Files*)




Illustration 2. Ebenezer Bryce Cabin beside Paria River, probably 1920-1930.
(Bryce Canyon National Park History Files)




Illustration 3. Tourist's Rest, circa 1920-1923. (Colorado Historical Society)

<<< [Previous](#)

<<< [Contents](#) >>>

[Next](#) >>>

Bryce Canyon

Historic Resource Study



REGIONAL DEVELOPMENT (continued)

UNION PACIFIC SYSTEM

The letter from Gray to Lovett, quoted above, is notable in other respects. In it the U. P.'s President explained along general lines how the company intended to develop the scenic attractions of southwestern Utah. Gray also illuminated the underlying justification for what would amount to a massive expenditure of approximately \$5,000,000. [66] The more specific problem of Section 36 in what was soon to become Bryce Canyon National Monument was temporarily ignored.

Gray was convinced that Cedar City, Utah, should be made the hub of the U. P.'s proposed development. This could only be realized if a spur were constructed into Cedar City from the main line, which ran through Lund, Utah, 33 miles to the northwest. Cedar City would require a large, modern hotel. It would also be necessary to construct smaller hotels in Zion and Bryce and a luncheon pavilion in Cedar Breaks. For the time being Gray thought the Union Pacific should not involve itself in the development of the North Rim, given the extremely poor state of the road, via Kanab, which led into this attraction. Roads were also of uneven quality in southwestern Utah, but Gray felt that with the cooperation of State and Federal agencies the most pressing problems could be overcome. The railroad did not want to assume any direct responsibility for the construction or improvement of roads, but did want the exclusive right to transport tourists over them.

President Gray and his closest advisers were thinking big. They wanted to soon advertise a major tourist attraction, whose season lasted at least a month longer than Yellowstone's. They also saw no theoretical reason why a trinity of first-rate attractions, properly developed, managed and advertised, would not rival the annual volume of tourism to Yellowstone. [67] Gray appears to have based his position—in part at least—on earlier information which passed between Basinger and Adams.

This information was in Basinger's September 1921 report to Adams, which described the former's North Rim trip. It included a meaty section on the "Possibility of Tourist Travel" for North Rim and environs. At the time Basinger was convinced the Union Pacific System needed convention sites for Pacific Coast groups that could provide accommodations "early in June and as late as October, to which we are unable to offer Yellowstone Park and the members of which are induced for that reason to use the Santa Fe [to South Rim] or the Canadian Pacific." [68] Basinger also stressed his belief that with proper roads and hotel accommodations at North Rim the Union Pacific could put a dent in the Santa Fe Railroad's South Rim traffic. [69] As noted above, Gray's letter to Lovett, dated August 14, 1922, suggests he gave less credence to this part of Basinger's report.

Lund-Cedar City Spur

On October 24, 1921, President Gray instructed Vice President of Traffic H. N. Adams to direct "quiet investigations," on the part of the Traffic Department, for the purpose of

ascertaining the feasibility of a rail line from Lund to Cedar City. Thereafter, the project moved forward quickly. On February 5, 1922, Gray wrote to H. V. Platt, Manager of the Oregon Short Line. He explained to Platt how Omaha planned to justify the Lund-Cedar City Spur to the company's Executive Committee in New York City. Basically, Gray thought the real potential lay in the excursion business; but, admittedly, this would only be a paying proposition for 3 or 4 months a year. [70] To convince the Executive Committee—and by extension, Union Pacific investors—it would be necessary to offer additional inducements for the spur's construction. These were readily available.

Gigantic deposits of iron ore were believed to exist just northwest of Cedar City. [71] Southwestern Utah had also gained a reputation for the fertility of its arable land. Agronomists had proven that anything, with the exception of citrus fruit, could be grown in this part of the State. [72] Therefore, the promise of a lucrative freight traffic in ore and fresh foodstuffs certainly abetted Gray's argument. The Columbia Steel Corporation, which operated three large plants—one at Ironton, Utah, and the other two in Pittsburg and Torrance, California—had, in fact, recently secured claims to iron ore in the Iron Springs District, 10 miles west of Cedar City. [73] Columbia had no efficient means of transporting its ore from iron Springs to Lund, and so proposed to construct a rail line. In August 1922, Columbia founded a subsidiary for the purpose, whose legal name was the Iron County Railroad Company. [74]

It is coincidental that two independent corporations should have developed a simultaneous interest in a spur from Lund to Cedar City or its environs. It is highly doubtful, however, that the Union Pacific found the situation at all amusing. Action was called for and the Union Pacific took the initiative as was its custom. Columbia wanted access to the main line at Lund, and the Union Pacific wanted to see this access realized, providing the track used was its own. Apparently, Columbia was approached late in the summer of 1922 by Union Pacific representatives and agreed to withdraw its application to the interstate Commerce Commission (I.C.C.) if the Union Pacific would build the Lund-Cedar City Spur, do it quickly, and provide the Iron Springs District ready access to it. During the last week of August 1922 the I.C.C. approved the Union Pacific's petition. [75] This cleared away the first major obstacle for the proposed development of the high plateau country.

The citizens of Cedar City were understandably eager to see the railroad come into their town. Consequently, they readily agreed to conditions imposed by the Union Pacific, which included the following. First, Cedar City was required to furnish the right-of-way from Lund, and guarantee fulfillment by posting a \$50,000 bond, Second, the city was to sell two downtown blocks to the Union Pacific at a cost not to exceed \$45,000. The Citizen's Committee of Cedar City agreed to absorb any amount in excess of this figure. [76] Local cooperation was all the railroad had a right to expect. On June 27, 1923, the first scheduled train into Cedar City from Lund arrived, bearing President Warren C. Harding and his entourage. A few weeks later, on September 12 the completion of the Lund-Cedar City Spur was officially celebrated by the laying of a "golden rail." [77]

Cedar City Complex

The third and final condition imposed on Cedar City by the Union Pacific involved what was to become the core building in the railroad's Cedar City Complex. [78] In 1918 the townspeople had begun the construction of a large hotel. From its onset the project was badly under-financed, and by the summer of 1922 the hotel was only half completed. [79] Omaha wanted to purchase the building for estimated costs expended on it, less interest. This sum amounted to \$77,597.14, and the railroad assumed it would take another \$100,000 to open the hotel. [80] Actually, this estimate was only about 50 percent of what the Union Pacific poured into the structure, but it was ready for business late in 1923. [81] The hotel was

named "El Escalante" in honor of Friar Escalante who had traversed the region in 1776 (see Modern Discovery, Expeditions to the Bryce Canyon Region).

Construction of the Cedar City depot was accomplished during the first 6 months of 1923. George Albert "Bert" Wood, a Cedar City contractor, did the work. He was also responsible for completing the Escalante Hotel and later participated in building the Utah Parks Lodges. The depot was rounded out in 1929 when a patio and bus shelter were added to its south and east sides. [82] Between 1925-29 the completion of four buildings augmented the complex. These were the West Garage (1925), Chauffer's Lodge (1926), Machine Shop (1928), and Commissary Building (1929). [83]

Incorporation of Utah Parks Company

Omaha's decision to go ahead with the Cedar City Complex carried with it the realization that sooner or later the railroad would need to conclude long-term concession agreements with the National Park Service. Director Mather of the National Park Service made it clear to Union Pacific as early as March 1922 that he thought the railroad should operate in the Cedar City region as two separate companies. One should take the responsibility for transportation and related services, the other for hotels and camps. Mather suggested that transportation be handled as an extension of the railroad—and hotels and camps by "Utah people," with the financial backing of the railroads.

Mather knew well the political climate in Washington, D. C., and was particularly concerned about Enos Mills' agitation against what Mather called "so-called monopolies" in the national parks. [84] Members of the Appropriation Committee for the Interior Department who had visited the parks were generally pleased with cooperation between western railroads and the Park Service; but, Mather sensed that constant agitation could raise questions in the minds of constituents, and put unwanted pressure on friendly politicians. [85] Mather's message to the Union Pacific was clear: why needlessly antagonize these politicians? Omaha was essentially forced to concur with Mather's position.

There were also secondary reasons why the formation of a separate corporation for concessions made sense to the railroad. For one thing it would limit legal responsibility, and as Gray once remarked to Lovett "a great railroad is much more subject to attack in such matters than a smaller and independent corporation." Additionally, Gray felt a separate corporation, dealing on a day to day basis with a well-heeled, discriminating, carriage trade, would "avoid compromising [the] railroad in the thousand and one little elements of dissatisfaction arising in [the] operation of hotels." [86]

Articles of incorporation for the "Utah Parks Company" (UPC) were drawn up in Salt Lake City on March 26, 1923, antedating by several months the opening of the Escalante Hotel in Cedar City. Article V established the UPC's responsibility, not only for a wide range of tourist accommodations, but for transportation facilities as well:

The business of this corporation . . . shall be as follows to own, lease, operate and maintain automobiles, automobile busses, trucks and other self propelled vehicles and to establish, maintain, operate and conduct a general automobile, livery, and garage business and service including the hiring out of automobiles of any and all kinds, and the care, repair, maintenance supply thereof, together with the necessary buildings, shops, service stations, and other facilities necessary or incident thereto . . . [87]

The Railroad Securities Company of New Jersey, a Union Pacific subsidiary, subscribed 98 percent of the Utah Parks Company's capital stock. High officials of the railroad assumed key positions in the new company. Gray became the Utah Parks Company's President and H. M.

Adams the Vice President. Both E. S. Calvin, Union Pacific's Vice President of Operations, and George H. Smith, General Counsel for the Union Pacific System, became Utah Parks Company Directors. [88]

Section 36, Bryce Canyon

In August 1922 Union Pacific's President, Carl B. Gray, was willing to temporarily ignore the problems posed by Section 36 in soon-to-be Bryce Canyon National Monument, but not for very long. Intensive negotiations with the State of Utah were opened in April 1923. Gray telegraphed Governor Mabey on April 19 proposing that the railroad buy the 30 acres along the Plateau rim and sign a 25-year lease for the remainder of the section. Gray made it perfectly clear to Mabey that the Union Pacific was willing to agree to certain limitations on the lease. Gray emphasized that Section 36 would never be closed to the public. Areas for parking and camping would be set aside by the railroad for the State's use, at no charge to either the general public or State. [89]

Ten days later Gray telegraphed George Smith, informing him precisely what it was the railroad wanted:

We want to acquire the southeast quarter of the southeast quarter of section thirty six, township thirty six south, range four west, and will want to lease the balance of this section for the term of twenty five years with right for an additional twenty five years as provided in special statute. You are authorized to make formal application in behalf of the corporation Utah Parks Company. Will want this transaction to include understanding that we may, presently or later, transfer this property and leasehold to Los Angeles & Salt Lake Railroad Company or Union Pacific Railroad Company if we desire. [90]

Smith did as he was instructed on May 3, 1923, making formal application in the name of the Utah Parks Company with John T. Oldroyd, the State Land Commissioner. [91] The next day Smith sent Gray a copy of the application to Oldroyd. He noted that the Land Board had classified the section as grazing land, appraised at \$2.50 per acre with a lease value of 25 cents per acre. It was Smith's impression that Oldroyd was indifferent to the railroad's proposal. On the morning of May 4 Oldroyd told Smith that the State wanted a much larger sum for the land. Smith had inferred from this that the Land Board would immediately reclassify and reappraise Section 36, so as to conclude the most advantageous bargain. [92]

Subsequently, Gray and Smith began to learn that the State was not merely interested in money. About May 10, State Senator Lunt, a member of the State Road Commission, informed Smith that State authorities feared the railroad would eventually exclude the general, nonpaying public from Section 36. Lunt himself favored an outright sale of all or part of the section to the Union Pacific but indicated to Smith that his hands were tied. [93]

At this stage of the negotiations Gray became exasperated. On May 14 he wired Smith that the Union Pacific would not be forced in the matter:

We will neither pay an excessive price and rentals nor will we take any other land than that we have decided upon, and if the matter is delayed and the hotels not constructed, the responsibility will have to rest where it belongs, which would certainly not be with us... [94]

Arbitration between the two parties reached its lowest point on May 16, when Smith, accompanied by Union Pacific System Park Engineer S. L. Lancaster, met with Oldroyd. Smith first tried to schedule a meeting at Bryce Canyon between Governor Mabey, interested State officials, and representatives from the railroad. This meeting appears to have taken

place about the beginning of June, but it was probably not because of any effort Oldroyd made. In fact, during the May 16 meeting Oldroyd became flippant and at one point laughingly remarked to Smith and Lancaster that he, Oldroyd, had received suggestions that land in Section 36 be sold for \$500 an acre, or as much as \$100,000 for a 40-acre tract. Even at this price Oldroyd was insistent the State would never relinquish title to the southeast corner of Section 36, but would want the railroad to take its 40 acres "farther back." [95] Smith must have left this meeting clenching his fists.

During the next few days several influential members of the Salt Lake Chamber of Commerce and Commercial Club actively came to the railroad's support. [96] On May 26 the Board of Governors of the Commercial Club met with Mabey and Oldroyd. [97] These businessmen do not appear to have completely carried the day, but were likely instrumental in scaling down the State's demands. Unfortunately, no record is known to exist of what transpired between June and September. Gray's September 27 correspondence to Lovett as well as a lease, deed, and patent from the State, dated September 8 and 10; however, do spell out the compromise solution reached between the State and railroad.

Omaha, in the name of the Utah Parks Company, was granted a lease on 618.39 acres of Section 36—said lease to begin on January 1, 1923, and run for 25 years at \$2 per acre per year. An option for an extension of 25 years was written into the lease. Leased land comprised the following parcels: (1) W1/2; (2) NE1/4; (3) W1/2 of SE1/4; (4) NE1/4 of the SE1/4; and (5) beginning at the SE corner of the SE1/4 of the SE1/4, running W 1320 feet, then N 970 feet, then E 970 feet, then N 970 feet, then E 350 feet, then S 1320 feet to the SE corner (18.39 acres). [98] The 18.39 acre parcel in the SE1/4 of the SE1/4 was deeded back to the State "for the support of the common schools of the grantee." [99] The 21.69 actually sold to the railroad, cost \$540.25, that is \$25 per acres. [100]

Both parties could be justifiably satisfied with the settlement. For its part, the Union Pacific now effectively commanded the situation at Bryce Canyon. An outlay of several hundred dollars was indeed a modest price to pay for this first rate opportunity. The annual lease fee was negligible. On the other hand, the State of Utah could claim its servants had carefully considered the situation, and what was done had been done for the long-term welfare of the State's citizens. Numerous conditions attached to the settlement do make clear that Omaha did plenty of compromising. The Union Pacific was required to provide ample space (as much as 40 acres) for public camping, and relinquish a right of way for a public road to the campground. [101] No timber could be cut on leased land without the States permission. [102] The State retained all mineral rights on the 21.69 acre plot it sold to the railroad. [103]

Syrett Camp

A more informal condition imposed by Salt Lake obligated the Union Pacific to reach "an amicable settlement with B. Syrett." [104] Omaha viewed this as a necessity anyway, since Syrett had filed on the closest water supplies to the SE corner of Section 36. It was also apparent to Smith that Syrett was well regarded in Mormon settlements near Bryce Canyon. It would make no sense to incur Syrett's enmity, and risk poisoning relations with the local populace. Smith accordingly opened negotiations with Syrett during the first week of June 1923. The Union Pacific offered to loan Syrett \$2,500 at 6 percent interest, for the purpose of paying off debts Syrett had incurred to improve Tourists' Rest. Syrett would be allowed to operate Tourists' Rest until the Bryce Lodge was ready for occupancy. He would then be moved, at the railroad's expense, to another location within the SE 1/4 of Section 36, and issued a 5-year lease—presumably for the purpose of catering to motorists. In return for Syrett's assignment of water rights in Section 16, T. 37 S., the Union Pacific agreed to furnish Syrett's camp with free water "for such period of the year as the water supply is available." No concessions, such as the saddle horse operation, were offered to Syrett. [105]

Smith's proposal was pretty tight-fisted and Syrett likely saw it that way. Ruby thus attempted to use the State Land Commission as an intermediary, for the purpose of securing a better deal. Land Commissioner Oldroyd was not a personal friend of Syrett, but was prone to side with a fellow Utahn, especially one pitted against a powerful out-of-State corporation. Syrett presented the State Land Commission an inventory of property, valued by himself, at \$15,500, inclusive of water rights. Howard Mann, a Union Pacific engineer, valued Syrett's property at \$7,360, exclusive of water rights. [106] Smith was reluctantly drawn in. He proposed the sum of \$9,000 as a fair offer, subject to Gray's approval. [107] Syrett had successfully managed to raise the ante in his favor, and decided to horse-trade for all the situation was worth.

Late in September a series of offers and counter-offers resulted in the Union Pacific's willingness to pay Syrett \$10,000 for the latter's property and water rights. [108] Actually, the company was under pressure. Oldroyd, backed by State law, was withholding patent to land the railroad had purchased until either the company settled with Syrett, or deposited an amount with the Land Commission equal to the value of Syrett's improvements, as assessed by the State. The Union Pacific could resort to the latter method of settlement, but this would take time, and—more importantly—would not solve the water rights question. [109] Gray also had information from an unnamed source that the National Park Service had made an attempt to discourage Governor Mabey from facilitating the sale to the Union Pacific of any property. [110] Gray inferred from this that the National Park Service assumed Section 36 might someday be incorporated into a national park.

Syrett, too, may have been under some pressure to conclude agreement. He was in debt for improvements to Tourists' Rest, and it may be that the Panguitch bank wanted the debt liquidated. At any rate, a Bill of Sale concluded on September 25, 1923, settled the issue. Ruby and Minnie Syrett received \$10,000 for enumerated property situated in the SE1/4 of the SE1/4 of Section 36, and water rights they held outside the section. [111] The Los Angeles and Salt Lake Railroad Company (L.A. & S.L. R.R.) acted on behalf of the Union Pacific System.

Water Supply for Section 35

Syrett's water rights, as assigned to the Union Pacific System on September 25, 1923, consisted of Hopkins Spring and Shaker Springs—sometimes referred to as Weather Springs. Syrett's application to the State Engineer for Hopkins Springs was approved on January 9, 1923, bearing registration No. 8888. [112] Union Pacific Attorney George Smith noted that Hopkins Spring was located adjacent to Syrett's Tourists' Rest complex and informed Gray the spring did not amount to much. [113] Syrett's application for Shaker Springs was approved on June 25, 1923, and bore registration No. 9221. [114] Shaker Springs was located approximately 4-1/2 miles northeast of the proposed site for Bryce Canyon Lodge in Section 16, T. 37 S. It was considerably larger than Hopkins Spring and was the main reason the railroad wanted to buy out Syrett's water rights. When Syrett applied for Shaker Springs he probably intended to cover another spring in the immediate vicinity. Nevertheless, his description was defective, and Omaha thought questions might arise as to the claim's validity. The L.A. & S.L. R.R. thus made an independent filing on the spring to avoid future complications. [115]

On October 18, 1923, Union Pacific Resident Engineer, H. C. Mann, informed the Los Angeles office of the L.A. & S.L. R.R. that it would be necessary "to do some work" before December 31, in order to hold the water filing at Bryce. It appears Mann was referring to Hopkins Spring alone. Smith and Mann conferred on this issue, which implies the improvements were for the purpose of conforming to State law. Smith recommended that excavations be made for a head box around the spring. It would then be necessary to build

forms and fill them with concrete or stone mortared into place. Smith estimated the project to cost between \$500 and \$1,000. On account of Bryce Canyon's severe winter climate, Smith said work should begin as soon as possible. [116] It must be assumed the project was completed late in the fall of 1923.

There is every reason to believe Union Pacific employees directly involved with the Bryce Canyon Lodge project were uneasy with the water supply acquired from Syrett. Consequently, additional sources of potable water were energetically sought after. In June 1925 the Union Pacific System, in the name of the L.A. & S.L. R.R., concluded a 25 year lease with W. J. and Elizabeth W. Henderson. For \$50 per annum, the railroad acquired the use of a spring in the W 1/2 of Section 34, T. 36 S., whose rate of flow was gauged at 0.16 second feet of water, i.e., over 100,000 gallons per day. The lessor agreed to permit the use of sufficient land in the W 1/2 of Section 34 for the construction and maintenance of a pumphouse and pipeline. [117] Having concluded the Henderson Lease, the Union Pacific probably evaluated its water supply as adequate for years to come.

Reconnaissance for Bryce Canyon Lodge

Union Pacific's intent to construct major buildings in Zion National Park, Bryce Canyon, and Cedar Breaks made it necessary for the company to secure the services of a competent architect. During the early spring of 1923 National Park Service Landscape Architect Daniel P. Hull worked closely with an architect named Gilbert Stanley Underwood on the Yosemite Village project. Notwithstanding Underwood's limited success on the project, Hull was impressed with Underwood, [118] and undoubtedly recommended him to the Union Pacific System for use of the development of the Utah parks. [119]

Underwood, who had opened an office in Los Angeles in January 1923, [120] was invited to come to Omaha. On the morning of May 1, 1923, he met with S. S. Adams and J. L. Haugh, Executive Assistants to President Gray. Adams and Haugh hired Underwood to plan the Zion Lodge. [121] They also asked Underwood to go over to Bryce Canyon and "look it over and make some suggestions." [122] It was understood that if the railroad was pleased with the results of Underwood's Zion project, he would shortly receive similar commissions. The next day Underwood started for Utah, accompanied by Union Pacific Park Engineer S. L. Lancaster and Randall L. Jones, the Union Pacific System's key liaison man in the Cedar City area. Enroute, Daniel Hull joined the group in Cheyenne. [123]

Underwood and the others arrived in Cedar City on the afternoon of May 4. They spent the night in Cedar City, then went on to Zion and spent the entire day there. The next morning, Sunday, May 5, 1923, the group departed for Bryce, and in Lancaster's words arrived there "in time to see the effect of the beautiful Sun Set." [124] Architect Underwood's first involvement with Bryce Canyon then, was on the Monday morning of May 6, 1923. He confined his efforts to the selection of a suitable site for the lodge. It appears that Underwood was made aware of the fact the plateau rim would likely be off-limits as a construction site. For this and less well known reasons, a site was chosen back away from the rim, yet close enough to make it readily accessible to lodge guests.

Lancaster was scheduled to meet Underwood in Los Angeles on May 21, 1923. [125] At that time the two presumably went over Underwood's preliminary sketches for Zion Lodge, and may have exchanged a few words regarding the proposed structures for Bryce Canyon and Cedar Breaks. Underwood and Lancaster did not meet again until early in July. [126] This conference—involving Underwood, Lancaster, and Hull—centered on Zion Lodge. During the working season of 1923 Architect Underwood's work at Bryce Canyon can be characterized as nothing more than reconnaissance.

Construction Program's Organization

During May 1923, with everything in a state of flux, the Union Pacific began to assemble and organize key personnel in its ad hoc construction team for the Utah parks. Howard C. Mann, a veteran Resident Engineer in the Union Pacific System, was transferred from the Columbia River bridge project to an office in Cedar City. He assumed a role as the principal technical figure in the entire Utah parks construction program. Mann was expected to handle estimates and expenditures, construction routines, and individual project organization. Samuel C. Lancaster, Union Pacific's roving Park Engineer, reported to Mann. Lancaster was responsible for choosing building sites and for landscaping. It would be his additional task to work with the National Park Service, Forest Service, and County and State Road Commissions regarding road work. Randall L. Jones had two primary responsibilities. He would be depended upon to secure local laborers and craftsmen. He was also to assist Mann as a supervisory architect. Jones, like Lancaster, reported directly to Mann. [127] As a team Mann, Lancaster, and Jones were destined to successfully inaugurate Union Pacific's major construction program for the Utah parks. The erection of all buildings in Bryce Canyon's "initial" building phase, between 1924-29, can be attributed to their efforts.

Materials for Bryce Lodge

As early as March 27, 1923, Lancaster sent Randall Jones to Bryce Canyon to investigate the possibilities of using local timber and rock for the construction of Bryce Lodge. [128] On March 29 Lancaster returned to Cedar City from St. George and made arrangements with the Forest Service for cutting timber to be used in the lodge's framework. The Forest Service charged \$475 for this privilege. [129] Two days earlier Jones had contacted Charles Church and Fred Worthen to quarry suitable stone. For the sum of \$143.65, Church and Worthen furnished 12 men and the necessary teams to haul stone. These men would be split into two 6-man gangs, with Church and Worthen acting in a dual capacity as foremen and powdermen. A quarry site was selected within 1-1/2 miles of the lodge site. Men were paid \$3.20 per day, the foremen \$5. [130]

Lancaster planned to accumulate lumber by means of a contract with Ruby Syrett and Owen Orton, dated March 30, 1923. These men were to provide 200,000 board feet of lumber at \$27.50 per 1,000 feet. The contract also stipulated that as many slabs as needed for the lodge's construction be provided at 5 cents per linear foot. Each side of an individual slab had to be 1 foot wide, with its sides and ends squared. Syrett and Orton were to harvest all trees on National Forest land and agreed to have lumber and slabs properly piled on the lodge construction site by July 15, 1923. [131]

Lancaster justified these preliminary expenditures to Gray by explaining that construction during the 1924 working season could not proceed without properly seasoned timber. [132] Naturally, no timber could be used until the basement and foundations had been laid in stone. Lancaster estimated that shipping timber from the Northwest would add \$20,000 to \$30,000 to the cost of buildings proposed for Bryce Canyon and Cedar Breaks. He insisted that the best way to save money was to employ local people. This labor force could erect the lodge up to the laying of floors, the installation of plumbing, and the application of finished work. [133]

For some time Union Pacific's Executive Committee in New York was at pains to understand why Lancaster proposed to use so much stone in the Lodge's construction. On June 21 Lovett remarked to Gray that:

. . . stone-cutters are among the highest paid class of workmen and, furthermore, are not very plentiful . . . I confess it is rather hard for me to believe that

attractive hotels can be built with stone at less expense than with lumber grown in abundance on our own lines no matter where the stone is found . . . [134]

In subsequent correspondence Gray pointed out to Lovett, and the rest of the Executive Committee, that the Utah parks buildings would be built "in the interior, far from the railroad." [135] Hauling lumber into Bryce by truck from Cedar City would also entail large expenses. Perhaps Gray's most persuasive argument was that stone work could be done at Bryce Canyon for 40 cents an hour. [136] Lovett, at least, was convinced and on July 30 communicated to Gray: "There is, of course, no doubt under the facts stated by you that the stone should be used in building these hotels." [137]

A few days earlier, in a progress report, dated July 15, 1923, Gray had told Lovett the foundation stone for Bryce Lodge was in the process of being quarried:

The stone is of such a nature that it breaks out from the quarry in the shape required for laying in the walls and it will not be necessary in any case to use a stone cutter upon it. The stone is to be laid up in a rough rustic style in cement and mortar, and can be done with the same common labor that is used for quarrying it. [138]

Gray further explained that timber at Bryce Canyon had proven to be of inferior quality—not at all suitable for the lodge's exterior finishing. Milling the requisite amount of lumber was slow because of the trees' small size. Gray figured the lodge's walls would be built up to the snowline with stone, above that with timber. He concluded by stating that actual construction would not begin until the spring of 1924 principally because of the area's poor roads. [139]

During a meeting of the Executive Committee, held in the first week of October, F. A. Vanderlip took an extremely negative view of the entire Utah parks venture. Vanderlip centered his criticism on two issues: the expense of individual buildings, Bryce Lodge among them, and what he termed the wretched condition of regional roads. [140] Lovett, himself, could not dismiss this criticism and asked Gray to fully advise him of the situation. Gray's reply to Lovett on October 6 was masterful and shows the President intended to stand firm during this period of crisis over the Utah parks program.

Gray adequately justified expenditures for rough materials. He explained that it was necessary to take good advantage of weather conditions. If the railroad decided not to build the lodge, this material could be used for the construction of camps. Gray emphasized his disagreement with Vanderlip's objection to the construction of lodges in Zion and Bryce Canyon. Gray cited that Omaha's Traffic Department had assessed that with camps alone the Union Pacific would be restricted to a "secondary class of travel." [141] This implied the railroad would not be able to secure any of the convention traffic, which then represented a significant percentage of rail traffic to Yellowstone and Glacier National Parks. The proposed return on camps alone also failed to justify a major advertising campaign for the Utah parks—a campaign considered absolutely necessary if the Union Pacific hoped to effectively compete with the first-class hotel accommodations available at Yellowstone, Glacier, and the South Rim of the Grand Canyon. [142] Gray did not ignore Vanderlip's remark about roads. He assured Lovett that Omaha's final decision to go ahead with development in Zion, Bryce Canyon, and Cedar Breaks was predicated on proper roads "and our [i.e. Omaha's] determination in this last respect has been very emphatically stated." [143]

Transportation Franchise

From early on Union Pacific officials were eager to launch a concerted effort for better roads in southwestern Utah. Yet, logic dictated that Omaha first secure the exclusive right to transport tourists in the area, and this meant dealing with the Parry brothers. Chauncey and

Gronway Parry pioneered the tourist transportation industry in southwestern Utah and northwestern Arizona. [144] At an unknown date, the brothers had secured a certificate of convenience and necessity from the Public Utilities Commission of Utah. [145] This entitled them to operate a touring service to all scenic attractions within the State of Utah, but "with limitation as to time." [146] In the spring of 1917, William W. Wylie, his brother, Clinton W. Wylie, and the Parry brothers incorporated the National Park Transportation and Camping Company, [147] whose title changed shortly thereafter to the Zion National Park Company. [148] The National Park Service granted this company the exclusive privilege to maintain tourist camps in Zion, and to provide a tourist transportation service in and out of the park. The contract was finalized on September 6, 1917, but made the company's privilege retroactive to January 1, 1917. [149] In February 1922 a Memorandum of Agreement was drafted and signed by both parties, extending the Zion National Park Company's concession privileges for an additional year, to January 1, 1923. [150]

George Smith approached Chauncey Parry early in April 1923, that is, several months after the Parrys' Zion franchise had expired. At the time Chauncey Parry told Smith the brothers had no property, other than a few automobiles, automobile equipment, and a small garage. Smith was taken back when Chauncey told Smith the brothers expected to secure interest in whatever transportation scheme the Utah Parks Company proposed for the region. It was Smith's impression Chauncey based this aggressive position on reassurances he had gained from an earlier conversation with Samuel Lancaster. [151]

A dearth of documents on the franchise issue prevents an accurate appraisal of Omaha's position between April 1923 and March 1924—when the railroad did effectively secure the Parry's interests in southwestern Utah. [152] From a strict legal standpoint the brothers' position was indefensible. Their Zion franchise had expired, and the State's Public Utility Commission license indicated the touring service from Cedar City and Marysville operated "with limitation as to time." It was probably this ambiguity written into the State license, however, and resistance on the part of the Public Utility Commission in Salt Lake City to clarify it, that forced the railroad into a contractual agreement highly attractive to the Parry brothers.

The 16-page agreement concluded on March 4, 1924, permitted the brothers to operate a regional motor transportation service under Utah Parks Company supervision. There were two key provisions in the contract, both generous to the Parrys. First, the brothers were to operate the transportation service for the Utah Park Company, until they decided to sell out completely. [153] Second, as long as the Parrys operated the service, in accordance with the provisions of the contract, they were to receive the combined annual salary of \$5,000. [154]

The Utah Parks Company was legally required to purchase only vehicular equipment acquired by the brothers after February 15, 1924. [155] A description of these vehicles is not included in the contract, but it is known the Parrys operated some "White" touring cars. [156] On May 3, 1923, nearly a year before the Parry settlement, H. R. Child, President of the Yellowstone Park Transportation Company, strongly recommended to H. M. Adams, Union Pacific's Vice President of Traffic, that the Utah Parks Company purchase White touring cars for its operation:

. . . I do not hesitate to say to you very frankly that there isn't a car manufactured which can come anywhere near holding its own in any way with this White equipment, and you will make a mistake if you put in any other automobile to handle your tourists . . . [157]

Child's advice was passed from Adams to Gray, but it appears Gray decided to be selective. In the spring of 1925, the Utah Parks Company received permission from the Utah Public

Utilities Commission to operate 40 touring cars, each having seats for 10 passengers. [[158](#)]
Eight of the forty were new White "53's" with Scott bodies. [[159](#)] In 1929, Utah Parks
Companies transportation fleet was augmented with the addition of 5 White "65's," capable of
carrying 13 passengers. [[160](#)] The Whites did prove durable and were the backbone of Utah
Parks Companies touring service until the outbreak of World War II.


<<< [Previous](#) <<< [Contents](#) >>> [Next](#) >>>


Bryce Canyon

Historic Resource Study




REGIONAL DEVELOPMENT





Map 2. Bryce Canyon National Monument, 1923. (*Record Group 79, Records of the National Park Service, National Archives Building, Washington, D.C.*)



[<<< Previous](#)

[<<< Contents >>>](#)

[Next >>>](#)

Bryce Canyon

Historic Resource Study



NATIONAL MONUMENT STATUS



Illustration 16. Construction of Deluxe Cabins, North Rim, 1927. (*Nebraska State Historical Society*)




Illustration 17. Deluxe Cabins at Bryce Canyon, probably late 1920s. (*Nebraska State Historical Society*)



Illustration 18. Interior of a Deluxe Cabin, Bryce Canyon or North Rim, probably late 1920s. (*Nebraska State Historical Society*)




Illustration 19. Utah Parks Company Shelter at Bryce Canyon Point, removed 1945. (*Record Group, Records of the National Park Service, National Archives Building, Washington, D.C.*)

[<<< Previous](#)

[<<< Contents >>>](#)

[Next >>>](#)

Bryce Canyon

Historic Resource Study



NATIONAL MONUMENT STATUS



Illustration 11. Bryce Canyon Lodge, 1924. (*Colorado Historical Society*)




Illustration 12. Concrete walks connecting Standard Cabins to Bryce Canyon Lodge, date unknown. (*Nebraska State Historical Society*)




Illustration 13. Interior of Standard Cabin, Bryce Canyon or Zion National Parks, date unknown. *(Nebraska State Historical Society)*




Illustration 14. Construction of Deluxe Cabin No. 3 at North Rim, 1927. *(Nebraska State Historical Society)*




Illustration 15. Construction of Deluxe Cabin No. 3 at North Rim, 1927. *(Nebraska State Historical Society)*

<<< [Previous](#)

<<< [Contents](#) >>>

[Next](#) >>>

brca/hrs/hrs4b.htm
Last Updated: 25-Aug-2004

Bryce Canyon

Historic Resource Study



NATIONAL PARK STATUS (continued)

LAND ACQUISITION

Senate Bill 1312 resulted in the February 25, 1928, Act of Congress which made the title Bryce Canyon National Park official. By virtue of this Act, and a corrective Act dated May 14, 1928, [231] a total of 11 sections of land were added to the future national park. These were: (1) the E1/2 of the E1/2 of Section 25 in T. 36 S., R. 4 W.; (2) the E1/2 and SW1/4 of Section 20, and all of Sections 21, 28, 29, 30, and 33 in T. 36 S., R. 3 W.; (3) all of Sections 24 and 25 in T. 37 S., R. 4 W.; and (4) all of Sections 19, 20, and 30 in T. 37 S., R. 3 W. From May 14, 1928, to June 13, 1930, Bryce Canyon included 22.625 sections, or 14,480 acres (Map 5).

Lands added to Bryce Canyon as a result of the 1928 Acts had to be excluded from Powell National Forest. This, of course, required close cooperation between the National Park Service and the Forest Service officials. The Chief Forester, Colonel Greeley, was willing to relinquish land to the Park Service, and asked only that it be land of particular scenic value. [232] Randall Jones, Union Pacific's agent in Cedar City, had thought for some time that Little Bryce Canyon and Boat Mountain belonged to the park, and available evidence suggests that Park Service officials concurred with his assessment. [233] They also wanted sufficient surrounding area to make these attractions accessible from Forest Service roads in Bryce Canyon. It is worth emphasizing, however, that indiscriminate additions to Bryce Canyon made no sense to either Mather or Albright. In fact, there was a deep seated unwillingness on Mather's part to acquire so much Forest Service land that road building obligations would overwhelm the future park's budget for years to come. [234]

The direct relationship between the size of Bryce Canyon and the financial obligations of the National Park Service toward it did not, however, prevent Senator Smoot of Utah from assiduously attempting to enlarge the park. Smoot actively opened his Congressional campaign in the spring of 1930 with Senate Bill 4170, a bill "To provide for the addition of certain lands to the Bryce Canyon National Park . . . and for other purposes." [235] On June 13, 1930, Senate Bill 4170 resulted in Public Law 352 of the 3rd session, 71st Congress. This law, and the joint recommendation of the Secretaries of Agriculture and Interior, authorized President Hoover to issue Proclamation No. 1930 on January 5, 1931.

Smoot's original bill, introduced on April 15, 1930, and House Bill 11698 sponsored by Utah Congressman Don Colton the following day, asked that any or all of unsurveyed Townships 37 and 38 S., R. 4 W. not already included in the park be added to it. [236] This general request was later made precise, and took in the following parcels by virtue of the Presidential Proclamation of January 5, 1931:

Unsurveyed T. 37 S., R. 4 W.

1. S1/2 of Section 2

2. S1/2 of SE1/4 of Section 3
 3. S1/2 and NE1/4 of Section 10
 4. All of Sections 11, 14, and 15
 5. E1/2 and the E1/2 of the SW1/4 of Section 16
 6. E1/2 of SE1/4 of Section 20
 7. All of Sections 21, 22, and 23
 8. W1/2 of Section 27
 9. All of Section 28
 10. E1/2 and E1/2 of SW1/4 of Section 29
 11. S1/2 of Section 31
 12. All of Section 32
 13. N1/2 of Section 33.
-

The principal effect of President Hoover's January 5, 1931, Proclamation was to more than double the size of Bryce Canyon from 22.625 sections (14,480 acres) to 47.75 sections (30,560 acres). Southwest expansion along the Paunsaugunt rim allowed the Park Service to take under its protection points of scenic interest as far south as Rainbow Point (Map 6).

On the very day President Hoover issued Proclamation No. 1930, Senator Smoot introduced Senate Bill 5564 to the 3rd session of the 71st Congress. Eight days later Congressman Colton followed with the near-duplicate House Report 16116. Smoot and Colton asked for the removal of Section 30 in T. 37 S., R. 3 W., and Section 25 in unsurveyed T. 37 S., R. 4 W., but the real thrust of their bills was the proposal to add approximately 9.42 sections northeast of the park, as well as a total of 1 section to the far south. These proposed additions promised to entail the National Park Service with no further road building obligations, so high Park Service officials—especially Albright—favored the measure.

Park Service Director Albright explained his position on House Rule 16116 in a letter to the Secretary of the Interior, dated January 17, 1931:

The area covered by this bill is adjoining and contiguous to the Bryce Canyon National Park and comprises approximately 6,360 acres [sic]. [\[237\]](#)

Approximately 3,400 acres of this area are within the Powell National Forest and the remaining approximately 2,960 acres are a part of the public domain but were withdrawn by Executive order dated January 5, 1931 for classification and in aid of legislation. The lands in the bill are not of any great value for grazing purposes and are of greater value for scenic and scientific purposes than for economic development.

This bill also proposes to eliminate 1,280 acres from what are now within the boundaries of the national park and add same to the Powell National Forest. The adjustment of the boundaries of the Bryce Canyon National Park as provided for by the bill is along lines worked out by the superintendent of the Bryce Canyon National Park and the regional forester of the United States Forest Service under agreement between the two services. This adjustment will not change in any way the financial obligation of either service.

...

I have to recommend that H.R. 16116 . . . be given favorable consideration and enacted into law. [\[238\]](#)

The House Report did become Public Law 675 of the 3rd session, 71st Congress on February

17, 1931. President Hoover used this law as partial authorization for Proclamation No. 1952, dated May 4, 1931. Additions to Bryce Canyon included in the Proclamation are listed below with necessary emendations:

T 36 S. R 3 W.

Surveyed

1. S1/2 of SW1/4 of Section 2
2. S1/2 of S1/2 of Section 3
3. SE1/2 of SE1/4 of Section 4
4. E1/2 of Section 8
5. All of Section 9
6. N1/2 of Section 10
7. NW1/4 of Section 11
8. E1/2 of NE1/4 of NW1/4 and E1/2 of NW1/4 of NW1/4 and E1/2 of NW1/4 of NW1/4 and N1/2 of SE1/4 of NW1/4 and S1/2 of NE1/4 of SW1/4 and N1/2 of the S1/2 of SE1/4 of NW1/4 and N1/2 of SE1/4 of SW1/4 of Section 17.

Note:

Both the Act of February 17, 1931, and Proclamation of May 4, 1931, erroneously described Section 17. The correct description should read: E1/2 and NE1/4 of NW1/4, etc. This correction was made by Public Law 485 of the 2nd session, 77th Congress on March 7, 1942. Public Law 485 of the 2nd session, 77th Congress, brought to an end the legislative history for Bryce Canyon.

9. S1/2 of S1/2 of Section 19
10. S1/2 of NW1/4 of Section 20.

Unsurveyed

1. S1/2 of Section 10
2. SW1/4 of Section 11
3. W1/2 of Section 14
4. All of Sections 15 and 16
5. W1/2 of W1/2 of E1/2 and NE1/4 of NE1/4 of Section 22

Note: Both the Act of February 17, 1931, and Proclamation of May 4, 1931, erroneously described Section 22. The correct description should read: W1/2 and W1/2 of E1/2, etc. This correction was made by Public Law 485 of the 2nd session, 77th Congress on March 7, 1942.

6. N1/2 of NW1/4 of Section 23
7. W1/2 of Section 27
8. N1/2 of NW1/4 of Section 34.

The principal effect of President Hoover's May 4, 1931 Proclamation was to increase Bryce Canyon from 45.75 sections (29,280 acres) to 56.22 sections (35,980 acres). Northeast expansion along the Paunsaugunt rim allowed the Park Service to take under its protection points of scenic interest as far north as Shakespeare Point.

Boundaries — Marian Frost Settlement

Section 2 of the June 7, 1924, Act establishing the Utah National Park Stipulated that:

. . . nothing herein contained shall affect any valid existing claim, location, or entity under the land laws of the United States, whether for homestead, mineral, right of way, or any other purposes whatsoever, or shall affect the rights of any such claimant, locator, or entryman to the full use and enjoyment of his land . . .

The full meaning of this provision was not an issue until Marion Frost, a resident of Tropic, directed a complaint to the State Land Board on September 22, 1930. This complaint was soon referred to the General Land Office in Salt Lake City for an answer. In it, Frost explained that "Park Surveyors" had sent him notice to move his house and fence from a 40 acre tract in Section 33, T. 36 S., R. 3 W. This property, Frost contended, was as much his as the patented homestead adjoining it—upon which he claimed settlement since 1917. [[239](#)]

Frost originally had his house and other improvements located on the SW1/4 of the SW1/4 in Section 34, T. 36 S., R. 3 W., and after patent moved them to the unsurveyed SE1/4 of the SE1/4 of Section 33—the land in question. "About" September 1928 Frost sold his 120 acre homestead, comprising the W1/2 of the SW1/4 and NE1/4 of the SW1/4 of Section 34, and the 40 acre tract in Section 33 to Jesse L. and Mary L. Jolley of Tropic. At the time of the sale Frost gave the Jolleys a written statement, transferring all rights and interest in the homestead, and promised he would deliver deeds to the unsurveyed land in Section 33 as soon as they were obtainable. [[240](#)]

If Frost's claim was valid, its effect on the young park would be singularly negative. Naturally, the most far reaching implication involved the cardinal condition imposed for the creation of a National Park at Bryce Canyon by the June 7, 1924, Act: that all land within the park be owned by the Federal Government. If this condition had not been fulfilled, then everything done by the National Park Service since its administrative takeover on September 15, 1928, was illegal. Secondly, if the 40-acre tract were removed from the park, it would be left as an isolated, unsurveyed block, with contiguous land to the north and west already having been added to Bryce Canyon (see Map 5).

Responsibility for certifying that the land in question was free of encumbrances lay with the General Land Office, Department of Interior. However, Eli F. Taylor, Registrar of the Land Office in Salt Lake City, had already muddied the water by recognizing Frost's title to the SE1/4 of the SE1/4 of Section 33. This forced the National Park Service to seek a solution from higher authorities. On September 30, 1930, Bryce Canyon/Zion Superintendent Scoyen directed correspondence to Acting National Park Service Director G. A. Moskey, plainly asking for advice. A week later Moskey told Scoyen to wait until the Land Office in Washington, D. C., conducted an investigation and issued a decision. [[241](#)]

Scoyen was understandably uneasy. On October 8, 1930, he wrote National Park Service Director Albright that:

. . . the General Land Office in Salt Lake advises that they . . . had no way of knowing the existence of this claim, and, on the basis of information presented, there could be doubt as to the validity of Frost's claim. However, in view of the fact he has sold this claim, it will be necessary for him to prove that this transaction was completed before the land was put in the park. If this cannot be done the purchaser will have no claim to the land and Frost's claim will no longer be effective. [[242](#)]

Given the issue's seriousness the General Land Office in Washington, D. C., moved quickly

to resolve it. On November 11, 1930, Acting Assistant Commissioner John McPhaul of the Land Office wrote a stern letter to Registrar Taylor, definitely implying that Taylor was guilty of hasty judgment in recognizing Frost's claim to the unsurveyed 40 acres in Section 33. Early in January 1931 Assistant Commissioner Thomas C. Havell of the General Land Office reached a final decision, holding that neither Frost nor his successors in interest—the Jolley family—had a valid claim. Havell's decision was immediately approved by John H. Edwards, the Assistant Secretary of the Interior. Edwards' action denied Frost any right of appeal. The case was closed.

Havell's reasoning followed the principle enunciated by Superintendent Scoyen 3 months earlier. Thus, it could be demonstrated that Frost had legally sold the 120 acres in Section 34 to the Jolley family, but the "sale" of 40 acres in Section 33 was another matter. In Havell's words:

The original act [i.e. June 7, 1924] excepted from its provisions valid existing claims, locations and entries under the land laws "whether for homestead, mineral, right of way, or any other purpose whatsoever." Under the terms of these acts, any valid existing settlement claim within the areas set aside for park purposes is protected from the force and effect of the withdrawal, so long as the claim is properly maintained. Upon the failure of such claim, however, by relinquishment, attempted sale, or otherwise, the withdrawal at once becomes effective and prevents any further appropriation of the land.

It would seem, therefore, that upon the sale of the said patented land and the attempted sale of the settlement claim by Frost, the withdrawal attached as to the unsurveyed land and prevented any further lawful appropriation thereof; that the settler, Frost, has forfeited whatever right he had to such claim and that the purchaser, Mrs. Mary L. Jolly [sic], has no right thereto which can be successfully asserted as against the withdrawal. [244]

Abbreviated Grazing History

Expansion of the park, especially to the southwest, did not merely imply the National Park Service would be saddled with road building responsibilities. There was, as well, another major consideration: the opposition of local stockmen. These men reasoned that if certain areas upon which they grazed animals were absorbed into Bryce Canyon, they were likely to lose rights whose value was calculable. For example, a stockman selling a herd of sheep which had the right to graze on National Forest land was normally paid about \$3 extra for each animal covered by the permit. Consequently, if land under a valid Forest Service grazing permit was acquired by the new park, local stockmen expected the National Park Service to either buy out applicable grazing rights or continue to allow grazing in the area. [245]

Grazing was well established at Bryce Canyon, dating back to Mormon settlement of the area in the late 1860s. With the creation of the "East Division" of the Sevier National Forest in 1903, grazing at Bryce Canyon naturally came under Forest Service supervision. [246] The situation continued when the "East Division" was added to the Powell National Forest in 1919. [247] In fact, the Forest Service issued grazing permits at Bryce Canyon until 1929. As an interim measure the National Park Service Director authorized the Forest Service to handle grazing through 1929. [248]

Conditions of leniency ostensibly prevailed during the issuance of Forest Service permits from 1904-29 and in retrospect it can be demonstrated that between 1907-40 total forage in the Bryce Canyon area inexorably declined. [249] In 1936, 6 years after the Park Service

began imposing grazing restrictions, grass was still scarce along the Paunsaugunt rim. In 1930 the dead and partly dead stumps of shrubs such as snowberry, willow birch lear, aspen, and yellow pine were all too evident. [250] Their sad presence was poignant testimony to the story of overgrazing at Bryce Canyon.

In accordance with a memorandum of understanding between the two services, dated December 2, 1927, the Forest Service agreed to relinquish lands of exceptional scenic value to the future national park on condition the National Park Service refrained from imposing immediate or drastic action on local stockmen. At the time, District Forester Rutledge stressed that grazing permittees be given reasonable time and opportunities to locate alternate ranges. [251] Bound by this understanding, and the disinclination to buy away grazing rights, the National Park Service had little room for maneuver. It was, however, the intent of the Park Service to effectively impose those restrictions left at its disposal. The most important of these required that no transfer of grazing rights be made from one permittee to another without the personal approval of the National Park Service Director. [252] The principle here was clear: no sale of stock necessarily carried with it the right to graze the animals at Bryce Canyon.

Between 1928-31 cooperation between the Forest Service and Park Service was absolutely essential. Nearly all of the land covered by proposed additions to the park remained under the Forest Service's protection. A "field agreement" between the two services, dated December 4, 1930, put into effect the following measures for these lands: (1) no change of existing privileges to the detriment of current permittees; (2) administration of permits and fees by the Forest Service, in accordance with cooperative Forest Service-National Park Service plans; (3) no increase in the number of livestock permitted in areas contiguous to Bryce Canyon; (4) transfer of grazing permits allowed with a 20 percent reduction in each case; and (5) the elimination of grazing as a long-range goal. [253] President Hoover's May 4, 1931, Proclamation was partially reflective of this agreement, stipulating that stockmen had the right to drive their animals across the southwestern addition to the park. [254]

Inter-service cooperation during the years 1931-35 had the effect of eliminating grazing in the north-central area of Bryce Canyon. Encouraged, the Secretary of the Interior asked the National Park Service to study means for the speedy elimination of all grazing. A wide range of possibilities was given careful consideration by park personnel, and, in the end, their recommendation was to continue the December 4, 1930, Forest Service-National Park Service agreement for gradual reduction. In 1939 the Secretary accepted this recommendation, but wanted the National Park Service to cooperate more closely with the Grazing Service to find nearby ranges on which stock then grazing in Bryce Canyon could be easily transferred. [255]

In 1940 the status of grazing at Bryce Canyon was as follows:

<u>Permittee</u>	<u>No. and Kind of Stock</u>	<u>Time on park</u>
Findlay Brothers	500 sheep	1 month
John Johnson	1,000+ sheep	1 month
Samuel Follock	824 sheep	1 month
East Fork Cattle Association	802 cattle & horses	10 percent [256]

Subsequently, the trend toward gradual reduction continued. In 1944 Johnson sold his sheep and began to raise cattle. Findlay followed suit the following year. In 1946 Pollock sold his sheep, terminating all sheep grazing in Bryce Canyon. Johnson's permit was invalid in 1951. By 1953 the only permittees in the Bryce Canyon area were these:

<u>Permittee</u>	<u>No. of Stock</u>
Findlay Brothers	288 cattle
East Fork Cattle Association	484 cattle [257]

This satisfactory trend was brought to a temporary halt in 1956 when the Johnson permit was reinstated. It had been unilaterally terminated by the National Park Service in 1951 because of nonuse. Unfortunately, the Forest Service was not informed, which constituted a breach of the December 2, 1927, Memorandum of Understanding between the two services. Then, between 1951-56 the local Forest Supervisor's office had continued to carry Johnson as a permittee. [[258](#)] Although this was a temporary setback to the Bryce Canyon grazing termination program, in the long-run the incident was probably beneficial. It certainly had the effect of making Park Service personnel aware of the fact that a closer working relationship with the Forest Service was indispensable.

Of the two additional permittees, the Findlay Brothers were considered the more difficult problem. Their cattle watered at Riggs Spring on the Lower Podunk, a locale that was inside the park but which furnished very little forage. To get the Findlays to give up their permit inside the park, Bryce Canyon personnel had to consider piping water from Riggs Spring outside the park. Relations with the other permittee, the East Fork Cattle and Horse Association, were generally good. In 1956 the Association voluntarily agreed to reduce the level of grazing by its animals within the park. [[259](#)] Johnson's permit was not reinstated in 1957. He had divided his forest grazing permit among several members of his family. The Forest Service then refused to transfer to another operator that part of his permit which was applicable to park lands. [[260](#)] The Findlays and East Fork Cattle Association doggedly maintained their permits through the 1963 grazing season. Both permittees continued to cherish the water supply at Riggs Spring. In order to exclude these cattle, the park scheduled a fencing program for fiscal year 1964. Riggs Spring was understandably given top priority. [[261](#)]

Adequate funding during fiscal year 1964 enabled Bryce Canyon to pipe water from Riggs Spring to a trough outside the park's boundary. [[262](#)] This part of the boundary was also fenced. Completion of a 13 mile sector of fence along the west boundary eliminated grazing on the East Fork permits. By the end of the calendar year 1964, permit grazing at Bryce Canyon had been eliminated. [[263](#)]

<<< [Previous](#)

<<< [Contents](#) >>>

[Next](#) >>>

Bryce Canyon

Historic Resource Study



NATIONAL PARK STATUS




Illustration 45. Completion photograph of modernization, Campfire Lecture Facility at North Campground, probably early 1960s. (*Record Group 79, Records of the National Park Service, Denver Federal Records Center, Denver, Colorado*)



Illustration 46. Staging for Campfire Circle under construction at Sunset Campground, probably early 1960s. (*Record Group 79, Records of the National*

Park Service, Denver Federal Records Center, Denver, Colorado)



Illustration 47. Completion photograph of Campfire Lecture Facility at Sunset Campground, probably 1960s. (*Record Group 79, Records of the National Park Service, Denver Federal Records Center, Denver, Colorado*)

[<<< Previous](#)

[<<< Contents >>>](#)

[Next >>>](#)