



Water Quality Monitoring at Acadia National Park

Northeast Temperate Network 2014 Summary Report

Natural Resource Data Series NPS/NETN/NRDS—2016/1021



ON THE COVER

Breakneck Brook, June 2014

Photograph by: Shannon Wiggin

Water Quality Monitoring at Acadia National Park

Northeast Temperate Network 2014 Summary Report

Natural Resource Data Series NPS/NETN/NRDS—2016/1021

William G. Gawley
Shannon P. Wiggin

National Park Service
Acadia National Park
PO Box 177
Bar Harbor, Maine 04609

May 2016

U.S. Department of the Interior
National Park Service
Natural Resource Stewardship and Science
Fort Collins, Colorado

The National Park Service, Natural Resource Stewardship and Science office in Fort Collins, Colorado, publishes a range of reports that address natural resource topics. These reports are of interest and applicability to a broad audience in the National Park Service and others in natural resource management, including scientists, conservation and environmental constituencies, and the public.

The Natural Resource Data Series is intended for the timely release of basic data sets and data summaries. Care has been taken to assure accuracy of raw data values, but a thorough analysis and interpretation of the data has not been completed. Consequently, the initial analyses of data in this report are provisional and subject to change.

All manuscripts in the series receive the appropriate level of peer review to ensure that the information is scientifically credible, technically accurate, appropriately written for the intended audience, and designed and published in a professional manner.

This report received informal peer review by subject-matter experts who were not directly involved in the collection, analysis, or reporting of the data.

Views, statements, findings, conclusions, recommendations, and data in this report do not necessarily reflect views and policies of the National Park Service, U.S. Department of the Interior. Mention of trade names or commercial products does not constitute endorsement or recommendation for use by the U.S. Government.

This report is available from the Northeast Temperate Network website (<http://science.nature.nps.gov/im/units/netn/monitor/programs/lakesPonds/lakesPonds.cfm>) and the Natural Resource Publications Management website (<http://www.nature.nps.gov/publications/nrpm/>). To receive this report in a format optimized for screen readers, please email irma@nps.gov.

Please cite this publication as:

Gawley, W. G., and S. P. Wiggin. 2016. Water quality monitoring at Acadia National Park: Northeast Temperate Network 2014 summary report. Natural Resource Data Series NPS/NETN/NRDS—2016/1021. National Park Service, Fort Collins, Colorado.

Contents

	Page
Figures.....	v
Tables.....	vii
Executive Summary	viii
Introduction.....	1
Sampling Sites	1
Methods.....	4
Water Quality Standards	4
Results.....	7
Water Quality	7
Specific Conductance	7
pH	10
Temperature.....	12
Dissolved Oxygen	14
Acid Neutralizing Capacity	16
Apparent Color	18
Dissolved Organic Carbon	20
Transparency	22
Light Penetration Profiles.....	23
Turbidity	28
Nutrient Enrichment	29
Phosphorus	29
Nitrogen.....	30
Chlorophyll a	33
Other Analytes.....	34
Chloride	34
Sulfate.....	37
Water Quantity	39
Stream Discharge.....	39

Contents (continued)

	Page
Stream and Lake Stage	41
Invasive Aquatic Plants	43
Other Monitoring.....	44
Quality Assurance and Quality Control (QA/QC)	45
Field QC Replicate Measurements	45
Nutrient QC Sample Results	45
Summary	47
Literature Cited	49
Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014.	51
Appendix B. Acadia National Park (ACAD) Blank and Replicate Water Samples, 2014.	117

Figures

	Page
Figure 1. NETN lake and stream monitoring sites at Acadia National Park	2
Figure 2. Explanation of box plot graph.	7
Figure 3. Lake and pond specific conductance from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014.....	8
Figure 4. Stream specific conductance from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014.....	9
Figure 5. Lake and pond pH from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014	10
Figure 6. Stream pH from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014.....	11
Figure 7. Lake and pond water temperature (surface) from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014.....	12
Figure 8. Stream water temperature (surface) from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014.....	13
Figure 9. Lake and pond dissolved oxygen (surface) from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014.....	14
Figure 10. Stream dissolved oxygen (surface) from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014.....	15
Figure 11. Lake and pond acid neutralizing capacity from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2006-2014.....	16
Figure 12. Stream acid neutralizing capacity from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2006-2014.....	17
Figure 13. Lake and pond apparent color from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2006-2014.....	18
Figure 14. Stream apparent color from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2006-2014.....	19
Figure 15. Lake and pond dissolved organic carbon (DOC) from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2012-2014.....	20
Figure 16. Stream dissolved organic carbon (DOC) from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2012-2014.....	21
Figure 17. Secchi disk transparency from 2014 monthly measurements overlaid on a box plot of measurements taken from 2006-2014	22
Figure 18. Light penetration profiles from Jordan Pond.....	24
Figure 19. Light penetration profiles from Lake Wood.....	25

Figures (continued)

	Page
Figure 20. Light penetration profiles from Round Pond.....	26
Figure 21. Light penetration profiles from Upper Breakneck Pond	27
Figure 22. Stream turbidity from 2014 monthly measurements overlaid on a box plot of measurements taken from 2012-2014.....	28
Figure 23. Lake and pond total phosphorus (TP) from 2014 spring and summer water samples.....	29
Figure 24. Stream total phosphorus (TP) from 2014 spring and summer water samples	30
Figure 25. Lake and pond total nitrogen (TN), the nitrogen component of nitrate (NO ₃ -N) and ammonia (NH ₃) from 2014 spring and summer water samples	31
Figure 26. Stream total nitrogen (TN) and the nitrogen component of nitrate (NO ₃ -N) and ammonia (NH ₃) from 2014 spring and summer water samples	32
Figure 27. Lake and pond chlorophyll <i>a</i> from 2014 spring and summer water samples	33
Figure 28. Lake and pond chloride from 2014 spring and summer water samples	35
Figure 29. Stream chloride from 2014 spring and summer water samples.....	36
Figure 30. Lake and pond sulfate from 2014 spring and summer water samples.....	37
Figure 31. Stream sulfate from 2014 spring and summer water samples	38
Figure 32. Monthly stream discharge measurements from partial and continuous record sites.	39
Figure 33. Daily mean discharge from the Otter Creek continuous record site for calendar year 2014.	40
Figure 34. Daily mean stream stage measured in 2014 at NETN permanent record stream monitoring sites in Acadia NP.	41
Figure 35. Weekly lake stage measured in 2014 at NETN monitoring sites in Acadia NP.....	42

Tables

	Page
Table 1. 2014 lake and pond monitoring sites at Acadia National Park.	3
Table 2. 2014 stream monitoring sites at Acadia National Park.	3
Table 3. EPA Ecoregion 8 nutrient criteria.	5
Table 4. Maine Center for Invasive Aquatic Plants species of concern.	43

Executive Summary

This report on the water quality of Acadia National Park (ACAD) includes data gathered by the Northeast Temperate Network (NETN) during the 2014 monitoring season and displays these results in graphic form, accompanied by a brief interpretation. The data address the NETN objective to detect change in the status of physical, chemical, or biological attributes of park freshwater bodies.

The NETN freshwater monitoring protocol calls for a total of 37 ACAD lakes, ponds and streams to be sampled monthly from May through October, with 12 sites monitored annually and the remainder visited on a 2-year (streams) or 3-year (lakes and ponds) rotating schedule. Staff measured physical and in-situ water chemistry parameters each month and periodically collected water samples for analysis at the University of Maine's Sawyer Environmental Chemistry Research Laboratory.

Monthly sampling parameters included in-situ water quality measures (pH, specific conductance, temperature, and dissolved oxygen), lake water transparency and light, stream turbidity, weather, stream flow (discharge), and stream and lake/pond stage. In May (stream only), June (lakes and ponds only) and August (all sites), water samples were obtained and analyzed for acid neutralizing capacity (ANC), color, nutrients, dissolved organic carbon (DOC), chloride, sulfate, and chlorophyll *a* (lakes and ponds only). April and October lake acidification samples were also collected.

The primary environmental stressors affecting ACAD water resources include nutrient enrichment and toxic contaminants within the watershed, atmospheric deposition, and climate change.

Monitoring in 2014 revealed that the majority of water quality parameters for Acadia National Park were within state standards, and were generally within the range of EPA regional nutrient criteria, where applicable. The values were also typically within the range of Acadia's historic monitoring data record, and there were no indications that significant nutrient enrichment took place during the 2014 season. Analysis results of 2014 quality control samples were within the acceptable range of accuracy and precision.

Introduction

This report on the water quality of Acadia National Park (ACAD) generated by the Northeast Temperate Network (NETN) Water Quality Monitoring Program includes data gathered in the 2014 monitoring season and displays these results in graphical form, accompanied by a brief interpretation. Appendix A contains data collected in 2014 in tabular form.

The vital signs for freshwater bodies included in the NETN Freshwater Monitoring Protocol (Gawley et al. 2014) are water chemistry, nutrient enrichment, water quantity, and the detection of invasive plant species. These metrics were chosen to address the NPS Inventory and Monitoring Program objective to detect change in the status of physical, chemical, or biological attributes of the ecosystem.

The NETN freshwater monitoring protocol calls for lakes, ponds, and streams to be sampled monthly from May through October. A total of 37 ACAD water bodies are monitored, with 12 sites monitored annually and the remainder visited on a 2 year (streams) or 3 year (lakes/ponds) rotating schedule. Park staff measure physical and in-situ water chemistry parameters during each monthly visit, and periodically gather water samples for analysis at the University of Maine's (UMO) Sawyer Environmental Chemistry Research Laboratory. Additionally, stage height (water level) is recorded weekly at 17 lakes during the open-water season. All monitoring data are incorporated into a series of comprehensive databases that ultimately feed the U.S. Environmental Protection Agency's (EPA) "STORET" data system, the repository for all NPS water quality and quantity data.

Sampling Sites

Acadia National Park lakes, ponds, and streams that are monitored by NETN are mapped in Figure 1. Eight lake and pond sites are sampled every year, while nine additional lakes and ponds are monitored as part of a rotating design in which each site is sampled every 3rd year. A total of 11 lakes and ponds are monitored each year. Three continuous-record stream sites (with stream stage gages that collect data automatically) are sampled annually, and 16 partial-record stream sites (monthly stream flow data collection) are sampled using a rotating design where each site is sampled every other year. Beginning in 2011, one partial-record site (Stanley Brook) is also sampled annually due to concerns about potential threats from residential development in the watershed. A maximum of nine partial-record sites and three continuous-record stream sites are sampled each year. The sites monitored in 2014 are listed in Table 1 (lakes and ponds) and Table 2 (streams).



Figure 1. NETN lake and stream monitoring sites at Acadia National Park. Pond sites are included in the lake category.

Table 1. 2014 lake and pond monitoring sites at Acadia National Park.

Site Type	Name	NETN Site Code	Latitude	Longitude
Annual sites	Bubble Pond	ACBUBL	44.3450646	-68.2388551
	Eagle Lake	ACEAGL	44.3635138	-68.2504239
	Echo Lake	ACECHO	44.3270197	-68.3377142
	Jordan Pond	ACJORD	44.3311101	-68.2552632
	Long Pond	ACLONG	44.3275187	-68.3633332
	Seal Cove Pond	ACSEAL	44.3014677	-68.3971887
	Upper Hadlock Pond	ACUHAD	44.3213604	-68.2874398
	Witch Hole Pond	ACWHOL	44.4000095	-68.2429494
Rotating sites	Round Pond	ACROUN	44.3527900	-68.3777000
	Lake Wood	ACWOOD	44.4077800	-68.2684400
	Upper Breakneck Pond	ACUBRK	44.3865500	-68.2554500

Table 2. 2014 stream monitoring sites at Acadia National Park.

Site Type	Name	NETN Site Code	USGS Station #	Latitude	Longitude
Permanent continuous-record sites	Cadillac Brook	ACCADS	01022835	44.3445581	-68.2170000
	Hadlock Brook	ACHADB	01022860	44.3316667	-68.2800000
	Otter Creek	ACOTRC	01022840	44.3327778	-68.2072222
Permanent partial-record site	Stanley Brook	ACSTNL	01022850	44.3055560	-68.2430560
Rotating partial-record sites	Hunters Brook	ACHNTR	01022845	44.3093900	-68.2223600
	Kebo Brook	ACKEBO	01022829	44.3724100	-68.2218500
	Sargent Brook	ACSGTB	10228665	44.3502900	-68.2902000
	Breakneck Brook	ACBRKB	01022825	44.4112300	-68.2520400
	Aunt Bettys Pond inlet	ACABIN	01022869	44.3651200	-68.2724100
	Marshall Brook	ACMRSL	01022890	44.2747400	-68.3515000
	Heath Brook	ACHTHB	01022895	44.2778200	-68.3681700

Methods

Detailed descriptions of all monitoring methods are found in the original protocol (Lombard et al. 2006) and the most recent protocol update (Gawley et al. 2014). Monthly sampling parameters included in-situ water quality measures (pH, specific conductance, temperature, and dissolved oxygen) determined with a YSI 600XL sonde, Secchi transparency or light penetration (lake and pond sites only), stream turbidity, weather, stream flow (discharge), and stream and lake stage. In May (streams only), June (lakes and ponds only) and August (all sites), water samples were obtained and analyzed for acid neutralizing capacity (ANC), color, nutrients (including total nitrogen, nitrate, and total phosphorus), and chlorophyll *a* (lakes and ponds only). In 2012, dissolved organic carbon (DOC), sulfate, and chloride were added to the analyte list, and total dissolved phosphorus, soluble reactive phosphorus, and total dissolved nitrogen were removed as analytes.

The lake and pond sampling procedure entails collecting all in-situ measurements and water samples from the deep hole (or center, in the case of lakes with uniform bathymetry) of the water body. Nutrient chemistry parameters are analyzed from a series of epilimnion core samples (4-10 meter depth) integrated in a churn splitter if the lake is stratified or a half-meter grab sample if the lake is unstratified.

Stream discharge was measured using U.S. Geological Survey protocols (Rantz et al. 1982), employing a measuring tape, wading rod, and SonTek FlowTracker or a Price Pygmy current meter to measure a particular cross-sectional area of the stream and the velocity of the water at that cross section.

In-situ stream water chemical and physical measurements and water samples were collected within 5 meters of the location of the discharge measurement. Sonde measurements were taken in the main stream flow with care taken that the sonde was not resting directly on the stream bottom. Grab samples were obtained by submerging the sample bottle directly in the stream with a gloved hand.

Water Quality Standards

Maine Statutes, Title 38, Sections 464, 465, and 465-A define the classification program and water quality standards for Maine waters (Maine State Government 2011, 2007a, 2007b). Existing in-stream water uses and the level of water quality necessary to protect those existing uses must be maintained and protected. All waters in national parks are considered outstanding national resource waters (ONRW) in Maine. The water quality of ONRW must be maintained and protected. Class AA is the highest classification and its standards are applied to waters that are outstanding natural resources.

“Class AA waters must be of such quality that they are suitable for the designated uses of drinking water after disinfection, fishing, agriculture, recreation in and on the water, navigation, and as habitat for fish and other aquatic life. The habitat must be characterized as free-flowing and natural. The aquatic life, DO [Dissolved Oxygen], and bacteria content of Class AA waters shall be as naturally

occur” (Maine State Government 2007a). No quantitative criteria are given for AA waters, but the DO content of Class A waters (the next lowest classification) “shall be not less than 7 parts per million or 75 percent of saturation, whichever is higher”.

Great ponds (more than 10 acres in size) and smaller natural ponds and lakes are all classified as Class GPA waters. “Class GPA waters must be of such quality that they are suitable for the designated uses of drinking water after disinfection, recreation in and on the water, fishing, agriculture, industrial process and cooling water supply, hydroelectric power generation, navigation, and as habitat for fish and other aquatic life. The habitat must be characterized as natural” (Maine State Government 2007b).

“Class GPA waters shall be described by their trophic state based on measures of the chlorophyll *a* content, Secchi Disk Depth (SD), total phosphorus content, and other appropriate criteria.” Water quality standards for Maine indicate that class GPA waters “shall have a stable or decreasing trophic state, subject only to natural fluctuations, and shall be free of culturally induced algal blooms” (Maine State Government 2007b). Bloom conditions are defined as SD measurements of less than 2 meters in lakes having color less than 30 standard platinum units (SPU). Lakes that chronically (more than 5 of the past 10 years) show algal blooms are not in attainment of state water quality standards.

EPA Ecoregion 8 water quality criteria (Table 3; U.S. Environmental Protection Agency 2000a, 2000b) are also used as a benchmark in this report. EPA water quality criteria for nutrients help translate narrative criteria within State or Tribal water quality standards by establishing values for causal variables (e.g., total nitrogen and total phosphorus) and response variables (e.g., turbidity and chlorophyll *a*). Causal variables are necessary to provide sufficient protection of designated uses before impairment occurs and to maintain downstream uses. Early response variables are necessary to provide warning signs of possible impairment and to integrate the effects of variable and potentially unmeasured nutrient loads.

Table 3. EPA Ecoregion 8 nutrient criteria.

Nutrient Criteria	Streams	Lakes
Total Phosphorus	10 µg/L	8 µg/L
Total Nitrogen	0.38 mg/L	0.24 mg/L
Chlorophyll <i>a</i>	0.63 µg/L	2.43 µg/L
Secchi disk depth	N/A	4.93 m

These criteria were developed specifically for Ecoregion 8 (which includes the entire states of Maine, New Hampshire, and Vermont) and are designed to represent conditions of surface waters that are minimally impacted by human activities and thus protect against the adverse effects of nutrient over-enrichment from cultural eutrophication. The values are EPA’s scientific recommendations regarding ambient concentrations of nutrients that protect aquatic resource quality. They do not have any regulatory impact or meaning.

For lakes (waterbodies greater than 10 acres and with mean water residence time of 14 or more days; U.S. Environmental Protection Agency 2000a), the criteria were established based on the lower 25th percentile of lakes that EPA found data for. This percentile is expected to approximately correspond to the 75th percentile of reference (undisturbed) lakes. In other words, 75% of lakes in the ecoregion do not meet the criteria, nor do roughly 25% of reference lakes. For streams and rivers, a parallel approach was used to establish the nutrient criteria (U.S. Environmental Protection Agency 2000b).

Results

Monitoring results for 2014 are displayed in scatter-plot graphs showing all data for each site for a given parameter. The scatter plots of 2014 data are overlaid on box plots representing the overall range and distribution of data values collected from 2006 through 2014 for the specified parameter and site (Appendix A contains all data in tabular form). A box plot (Figure 2) is a summary plot that graphs data as a box representing statistical values. The boundary of the box closest to zero indicates the 25th percentile, a line within the box marks the median, and the boundary of the box farthest from zero indicates the 75th percentile. Whiskers (error bars) above and below the box indicate the 90th and 10th percentiles respectively. Outliers are displayed as black filled circles. At least nine data points are required to compute the 5th, 10th, 90th and 95th percentiles. If a percentile point is unable to be computed, that set of points is not drawn. If EPA or other water quality criteria exist for a particular parameter they are displayed on the graphs as specification lines.




Figure 2. Explanation of box plot graph.

Water Quality

Measures of water quality include specific conductance, pH, water temperature, dissolved oxygen (DO), acid neutralizing capacity (ANC), and apparent color. Assessment of water quality data aids in the interpretation of the biotic condition and ecological processes of surface water resources.

Specific Conductance

Specific conductance (shown for lakes in Figure 3 and streams in Figure 4) is a measure of the ability of water to carry an electrical current, and is directly related to the level of dissolved ions in the water. An increase in specific conductance can be an indicator of pollutants in the water. Naturally occurring values range from less than 20 to more than 1,000 microsiemens per centimeter ($\mu\text{S}/\text{cm}$). Specific conductance values from 2014 were within the appropriate range for low ionic strength waters, and values were generally within the ranges recorded in previous years. Two notable exceptions were Echo Lake, which was above the 90th percentile from July through September, and

Upper Breakneck Pond which was at or above the 90th percentile during May and June. Most of the stream sites had elevated conductance measures during October.




Figure 3. Lake and pond specific conductance from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating sites with data from 2008, 2011, and 2014 only.




Figure 4. Stream specific conductance from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating partial-record sites with data from 2006, 2008, 2010, 2012, and 2014 only.

pH

The pH of a water body reflects how acidic or basic the water is, measured on a scale of 1 to 14, with 7 being neutral. Measurements below 7 are considered acidic, while measurements above 7 are considered alkaline. A one unit change in pH represents a 10-fold change in acidity or alkalinity. Maine has no numeric water quality standard for pH, but standards of most northeast states indicate that a pH between 6.5 and 8.0 is within the acceptable range. Most historic lake and pond pH values from Acadia tend to be slightly acidic, which is typical of poorly-buffered, unproductive Maine waters. Almost all lake and pond pH values from the 2014 monitoring season (Figure 5) were higher than in past years, and most of the larger, oligotrophic lakes (Bubble, Eagle, Echo, Jordan) had pH values consistently above the 75th percentile of the box plots. Even some of the smaller sites that are rimmed by sphagnum dominated wetlands (which sometimes can contribute natural acidity to the system) had the majority of 2014 pH values above the overall median value for the respective site.




Figure 5. Lake and pond pH from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating sites with data from 2008, 2011, and 2014 only.

The majority of stream pH measurements in 2014 (Figure 6) were generally acidic with similar (though slightly less pronounced) increases in pH over historic values as seen in the lakes and ponds. Heath Brook is downstream of wetlands that contribute organic acidity and in turn lower stream pH. Cadillac Brook is a high-elevation stream site, susceptible to episodic acidification from acid deposition due to the minimal buffering of the granite bedrock and thin soils. A defective pH probe precluded most May pH measurements in streams, excepting Cadillac and Hadlock Brooks which were monitored after the probe was replaced.




Figure 6. Stream pH from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating partial-record sites with data from 2006, 2008, 2010, 2012, and 2014 only.

Temperature

Temperature can affect water chemistry and biology. For example, the amount of dissolved oxygen that water can hold is directly related to the temperature of the water. The higher the temperature, the less dissolved oxygen water can hold, which can be observed in both diel (day and night) and seasonal shifts (although these shifts are also influenced by fluctuations in photosynthetic activity). Oxygen will naturally decline during the summer months as water temperatures rise. Temperature can also determine the kinds of plants and animals found in a lake, pond or stream. Certain species of fish, insects, and algae will predominate during the cooler temperatures of the spring and fall, yet be less visible and/or abundant during the warmer temperatures of summer. Many July and August lake, pond and stream water temperatures (Figures 7 and 8) were in the upper range of variability in 2014, reflecting the contributions of high air temperature and solar radiation, though May and October values were in the lower range of the historic NETN monitoring data from Acadia.




Figure 7. Lake and pond water temperature (surface) from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating sites with data from 2008, 2011, and 2014 only.




Figure 8. Stream water temperature (surface) from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating partial-record sites with data from 2006, 2008, 2010, 2012, and 2014 only.

Dissolved Oxygen

Dissolved oxygen (DO) is a critical indicator of water quality because aquatic life generally needs DO concentrations at or above 5 mg/L to thrive. Low oxygen concentrations can directly kill or stress organisms such that they will not be able to successfully reproduce or grow. Water with less than 1 mg/L of oxygen is considered anoxic (no oxygen present). The surface layers of all ACAD lakes and ponds monitored in 2014 were well oxygenated (Figure 9). Mid-summer DO profiles of some of the shallow, more productive lakes such as Witch Hole Pond showed some moderate oxygen depletion at lower depth, likely caused by biological activity and low redox (chemical reduction-oxidation reaction) potential in proximity of the lake bottom. As water temperatures rise and temperature stratification is established in deeper lakes, variation in water density can also inhibit oxygen replenishment to deeper waters. The complete profile data are provided in Table A2 in Appendix A.




Figure 9. Lake and pond dissolved oxygen (surface) from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating sites with data from 2008, 2011, and 2014 only.

Although Maine has no numerical dissolved oxygen minimum standards for Class AA streams, which includes all streams in Acadia, the DO content of Class A waters (the next lowest classification) is required to be above 7 mg/L. As seen in Figure 10, several of the 2014 DO measurements from Aunt Betty's Pond Inlet, Cadillac Brook, and Heath Brook were below this standard. These measurements were taken during periods of low water level and minimal streamflow.




Figure 10. Stream dissolved oxygen (surface) from 2014 YSI sonde in-situ measurements overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating partial-record sites with data from 2006, 2008, 2010, 2012, and 2014 only.

Acid Neutralizing Capacity

Acid neutralizing capacity (ANC) is also known as alkalinity, or buffering capacity. It is due primarily to the presence of naturally available bicarbonate, carbonate, and hydroxide ions, with bicarbonate being the major form. Most states do not have numerical criteria for ANC in their water-quality standards. ANC values greater than 100 $\mu\text{eq/L}$ are considered well-buffered, while values less than zero typify acidic waters (Stoddard et al. 2003). Acadia surface waters are generally poorly buffered, a result of chemically-resistant granite bedrock, thin (or absent) soils, and steep slopes with rapid runoff (Kahl et al. 2000). In lakes, ponds, and streams, spring 2014 ANC measurements followed the typical seasonal pattern of being lower than summer values. This is likely due to the contribution of episodic acidification from spring snowmelt and runoff. Several lake and pond ANC values were among the highest recorded in Acadia since the start of NETN monitoring.




Figure 11. Lake and pond acid neutralizing capacity from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating sites with data from 2008, 2011, and 2014 only.

Stream ANC (Figure 12) exhibited much greater seasonal variability than lake ANC values, and many of the summer (August) stream ANC measurements were considerably higher than those from the lakes. Some of the higher elevation streams (Cadillac, Hadlock, and Sargent) had the lowest ANC values, along with Heath Brook, which is surrounded by naturally acidic wetlands.




Figure 12. Stream acid neutralizing capacity from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating partial-record sites with data from 2006, 2008, 2010, 2012, and 2014 only.

Apparent Color

Color in pond and stream water is caused by natural metallic ions, humus and peat materials, plankton, weeds, and industrial wastes. Color is reported in Platinum-Cobalt (Pt-Co) units (PCU). Apparent color (the measurement method utilized by NETN) is determined on original samples without filtration. Color can be a rough indicator for organic acidity.

Water bodies with apparent color values greater than 25 PCU are considered to be highly colored, and often exhibit reduced water clarity and high phosphorus concentrations. Values of color are usually not included in water quality standards, except to note that they should be as naturally occurs.

Color values from the larger, deeper Acadia lakes were low, both in 2014 samples and in the 2006 to 2014 data (Figure 13). The shallower, more productive lakes and ponds were moderately to highly colored and historic measurements were more variable. This generally reflects the contribution of dissolved organic carbon (DOC) and other organic acidity. Direct measurements of lake, pond, and stream DOC began in 2012 and are graphed in the following section.




Figure 13. Lake and pond apparent color from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating sites with data from 2008, 2011, and 2014 only.

Stream apparent color values (Figure 14) were generally low, with the exception of Heath and Marshall Brooks and Aunt Bettys Pond Inlet. Upstream wetlands likely influence the color levels of these streams. The more moderately elevated values in Otter Creek, and Kebo, Sargent and Stanley Brooks could be the effect of runoff and sediment input to the systems from the adjacent roads, carriage roads and erosion from the upstream watershed.




Figure 14. Stream apparent color from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating partial-record sites with data from 2006, 2008, 2010, 2012, and 2014 only.

Dissolved Organic Carbon

Measurement of dissolved organic carbon by NETN began in 2012. Carbon is a nutrient required for biological processes. Sources of organic carbon in water include humic substances from plant and soil organic matter, wetland peat deposits, and atmospheric deposition. Certain forms of DOC can contribute to “tea” color in water, which can affect light attenuation. DOC is also an important part of the energy balance and acid-base chemistry in many freshwater systems. It also affects the transport (solubility and bioavailability) of metals, including mercury, in aquatic systems.

DOC values from Acadia lakes and ponds (Figure 15) were closely related to apparent color values and exhibited very little seasonal change. As expected, the deeper, less productive lakes had lower DOC concentrations in addition to lower apparent color values. The shallower, more productive lakes and ponds had more moderate DOC concentrations and historic measurements were more variable. These ponds all are surrounded by wetlands that contribute organic acidity.




Figure 15. Lake and pond dissolved organic carbon (DOC) from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2012-2014. Sites marked with an asterisk (*) are rotating sites with data from 2014 only.

DOC values from Acadia streams (Figure 16) were similar to lake and pond DOC values. Streams with higher DOC concentrations (Aunt Bettys Pond Inlet, and Heath and Marshall Brooks) also had higher color values, and drain wetlands that are high in organic matter.





Figure 16. Stream dissolved organic carbon (DOC) from 2014 spring and summer water samples overlaid on a box plot of measurements taken from 2012-2014. Sites marked with an asterisk (*) are rotating sites with data from 2012 and 2014 only.

Transparency

Transparency measurements can provide simple and affordable assessments of pond and lake productivity. Variation in precipitation is one of the major factors contributing to annual shifts in transparency. Often during drier conditions lakes and ponds will become clearer due to lower runoff of nutrient and soil inputs. In contrast, decreased transparency readings can often be attributed to the effects of high levels of spring and fall precipitation, as well as the cumulative effects of a high rainfall year.

2014 Secchi disk transparency measurements (Figure 17) in the majority of the lakes and ponds were distributed close to historical values for NETN monitoring at Acadia. Transparency depths in smaller and more productive lakes and ponds can frequently be greater than the water depth, and the clarity of these lakes can be better assessed using a radiation sensor to obtain light penetration profiles. Round Pond, Upper Breakneck Pond, and Lake Wood were in this category in 2014, and Secchi transparency was not measured at these sites.



Missing August value from Jordan Pond due to lost Secchi disk

Figure 17. Secchi disk transparency from 2014 monthly measurements overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating sites with data from 2008, 2011, and 2014 only.

Light Penetration Profiles

Nearly all the energy that drives and controls lake processes is derived from solar energy, which is converted to chemical energy via photosynthesis. For this reason, light penetration profiles can tell us much about the trophic conditions affecting lakes and ponds. This chemical energy is then transported to other areas of the ecosystem as various forms of organic matter. Solar energy, absorbed by the lake and dissipated as heat, plays a large role in defining a lake's thermal structure, stratification, and circulation patterns. These factors in turn affect nutrient cycling and the distribution of dissolved gasses. By understanding the quantity and behavior of the light entering a lake system, we can learn more about how the light is utilized in the system (Wetzel and Likens 2000). Light penetration profiles are used to measure light attenuation in Jordan Pond (since this pond's clarity is of special interest to park managers and researchers) and the Acadia lakes that are too shallow for use of a Secchi disk.

A light penetration profile is obtained using two solar radiation sensors and a datalogger to determine photosynthetically active radiation (PAR). One of the sensors is lowered into the water column on a weighted lowering frame, while the second sensor ("deck cell") is left on the surface to record ambient light. The datalogger records and processes readings from both sensors, dividing the measurement of light reaching any given depth by the measurement of ambient light, to yield a proportion (often expressed as a percentage). Measurements are taken at 1-meter increments of the water column until the light penetration drops below 1%. A light attenuation coefficient can be calculated through analysis of the profile data to quantify the loss of light transmission per meter of depth. A low attenuation coefficient denotes clear water and, conversely, a higher coefficient signifies reduced water clarity. Graphs of 2014 light penetration profiles and a listing of light attenuation coefficients are found in Figures 18 through 21. Full profile data from measurements made in 2014 are listed in Table A6 in Appendix A.




Figure 18. Light penetration profiles from Jordan Pond.




Figure 19. Light penetration profiles from Lake Wood.




Figure 10. Light penetration profiles from Round Pond




Figure 21. Light penetration profiles from Upper Breakneck Pond

Turbidity

Turbidity is the measure of the relative clarity of a liquid. It is measured by passing light through a water sample to determine how much light is scattered, and the results are reported in nephelometric turbidity units (NTU). Turbidity is caused by suspended matter or impurities that interfere with the clarity of the water. These impurities may include clay, silt, finely divided inorganic and organic matter, soluble colored organic compounds, and plankton and other microscopic organisms. In natural waters, turbidity is often used as an indicator of water quality and productivity. Turbidity is measured in the field using an electronic meter.

Turbidity in the water can create aesthetic, ecological, and health issues. Turbid water may indicate runoff from construction, roads, agriculture or other types of pollution. Suspended sediment can carry nutrients and pesticides throughout the water system. Suspended particles near the surface absorb additional heat from sunlight, raising the water temperature. High turbidity levels can reduce the amount of light reaching lower depths of lakes and streams, which can inhibit growth of submerged aquatic plants, and can interfere with the ability of fish gills to absorb dissolved oxygen. The majority of the turbidity values measured in Acadia streams during 2014 (Figure 22), the 3rd year of NETN turbidity testing, were less than 2 NTU, in the low range of dry-weather turbidity of surface waters (U.S. Environmental Protection Agency 1999).




Figure 22. Stream turbidity from 2014 monthly measurements overlaid on a box plot of measurements taken from 2012-2014. Sites marked with an asterisk (*) are rotating sites with data from 2012 and 2014 only.

Nutrient Enrichment

Nutrient enrichment and the acceleration of eutrophication have been identified in most NETN parks as one of the stressors of greatest concern. Total phosphorus and several forms of nitrogen are measured to give managers information regarding the trophic status and productivity of freshwater systems.

Phosphorus

Phosphorus (P) is one of the major nutrients needed for plant growth. It is generally present in small amounts in natural freshwater systems and typically limits the plant growth in streams and ponds. Several forms of phosphorus were tested, and total phosphorus (TP) was selected to be the most meaningful measure of this nutrient. TP is a measure of both inorganic and organic forms of phosphorus, and is the common water quality standard or criteria metric. Total dissolved phosphorus (TDP) and soluble reactive phosphorus (SRP) were also measured for several seasons, but were discontinued in 2012.

In 2014, most TP concentrations in lakes (Figure 23) were low, and the majority were below the EPA Ecoregion 8 criterion of 8 µg/L for lakes and ponds. Although Round Pond and Witch Hole Pond (and the August Lake Wood) values were above this criterion, they were within the expected range for shallow, relatively productive ponds. As described above (“Water Quality Standards”), the EPA criteria do not have any regulatory meaning.




Figure 23. Lake and pond total phosphorus (TP) from 2014 spring and summer water samples. The data are overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are

rotating sites with data from 2008, 2011, and 2014 only. There is no numeric Maine state water quality TP standard.

Total phosphorus concentrations in streams (Figure 24) were also generally low in 2014. Most TP values were below the EPA Ecoregion 8 criterion of 10 µg/L for streams.




Figure 24. Stream total phosphorus (TP) from 2014 spring and summer water samples. The data are overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating partial-record sites with data from 2006, 2008, 2010, 2012, and 2014 only. There is no numeric Maine state water quality TP standard.

Nitrogen

Total nitrogen (TN) is a measure of all forms of nitrogen (organic and inorganic). Nitrogen, often the limiting nutrient in marine waters, is an essential plant element and can also be the limiting nutrient in some freshwater systems. The importance of nitrogen in the aquatic environment varies according to the relative amounts of the forms of nitrogen present, including nitrate, nitrite, and ammonia. Nitrate (NO₃) is the most oxidized and stable form of nitrogen in a water body, and is the primary form of nitrogen used by plants. Nitrite (NO₂) is an unstable form of nitrogen that is either rapidly oxidized to nitrate (nitrification) or reduced to nitrogen gas (de-nitrification). This form of nitrogen

can also be used as a nutrient source for plants. Ammonia (NH_3) is generated by bacteria as a decomposition product of nitrogenous organic compounds, and is also readily assimilated by plants. Results of NO_3 , NO_2 , and NH_3 tests are all reported as the concentrations of the N component of these compounds, expressed in mg/L.

Total nitrogen in lakes and ponds (2014) are shown in Figure 25. Most lake and pond TN measurements were in the low range, with most values near or below the EPA Ecoregion 8 criterion of 0.24 mg/L (for lakes), although like TP this criterion does not have regulatory meaning. Nitrate results for lakes were very low, with many values below the method reporting limit of 0.014 mg/L (Appendix A, Table A3). Changes in instrumentation in the analytical lab facilitated detection of lower levels of ammonia and nitrite than in previous years, although 2014 concentrations of nitrite in lake samples were all below the method reporting limit.




Figure 25. Lake and pond total nitrogen (TN), the nitrogen component of nitrate ($\text{NO}_3\text{-N}$) and ammonia (NH_3) from 2014 spring and summer water samples. The data are overlaid on a box plot of TN measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating sites with data from 2008, 2011, and 2014 only.

Stream TN measurements (Figure 26) were also low, with all but one value below the EPA Ecoregion 8 criterion of 0.38 mg/L (for streams). Stream $\text{NO}_3\text{-N}$ values were higher than those of lakes, but still in the low range, with several results below the method reporting limit. Ammonia values were all very low, and as with lakes, concentrations of nitrite in Acadia stream samples were all below the method reporting limit.




Figure 26. Stream total nitrogen (TN) and the nitrogen component of nitrate ($\text{NO}_3\text{-N}$) and ammonia (NH_3) from 2014 spring and summer water samples. The data are overlaid on a box plot of TN measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating partial-record sites with data from 2006, 2008, 2010, 2012, and 2014 only.

Chlorophyll *a*

The amount of chlorophyll *a* in a water sample is a measure of the concentration of suspended phytoplankton and can be used as an indicator of algal biomass and thus of water quality.

Chlorophyll *a* is responsible for photosynthesis and is found in various forms within the living cells of algae, phytoplankton, and other aquatic plant matter. Like other biological response variables, chlorophyll *a* tends to integrate the stresses of various parameters over time, and thus is often an important nutrient-stress parameter to measure.

Chlorophyll *a* concentrations in most ACAD lakes and ponds were low in 2014 (Figure 27), which indicates relatively low algal productivity. Summer 2014 chlorophyll *a* concentrations in Round and Seal Cove Ponds were higher than the other monitored ACAD lakes and ponds, but were within the expected range for these moderately productive ponds and did not indicate evidence of any major algal blooms.




Figure 27. Lake and pond chlorophyll *a* from 2014 spring and summer water samples. The data are overlaid on a box plot of measurements taken from 2006-2014. Sites marked with an asterisk (*) are rotating sites with data from 2008, 2011, and 2014 only.

Other Analytes

Chloride

Chloride is one of the major negatively-charged ions in fresh water systems. The chloride content of natural surface waters will depend to a great extent on the geology of the area. Concentrations are generally greater in lakes that are in proximity to marine regions. Another source of chloride is road run-off from de-icing materials. Chloride is important in terms of metabolic processes, as it influences osmotic salinity balance and ion exchange.

Chloride concentrations in ACAD lakes and ponds were in the low to moderate range in 2014 (Figure 28). Echo Lake chloride levels were considerably higher than all of the other lakes and were at the upper end of the range of historic test results (all ACAD lakes mean = 336.2 $\mu\text{eq/L}$, 10th percentile = 252.3 $\mu\text{eq/L}$, 90th percentile = 384.3 $\mu\text{eq/L}$) which includes data from Acadia's lake acidification sampling program dating back to 1982. Spring (May) chloride concentration in Upper Hadlock Pond was also in the high range for that pond. Echo Lake and Upper Hadlock Pond are both located adjacent to major roadways, and run-off of salts from winter road treatment is a possible explanation for elevated chloride concentrations. Upper Breakneck Pond had higher Cl measurements than most of the other ponds, although it is not located near any treated roads. No historic chloride data exist for Upper Breakneck Pond.

Chloride concentrations in ACAD streams were in a similar range to lake and pond values (Figure 29), with two significant outliers. Marshall Brook and Stanley Brook levels were significantly higher than all of the other streams, but both of these streams were within their respective historic ranges. Both of these streams cross or are adjacent to treated roads, and the sampling sites are downstream of residential, commercial, and municipal influences. Even the highest chloride concentrations in Acadia lakes, ponds and streams are well below the U.S. Environmental Protection Agency recommended chronic criterion concentration for aquatic life of 230 milligrams per liter (6,488 $\mu\text{eq/L}$) (U.S. Environmental Protection Agency 2002).




Figure 28. Lake and pond chloride from 2014 spring and summer water samples. The data are overlaid on a box plot of measurements taken from 2012-2014. Sites marked with an asterisk (*) are rotating sites with data from 2014 only.




Figure 29. Stream chloride from 2014 spring and summer water samples. The data are overlaid on a box plot of measurements taken from 2012-2014. Sites marked with an asterisk (*) are rotating sites with data from 2012 and 2014 only.

Sulfate

Sulfate is found in most natural waters, originating from watershed geology, soils, and precipitation. Sulfate can play a major role in acidification of lakes and streams. Sulfate concentrations in sensitive Maine lakes have declined significantly since 1982, in part due to the 1995 implementation of Phase I controls of the Clean Air Act Amendments and in part to other long-term pollution reduction efforts (Kahl 1999).

Sulfate concentrations in ACAD lakes and ponds were low in 2014 (Figure 30) and in the lower range of the historic test results, including data from Acadia's lake acidification sampling program (all ACAD lakes mean = 63.9 $\mu\text{eq/L}$, 10th percentile = 2.5 $\mu\text{eq/L}$, 90th percentile = 97.8 $\mu\text{eq/L}$).




Figure 30. Lake and pond sulfate from 2014 spring and summer water samples. The data are overlaid on a box plot of measurements taken from 2012-2014. Sites marked with an asterisk (*) are rotating sites with data from 2014 only.

Although a few sites were slightly higher than lake and pond values, sulfate concentrations in ACAD streams were also relatively low (Figure 31).




Figure 31. Stream sulfate from 2014 spring and summer water samples. The data are overlaid on a box plot of measurements taken from 2012-2014. Sites marked with an asterisk (*) are rotating sites with data from 2012 and 2014 only.

Water Quantity

Stream Discharge

Monthly stream discharge measurements (Figure 32), taken with a current meter and wading rod, can be used to calculate loading of nutrient chemical constituents (flow X concentration), and also provides a record of variations in stream flow. Stream stage (height of water) measurements can be paired with discharge values and over time a stage to discharge relationship can be calculated. Once this relationship is established, investigators can interpolate the stream discharge from the stage measurement alone. Numerous discharge measurements at all ranges of streamflow are required to establish and maintain an accurate stage to discharge relationship. Most streams in Acadia have relatively low flow, although several 2014 discharge measurements were in the higher range in May and early July. This differed from the usual seasonal pattern where most flow drops to minimal levels in July and August, with some higher measurements in September. There were no high volume precipitation events in early fall, and consequently September and October stream discharge was very low. Recovery finally began in early November.




Figure 32. Monthly stream discharge measurements from partial and continuous record sites.

NETN staff continues to review discharge and stage measurement methodology and quality assurance/quality control procedures in order to enhance the quality and utility of the water quantity data. Stage to discharge relationship graphs will be produced once sufficient data are collected.

The Otter Creek continuous-record streamflow gage (USGS station 01022840) was installed by USGS in 2006 and is maintained as an index of streamflow for all stream resources at ACAD. This gage provides detailed streamflow information about one stream in the park, allowing for estimates of loads of constituents at this site, and also provides data to make estimates of streamflow at hydrologically similar un-gaged sites or partial-record sites. Figure 33 is a graph of the continuous discharge measurements at Otter Creek for the 2014 calendar year. Real-time data for this site are available at

http://waterdata.usgs.gov/me/nwis/dv/?site_no=01022840&PARAMeter_cd=00060,00065.




Figure 33. Daily mean discharge from the Otter Creek continuous record site for calendar year 2014.

Stream and Lake Stage

Monthly (stream) and weekly (lake and pond) stage measurements were taken by measuring to the water surface from a fixed datum point. Stream stage was measured during regular monthly monitoring visits to the rotating partial record sites, and the data (stage and discharge) from these visits in 2014 are listed in Table A4 in Appendix A. Discharge and stage were measured continuously, year-round, at the Otter Creek site, and stream stage was measured continuously throughout the ice-free season at the Cadillac Brook and Hadlock Brook permanent record sites. The Hadlock Brook datalogger malfunctioned in September preventing data collection at that site for the remainder of the year. Daily mean stream stage values at these permanent record sites from the 2014 monitoring season are graphed in Figure 34.




Figure 34. Daily mean stream stage measured in 2014 at NETN permanent record stream monitoring sites in Acadia NP.

Lake stage was measured weekly at all NETN lake monitoring sites throughout the ice-free season. Weekly lake stage data for the 2014 monitoring season is displayed in Figure 35.




Figure 35. Weekly lake stage measured in 2014 at NETN monitoring sites in Acadia NP.

Invasive Aquatic Plants

NETN's methods for invasive aquatic plant monitoring were adapted from the Maine Center for Invasive Aquatic Plants (MCIAP), a division of the Maine Volunteer Lake Monitoring Program (VLMP). In Acadia, investigators utilize a Level 1 survey, which concentrates on areas of public access and other areas of concentrated boat traffic. Boat launch survey areas extend horizontally along the shoreline at least 100 meters (~300 ft) on either side of the boat launch area, and offshore along the entire length to the depth at which rooted plants are no longer observed (the outermost extent of the littoral zone.) Detailed survey instructions can be found in the NETN protocol (Lombard et al. 2006) and in the MCIAP manual (Maine Center for Invasive Aquatic Plants 2011).

The primary targets of the invasive plant surveys were the 11 plants currently listed by the MCIAP (Table 4). Monitoring is conducted by Acadia National Park staff and volunteers who have received MCIAP training in survey methods and plant identification. The *Maine Field Guide to Invasive Aquatic Plants and their Common Native Look Alikes* (Maine Center for Invasive Aquatic Plants 2007) is used to aid identification in the field, and suspect plants can be sent to the MCIAP for expert identification.

In 2014, invasive aquatic plant monitoring was conducted at Eagle Lake, Echo Lake, Jordan Pond, Long Pond, Seal Cove Pond, and Upper Hadlock Pond. Results indicated that target invasive aquatic plants do not currently exist at any of the sites monitored in Acadia.

Table 4. Maine Center for Invasive Aquatic Plants species of concern.

Common name	Latin name
European Frogbit	<i>Hydrocharis morsus-ranae</i>
Water Chestnut	<i>Trapa natans</i>
Yellow Floating Heart	<i>Nymphoides peltata</i>
Eurasian Water Milfoil	<i>Myriophyllum spicatum</i>
Variable Water Milfoil	<i>Myriophyllum heterophyllum</i>
Parrot Feather	<i>Myriophyllum aquaticum</i>
Fanwort	<i>Cabomba caroliniana</i>
Hydrilla	<i>Hydrilla verticillata</i>
Brazilian Elodea	<i>Egeria densa</i>
European Naiad	<i>Najas minor</i>
Curly-Leaved Pondweed	<i>Potamogeton crispus</i>

During future visits to all NETN parks, monitoring crews will be increasingly attentive for the presence of Didymo (*Didymosphenia geminata*), also known as “rock snot,” a highly invasive alga that has recently invaded the northern reaches of the Connecticut River in New Hampshire, and in the

White and Battenkill Rivers in Vermont. This species has a great potential to alter habitats and displace native species, and is of great concern to officials in regions where infestations have been established.

Didymo can easily be spread by waders and potentially by water monitoring equipment and other gear that touches the bottoms of streams in infested areas. Just one cell of the alga breaking off and drifting downstream can spread the alga. Enhanced equipment cleaning and decontamination procedures are included in the latest NETN monitoring protocol revision (Gawley et al. 2014).

Since non-native, invasive plants have recently been detected with increasing frequency in New England lakes and ponds, it has become crucial to closely monitor the status of park waters. The early detection of an infestation can make eradication or control more feasible, and it can lead to efforts that reduce the spread of the plant to neighboring water bodies. Designating the early detection of these plants as a NETN vital sign and the ongoing partnership with state and local monitoring and eradication efforts are highly effective prevention strategies.

Other Monitoring

Several additional monitoring activities generating data not included in this report complement the core NETN parameters. Water samples were collected from the eight permanent Acadia NETN lake sites (as well as two additional lakes) in April and October and were analyzed for acid-base chemistry parameters. Results from 2014 were similar to those of the past several years, and suggest that the Clean Air Act and its subsequent revisions appear to be effective in reducing the effects of acid deposition.

Rapid hydro-geomorphic assessment evaluations of stream characteristics were conducted in July at each stream in the yearly rotation. These evaluations provide a qualitative assessment of conditions upstream and influencing the stream discharge and sampling site. This information supports stream discharge, in situ chemistry, and nutrient sampling analyses, and supplements observations of obvious changes in stream characteristics that are noted on monthly stream data forms. The NETN assessment techniques were adapted from the EPA Rapid Bioassessment protocol (Barbour et al. 1999), and were implemented utilizing a standard operating procedure (SOP) that was completed in December 2011.

ACAD staff also sampled benthic macroinvertebrates in five streams (Duck Brook, Hunters Brook, Marshall Brook, Sargent Brook and Stanley Brook) in August 2014, as part of an annual monitoring program conducted in cooperation with the Maine Department of Environmental Protection (MDEP). Products of this activity include identification of all collected organisms to the species level, voucher specimens, and analysis of taxonomic diversity and richness. A MDEP modeling program determines a stream water quality classification rating based on the taxonomic data. Duck, Hunters, and Stanley Brooks received “A” model determinations, attaining their “AA” statutory classification. Marshall Brook was determined to be Class B (and is scheduled to be re-sampled in 2015), and Sargent Brook received an “I” (incomplete) classification because several of the samplers were not submerged during the entire sample interval due to low stream water level.

Quality Assurance and Quality Control (QA/QC)

QA/QC is important to the success of a long-term data collection and trend detection program. Quality assurance (QA) is achieved through the establishment and use of the NETN Freshwater Monitoring Protocol. Specific procedures are used to control critical components of a project such as sampling at the right place with the right equipment and using the right methods. Over the years, staff will change, equipment may be updated, and methods may evolve. Although these changes will be kept to a minimum, changes are inevitable and therefore following an established and well-documented protocol will ensure that the data remain valid.

QA requirements incorporated in the protocol include consistency and low turnover in project leaders and staff, consistency in staff training and oversight, consistency in equipment used and calibration methods, the selection of a well-established chemical laboratory with a proven track record, and a robust sample design that includes an adequate number of field and laboratory quality control (QC) samples.

QC includes the assessment of bias and variability through the use of additional samples such as blank and replicate samples. QC samples are an objective assessment of whether or not QA protocols are adequate. The protocol calls for the collection of two blank and two replicate samples (one each from lakes/ponds and streams, respectively) during both the spring and summer nutrient sampling months at Acadia NP, and the same number, distribution, and schedule at the combined 8 “Lower NETN” parks. Sample collection sites are selected at random from both monitoring groups.

Field QC Replicate Measurements

The 2014 protocol revision requires in situ measurements, including Secchi transparency, sonde water quality, and stream discharge, to be periodically replicated to ensure that field equipment and observers are performing within the required precision standards. Water quality sonde temperature, pH and specific conductance measurements are to be compared monthly in the laboratory with similar measurements made with a NIST-traceable thermometer and benchtop pH and conductivity meters. Sonde dissolved oxygen measurements will be compared in the field to measurements made using a LaMotte dissolved oxygen test kit (Winkler titration method). The majority (>90%) of the results of these comparison procedures were within the desired limits. When replicates were outside of desired limits, equipment was recalibrated, repaired, or adjusted and/or observers were retrained to achieve acceptable results in subsequent replicate tests.

Nutrient QC Sample Results

Analysis results of all 2014 blank samples collected from Acadia NP lakes, ponds, and streams (Appendix B, Table B1) were below or near the method reporting limits, indicating little or no contamination was introduced during the sampling, handling and analysis processes. However, new instrumentation utilized at the analytical lab in June and August provided lower detection and reporting limits for several analytes (NO_2 , NH_3 , SO_4), allowing quantification of some levels of possible contamination not detected in the past. Consultation with laboratory manager is recommended to view laboratory blank results and determine if very low NO_2 and NH_3 values in field samples were representative of natural conditions or analytical noise. Replicate sample analysis

results (Appendix B, Table B2) showed that most Acadia samples were in the acceptable range of precision (relative percent difference or precision objective in units, depending on sample concentration). Two total nitrogen and one chloride sample pairs were significantly above the acceptable percent difference and may reflect very low level contamination.

Summary

The majority of the 2014 water quality parameters for the lakes and streams monitored in Acadia National Park were within state standards, and most are very close to EPA Ecoregion 8 criteria, where applicable. Nearly all of the values were within the ranges of historic NETN monitoring data from ACAD. ANC and pH measurements continued to exhibit slightly higher summer values, a recent trend which may reflect a reduction of acid deposition effects.

Apparent color and transparency measurements indicate that Acadia lake and pond waters remained clear, and there were no major runoff or sediment loading events detected by 2014 monitoring data. Nutrient levels (phosphorus and nitrogen) remained relatively low in 2014, and chlorophyll *a* measurements suggested that most lakes retained their minimal to moderate productivity status. The slightly elevated nutrient values in Round, Upper Breakneck and Witch Hole Ponds are not a major concern in these small, naturally productive lakes, and all 2014 values were within historic NETN values. The summer TP concentration in Lake Wood was relatively high for that water body, but the lake did not have a chlorophyll *a* value that would reflect a major algal bloom. Round Pond had the highest summer 2014 chlorophyll *a* value of all the lakes and ponds. Future test results from all of these ponds must be carefully considered to determine whether nutrient enrichment from anthropogenic sources is becoming a chronic problem.

Stream chemistry values in 2014 were generally low to moderate, with Aunt Bettys Pond Inlet, Heath Brook and Marshall Brook samples possessing higher concentrations of apparent color, DOC, TP and TN. These values can likely be attributed to the influence of substantial peat and sphagnum dominated wetlands in the headwaters of the three streams. Monthly turbidity tests showed little evidence of sediment input or other runoff-related issues. Monitoring at the Stanley Brook site showed little to no evidence of negative effects from a substantial ongoing soil erosion source (from municipal stormwater discharge) upstream of the sampling site.

Monthly streamflow measurements from partial record sites and continuous-record streamflow gage data have been effective at tracking water quantity in the park and can aid the quantification and interpretation of other water quality data such as the estimation of nutrient loads. Weekly lake stage measurements have continued to build on a 16-year data history documenting the dynamics of lake water levels. Continued review of and refinements to stage measurement techniques, site selection, and QA/QC methodology; as well as the increased use of continuous dataloggers (full deployment planned for 2015), will enhance the quality and utility of the water quantity data.

Water samples collected from 10 Acadia lake sites in April and October were analyzed for acid-base chemistry parameters. Results from 2014 were similar to those of the past several years, and suggest that the Clean Air Act and its subsequent revisions appear to be effective in reducing the effects of acid deposition.

Benthic macroinvertebrate monitoring in five streams resulted in Duck, Hunters, and Stanley Brooks receiving “A” model determinations, attaining their “AA” statutory classification. Marshall Brook was determined to be Class B (and is scheduled to be re-sampled in 2015), and Sargent Brook

received an “I” (incomplete) classification because several of the samplers were not submerged during the entire sample interval due to low stream water level.

Monitoring under the NETN protocol continues to build on the historic water quality monitoring by park staff and other agencies to provide critical baseline information on the chemical and physical status of the water resources at Acadia National Park. Changes implemented in the 2012 monitoring season have expanded the scope and usefulness of the monitoring data. These changes include taking monthly stream turbidity measurements and the addition of sulfate, chloride, and dissolved organic carbon (DOC) analyses to the spring and summer water chemistry testing. As more data are collected, our ability to detect changes outside this natural range of variability will increase, which in turn will more clearly indicate the status of the vital signs of water quality, nutrient enrichment, water quantity, and the detection of invasive plant species.

Literature Cited

- Barbour, M. T., J. Gerritsen, B. D. Snyder, and J. B. Stribling. 1999. Rapid Bioassessment Protocols for Use in Streams and Wadeable Rivers: Periphyton, Benthic Macroinvertebrates and Fish, Second Edition. EPA 841-B-99-002. U.S. Environmental Protection Agency; Office of Water; Washington, D.C.
- Gawley, W. G., B. R. Mitchell, and E. A. Arsenault. 2014. Northeast Temperate Network lakes, ponds, and streams monitoring protocol. 2014 Revision. Natural Resource Report NPS/NETN/NRR—2013/770. National Park Service, Fort Collins, Colorado.
- Kahl S., 1999. Responses of Maine surface waters to the Clean Air Act Amendments of 1990. EPA CX826563-01-0. Published Report-602094.
- Kahl, J. S., D. Manski, M. Flora, N. Houtman. 2000. Water resources management plan, Acadia National Park, Mount Desert Island, Maine: National Park Service.
- Lombard, P., W. Gawley, J. Caldwell. 2006. Freshwater Vital-Signs Monitoring Plan for National Parks in the Northeast Temperate Network (NETN) PHASE III: Water-Quality Monitoring Protocols in Lakes, Ponds and Streams. USGS, Augusta, Maine, 222 p.
- Maine Center for Invasive Aquatic Plants, 2007, Maine field guide to invasive aquatic plants and their common native look alikes. Maine Volunteer Lake Monitoring Program, 146 p.
- Maine Center for Invasive Aquatic Plants, 2011, Invasive aquatic plant screening survey procedures accessed on March 23, 2012 at: <http://www.mainevlmp.org/wp/wp-content/uploads/2011/03/2011-Screening-Survey-Section-pages.pdf>
- Maine State Government, 2007a, Maine statutes, Title 38, Section 465 accessed on March 23, 2012 at <http://www.mainelegislature.org/legis/statutes/38/title38sec465.html>.
- Maine State Government, 2007b, Maine statutes, Title 38, Section 465-A accessed on March 23, 2012 at <http://www.mainelegislature.org/legis/statutes/38/title38sec465-A.html>.
- Maine State Government, 2011, Maine statutes, Title 38, Section 464 accessed on March 23, 2012 at <http://www.mainelegislature.org/legis/statutes/38/title38sec464.html>.
- Rantz, S.E., et al., 1982, Measurements and computation of streamflow, volumes 1 and 2: U.S. Geological Survey Water-Supply Paper 2175, 631 p.
- Stoddard, J., J. S. Kahl, F. Deviney, D. DeWalle, C. Driscoll, A. Herlihy, J. Kellogg, P. Murdoch, J. Webb, and K. Webster. 2003. Response of surface-water chemistry to the Clean Air Act Amendments of 1990. U.S. Environmental Protection Agency USEPA/620/R-03/001, Washington, DC, 78 p.

- U.S. Environmental Protection Agency. 1999. Guidance Manual for Compliance with the Interim Enhanced Surface Water Treatment Rule: Turbidity Provisions. EPA 815-R-99-010, April 1999.
- U.S. Environmental Protection Agency. 2000a. Nutrient Criteria Technical Guidance Manual, Lakes and Reservoirs. First Edition. EPA-822-B00-001, April 2000.
- U.S. Environmental Protection Agency. 2000b. Nutrient Criteria Technical Guidance Manual, Rivers and Streams. First Edition. EPA-822-B00-002, July 2000.
- U.S. Environmental Protection Agency. 2002. National Recommended Water Quality Criteria: 2002. EPA-822-R-02-047, November 2002.
- Wetzel, R. G. and G. E. Likens. 2000. Limnological Analyses, 3rd ed.: New York, Springer-Verlag

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014.

Table A1. YSI sonde in-situ stream water quality measurements collected at ACAD. *Duplicate values are quality control check measurements.*

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Aunt Betty Pond Inlet	5/13/2014	0.19	17.80	8.44		28
Aunt Betty Pond Inlet	6/5/2014	0.40	15.60	4.93	6.44	46
Aunt Betty Pond Inlet	7/14/2014	0.19	21.20	6.14	6.19	30
Aunt Betty Pond Inlet	8/14/2014	0.26	17.17	7.52	6.54	35
Aunt Betty Pond Inlet	9/10/2014	0.17	17.07	5.41	6.18	40
Aunt Betty Pond Inlet	10/8/2014	0.20	14.28	8.89	6.20	34
Breakneck Brook	5/12/2014	0.18	18.18	9.08		39
Breakneck Brook	6/3/2014	0.18	19.93	8.78	6.88	44
Breakneck Brook	7/10/2014	0.19	24.43	7.72	6.86	44
Breakneck Brook	8/5/2014	0.04	23.22	7.92	7.08	49
Breakneck Brook	9/8/2014	0.07	15.26	9.31	6.87	57
Breakneck Brook	10/7/2014	0.09	12.34	9.55	6.91	64
Cadillac Stream	5/15/2014	0.16	9.42	10.98	6.60	25
Cadillac Stream	6/13/2014	0.15	10.75	10.13	7.04	28
Cadillac Stream	7/9/2014	0.14	15.77	8.82	6.65	25
Cadillac Stream	8/6/2014	0.12	14.85	6.51	6.17	30
Cadillac Stream	9/11/2014	0.07	12.28	3.07	5.49	35
Cadillac Stream	10/15/2014	0.05	12.71	2.77	5.43	42
Hadlock Brook	5/15/2014	0.28	7.21	11.86	6.97	30
Hadlock Brook	6/12/2014	0.20	11.70	10.78	6.87	33
Hadlock Brook	7/17/2014	0.21	14.51	10.08	5.86	22
Hadlock Brook	8/14/2014	0.11	13.77	10.14	6.48	29
Hadlock Brook	9/10/2014	0.12	13.05	9.78	6.49	38
Hadlock Brook	10/16/2014	0.10	13.97	9.33	6.81	42
Hunters Brook	5/8/2014	0.17	8.09	11.98		39

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A1 (continued). YSI sonde in-situ stream water quality measurements collected at ACAD.
Duplicate values are quality control check measurements.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Hunters Brook	6/2/2014	0.17	12.21	10.79	7.06	46
Hunters Brook	7/7/2014	0.18	13.58	10.33	6.70	34
Hunters Brook	8/4/2014	0.08	15.01	9.99	7.00	49
Hunters Brook	9/3/2014	0.10	16.88	9.38	6.89	55
Hunters Brook	10/6/2014	0.10	9.57	11.25	6.99	58
Heath Brook	5/12/2014	0.06	14.34	8.02		33
Heath Brook	6/9/2014	0.07	18.25	4.31	5.57	34
Heath Brook	7/14/2014	0.07	24.97	5.75	5.45	34
Heath Brook	8/7/2014	0.04	24.12	6.10	5.62	38
Heath Brook	9/8/2014	0.05	15.64	5.39	5.59	41
Heath Brook	10/9/2014	0.06	13.84	8.93	5.43	45
Kebo Brook	5/12/2014	0.19	8.88	11.30		27
Kebo Brook	6/4/2014	0.17	8.96	11.19	6.89	32
Kebo Brook	7/17/2014	0.36	14.71	9.88	6.65	21
Kebo Brook	8/6/2014	0.19	14.71	9.08	6.93	38
Kebo Brook	9/9/2014	0.05	12.50	10.09	7.01	49
Kebo Brook	10/6/2014	0.17	10.30	10.35	6.91	53
Marshall Brook	5/19/2014	0.21	9.61	11.25		108
Marshall Brook	6/9/2014	0.22	14.98	10.41	7.18	104
Marshall Brook	7/15/2014	0.06	16.70	9.10	6.81	96
Marshall Brook	8/7/2014	0.18	15.91	9.67	7.11	119
Marshall Brook	9/4/2014	0.11	14.94	9.98	7.13	126
Marshall Brook	10/9/2014	0.16	10.14	10.61	6.86	130
Otter Creek	5/7/2014	0.13	10.02	11.03		29
Otter Creek	6/4/2014	0.19	12.24	10.29	6.74	36
Otter Creek	7/7/2014	0.13	18.22	9.00	6.74	27
Otter Creek	8/4/2014	0.13	17.96	8.95	6.81	37
Otter Creek	9/8/2014	0.04	13.83	9.60	6.40	46

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A1 (continued). YSI sonde in-situ stream water quality measurements collected at ACAD.
Duplicate values are quality control check measurements.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Otter Creek	10/15/2014	0.04	13.08	9.35	6.20	53
Sargent Brook	5/13/2014	0.10	9.27	11.18		27
Sargent Brook	6/5/2014	0.15	10.21	10.56	6.36	28
Sargent Brook	7/14/2014	0.12	16.58	9.08	5.88	27
Sargent Brook	8/14/2014	0.20	14.38	9.95	6.28	26
Sargent Brook	9/10/2014	0.04	12.52	8.37	5.70	29
Sargent Brook	10/8/2014	0.09	12.72	10.06	5.61	29
Stanley Brook	5/8/2014	0.09	9.24	11.51		80
Stanley Brook	6/2/2014	0.06	11.03	11.10	7.16	87
Stanley Brook	7/7/2014	0.14	14.02	10.24	6.91	65
Stanley Brook	8/4/2014	0.06	14.33	10.25	7.22	81
Stanley Brook	9/5/2014	0.07	15.73	9.89	7.11	90
Stanley Brook	10/6/2014	0.12	10.25	11.32	7.01	94

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2. YSI sonde in-situ lake and pond water quality measurements collected at ACAD. *Duplicate values are quality control check measurements collected on the upcast.*

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Bubble Pond	4/28/2014	0.3	7.57	12.13	6.87	30
Bubble Pond	5/30/2014	0.1	13.47	10.35	7.27	31
Bubble Pond	5/30/2014	0.5	13.47	10.35	7.13	31
Bubble Pond	5/30/2014	1.0	13.47	10.33	7.04	31
Bubble Pond	5/30/2014	2.0	13.46	10.31	7.00	31
Bubble Pond	5/30/2014	3.0	13.37	10.32	6.98	31
Bubble Pond	5/30/2014	4.0	13.21	10.30	6.91	31
Bubble Pond	5/30/2014	5.0	13.07	10.26	6.88	31
Bubble Pond	5/30/2014	6.0	13.03	10.25	6.86	31
Bubble Pond	5/30/2014	7.0	12.87	10.23	6.83	31
Bubble Pond	5/30/2014	8.0	12.75	10.22	6.80	31
Bubble Pond	5/30/2014	9.0	12.65	10.16	6.75	31
Bubble Pond	5/30/2014	10.0	12.60	10.13	6.72	31
Bubble Pond	5/30/2014	11.0	12.49	10.10	6.70	31
Bubble Pond	5/30/2014	12.0	12.33	9.98	6.63	31
Bubble Pond	5/30/2014	12.6	12.06	5.58	6.40	34
Bubble Pond	6/26/2014	0.1	17.35	9.36	6.94	31
Bubble Pond	6/26/2014	0.5	17.35	9.36	6.93	31
Bubble Pond	6/26/2014	1.0	17.35	9.35	6.93	31
Bubble Pond	6/26/2014	2.0	17.32	9.35	6.91	31
Bubble Pond	6/26/2014	3.0	17.29	9.35	6.91	31
Bubble Pond	6/26/2014	4.0	17.23	9.35	6.91	31
Bubble Pond	6/26/2014	5.0	17.23	9.33	6.90	31
Bubble Pond	6/26/2014	6.0	17.15	9.34	6.88	31
Bubble Pond	6/26/2014	6.0	17.19	9.33	6.87	31
Bubble Pond	6/26/2014	7.0	17.03	9.33	6.85	30
Bubble Pond	6/26/2014	7.0	17.04	9.32	6.84	30
Bubble Pond	6/26/2014	8.0	17.00	9.29	6.82	30

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Bubble Pond	6/26/2014	9.0	16.97	9.24	6.80	31
Bubble Pond	6/26/2014	10.0	16.38	8.84	6.64	31
Bubble Pond	6/26/2014	11.0	14.43	7.02	6.21	31
Bubble Pond	6/26/2014	11.6	14.29	5.54	6.10	32
Bubble Pond	7/22/2014	0.1	22.29	8.78	7.05	30
Bubble Pond	7/22/2014	0.5	22.27	8.79	6.96	31
Bubble Pond	7/22/2014	1.0	22.24	8.79	6.84	32
Bubble Pond	7/22/2014	2.0	22.10	8.82	6.79	30
Bubble Pond	7/22/2014	2.0	22.09	8.83	6.82	30
Bubble Pond	7/22/2014	3.0	21.99	8.85	6.79	31
Bubble Pond	7/22/2014	4.0	20.52	8.95	6.70	30
Bubble Pond	7/22/2014	5.0	20.09	8.94	6.66	30
Bubble Pond	7/22/2014	6.0	19.35	8.19	6.44	30
Bubble Pond	7/22/2014	7.0	18.89	7.33	6.24	30
Bubble Pond	7/22/2014	8.0	18.12	6.19	6.11	31
Bubble Pond	7/22/2014	9.0	17.49	4.82	5.99	31
Bubble Pond	7/22/2014	10.0	17.28	4.41	5.97	32
Bubble Pond	7/22/2014	10.9	16.98	0.42	6.29	46
Bubble Pond	8/26/2014	0.1	21.40	8.74	7.21	31
Bubble Pond	8/26/2014	0.5	21.17	8.76	6.98	31
Bubble Pond	8/26/2014	1.0	21.09	8.77	6.99	31
Bubble Pond	8/26/2014	2.0	20.89	8.77	6.91	31
Bubble Pond	8/26/2014	3.0	20.42	8.75	6.88	30
Bubble Pond	8/26/2014	4.0	20.29	8.71	6.84	31
Bubble Pond	8/26/2014	5.0	20.11	8.62	6.76	31
Bubble Pond	8/26/2014	6.0	19.66	7.96	6.52	31
Bubble Pond	8/26/2014	7.0	19.50	7.65	6.42	29
Bubble Pond	8/26/2014	8.0	19.37	7.34	6.32	31

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Bubble Pond	8/26/2014	9.0	19.23	6.97	6.15	31
Bubble Pond	8/26/2014	10.0	19.13	6.68	5.93	31
Bubble Pond	8/26/2014	11.0	19.08	6.51	5.89	31
Bubble Pond	8/26/2014	11.7	18.96	3.05	6.07	38
Bubble Pond	8/26/2014	11.7	18.96	3.03	6.06	38
Bubble Pond	9/15/2014	0.1	17.86	9.10	6.87	31
Bubble Pond	9/15/2014	0.5	17.86	9.09	6.88	31
Bubble Pond	9/15/2014	1.0	17.85	9.09	6.89	31
Bubble Pond	9/15/2014	2.0	17.81	9.06	6.84	31
Bubble Pond	9/15/2014	3.0	17.74	9.08	6.89	31
Bubble Pond	9/15/2014	4.0	17.63	9.06	6.87	31
Bubble Pond	9/15/2014	5.0	17.57	9.06	6.85	31
Bubble Pond	9/15/2014	6.0	17.45	9.04	6.89	31
Bubble Pond	9/15/2014	7.0	17.39	9.05	6.86	31
Bubble Pond	9/15/2014	8.0	17.27	9.04	6.85	31
Bubble Pond	9/15/2014	9.0	17.23	9.04	6.86	31
Bubble Pond	9/15/2014	10.0	17.22	9.02	6.85	31
Bubble Pond	9/15/2014	11.0	17.21	8.98	6.81	31
Bubble Pond	9/15/2014	11.0	17.21	9.02	6.84	31
Bubble Pond	10/29/2014	0.1	9.87	10.82	6.45	30
Bubble Pond	10/29/2014	0.5	9.86	10.80	6.50	30
Bubble Pond	10/29/2014	1.0	9.86	10.80	6.53	30
Bubble Pond	10/29/2014	2.0	9.85	10.79	6.52	30
Bubble Pond	10/29/2014	3.0	9.86	10.80	6.48	30
Bubble Pond	10/29/2014	4.0	9.86	10.79	6.50	30
Bubble Pond	10/29/2014	5.0	9.86	10.78	6.50	30
Bubble Pond	10/29/2014	6.0	9.85	10.78	6.48	30
Bubble Pond	10/29/2014	7.0	9.85	10.78	6.48	30

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Bubble Pond	10/29/2014	8.0	9.85	10.78	6.47	30
Bubble Pond	10/29/2014	9.0	9.86	10.78	6.45	30
Bubble Pond	10/29/2014	10.0	9.86	10.78	6.43	30
Bubble Pond	10/29/2014	11.0	9.86	10.77	6.47	30
Bubble Pond	10/29/2014	11.5	9.86	10.75	6.44	30
Eagle Lake	4/28/2014	0.4	6.66	12.36	6.90	34
Eagle Lake	5/29/2014	0.1	12.80	10.78	7.08	32
Eagle Lake	5/29/2014	0.5	12.64	10.81	6.92	31
Eagle Lake	5/29/2014	1.0	12.52	10.82	6.86	32
Eagle Lake	5/29/2014	2.0	12.38	10.82	6.81	32
Eagle Lake	5/29/2014	3.0	12.26	10.92	6.79	33
Eagle Lake	5/29/2014	4.0	12.17	10.94	6.79	32
Eagle Lake	5/29/2014	5.0	12.16	10.90	6.80	32
Eagle Lake	5/29/2014	6.0	12.11	10.91	6.81	31
Eagle Lake	5/29/2014	7.0	11.93	10.98	6.81	31
Eagle Lake	5/29/2014	8.0	10.97	11.30	6.80	32
Eagle Lake	5/29/2014	9.0	10.59	11.30	6.76	32
Eagle Lake	5/29/2014	10.0	10.28	11.27	6.71	32
Eagle Lake	5/29/2014	11.0	10.07	11.27	6.66	32
Eagle Lake	5/29/2014	12.0	9.75	11.23	6.61	32
Eagle Lake	5/29/2014	13.0	9.72	11.17	6.57	32
Eagle Lake	5/29/2014	14.0	9.71	11.15	6.58	32
Eagle Lake	5/29/2014	15.0	9.58	11.13	6.58	32
Eagle Lake	5/29/2014	16.0	9.58	11.13	6.59	31
Eagle Lake	5/29/2014	17.0	9.57	11.13	6.58	32
Eagle Lake	5/29/2014	18.0	9.52	11.08	6.58	31
Eagle Lake	5/29/2014	19.0	9.52	11.06	6.57	32
Eagle Lake	5/29/2014	20.0	9.50	11.07	6.57	32

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Eagle Lake	5/29/2014	21.0	9.48	11.05	6.57	32
Eagle Lake	5/29/2014	22.0	9.46	11.08	6.57	32
Eagle Lake	5/29/2014	23.0	9.46	11.08	6.57	32
Eagle Lake	5/29/2014	24.0	9.47	11.09	6.57	32
Eagle Lake	5/29/2014	24.0	9.47	11.09	6.57	32
Eagle Lake	5/29/2014	25.0	9.46	11.10	6.57	32
Eagle Lake	5/29/2014	26.0	9.46	11.11	6.57	32
Eagle Lake	5/29/2014	27.0	9.45	11.09	6.57	32
Eagle Lake	5/29/2014	27.0	9.45	11.09	6.57	32
Eagle Lake	5/29/2014	28.0	9.46	11.11	6.57	32
Eagle Lake	5/29/2014	29.0	9.42	11.14	6.58	32
Eagle Lake	5/29/2014	30.0	9.43	11.16	6.59	31
Eagle Lake	5/29/2014	30.0	9.41	11.17	6.59	32
Eagle Lake	6/26/2014	0.1	16.94	9.60	7.26	33
Eagle Lake	6/26/2014	0.5	16.94	9.60	7.14	33
Eagle Lake	6/26/2014	1.0	16.94	9.60	7.06	33
Eagle Lake	6/26/2014	2.0	16.93	9.59	7.05	33
Eagle Lake	6/26/2014	3.0	16.92	9.59	7.04	33
Eagle Lake	6/26/2014	4.0	16.88	9.58	7.03	33
Eagle Lake	6/26/2014	5.0	16.68	9.64	6.99	33
Eagle Lake	6/26/2014	6.0	16.64	9.66	6.96	33
Eagle Lake	6/26/2014	7.0	16.62	9.67	6.94	33
Eagle Lake	6/26/2014	8.0	16.46	9.76	6.93	33
Eagle Lake	6/26/2014	9.0	15.99	9.89	6.89	33
Eagle Lake	6/26/2014	10.0	15.36	10.01	6.82	33
Eagle Lake	6/26/2014	11.0	12.33	10.68	6.52	33
Eagle Lake	6/26/2014	12.0	11.23	10.66	6.39	33
Eagle Lake	6/26/2014	13.0	10.74	10.54	6.30	33

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Eagle Lake	6/26/2014	14.0	10.58	10.47	6.26	33
Eagle Lake	6/26/2014	15.0	10.54	10.42	6.26	33
Eagle Lake	6/26/2014	16.0	10.46	10.37	6.27	33
Eagle Lake	6/26/2014	17.0	10.43	10.35	6.28	33
Eagle Lake	6/26/2014	18.0	10.39	10.31	6.28	33
Eagle Lake	6/26/2014	19.0	10.36	10.29	6.28	33
Eagle Lake	6/26/2014	20.0	10.35	10.26	6.26	33
Eagle Lake	6/26/2014	21.0	10.36	10.26	6.27	33
Eagle Lake	6/26/2014	22.0	10.35	10.25	6.28	33
Eagle Lake	6/26/2014	23.0	10.35	10.23	6.27	33
Eagle Lake	6/26/2014	24.0	10.33	10.21	6.26	33
Eagle Lake	6/26/2014	25.0	10.31	10.16	6.24	33
Eagle Lake	6/26/2014	26.0	10.30	10.11	6.23	33
Eagle Lake	6/26/2014	27.0	10.30	10.13	6.23	33
Eagle Lake	6/26/2014	28.0	10.30	10.13	6.24	33
Eagle Lake	6/26/2014	29.0	10.29	10.12	6.24	33
Eagle Lake	6/26/2014	30.0	10.28	10.10	6.23	33
Eagle Lake	7/22/2014	0.1	22.19	8.72	7.02	33
Eagle Lake	7/22/2014	0.5	22.18	8.72	7.01	33
Eagle Lake	7/22/2014	1.0	22.14	8.72	7.00	33
Eagle Lake	7/22/2014	2.0	22.11	8.71	7.00	33
Eagle Lake	7/22/2014	3.0	22.04	8.71	6.99	33
Eagle Lake	7/22/2014	4.0	21.37	8.86	6.97	33
Eagle Lake	7/22/2014	5.0	21.09	8.88	6.96	33
Eagle Lake	7/22/2014	6.0	20.74	8.93	6.93	33
Eagle Lake	7/22/2014	7.0	20.51	8.93	6.87	31
Eagle Lake	7/22/2014	8.0	20.39	8.93	6.88	33
Eagle Lake	7/22/2014	9.0	19.92	8.98	6.83	33

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Eagle Lake	7/22/2014	10.0	19.33	8.98	6.75	33
Eagle Lake	7/22/2014	11.0	17.40	9.24	6.54	33
Eagle Lake	7/22/2014	12.0	13.19	9.65	6.26	33
Eagle Lake	7/22/2014	13.0	12.43	9.57	6.21	31
Eagle Lake	7/22/2014	14.0	11.95	9.51	6.19	33
Eagle Lake	7/22/2014	15.0	11.62	9.43	6.16	33
Eagle Lake	7/22/2014	16.0	11.49	9.29	6.13	33
Eagle Lake	7/22/2014	17.0	11.38	9.23	6.12	33
Eagle Lake	7/22/2014	18.0	11.36	9.21	6.13	33
Eagle Lake	7/22/2014	19.0	11.32	9.18	6.13	33
Eagle Lake	7/22/2014	20.0	11.31	9.14	6.15	31
Eagle Lake	7/22/2014	21.0	11.27	9.07	6.15	33
Eagle Lake	7/22/2014	22.0	11.27	9.05	6.15	33
Eagle Lake	7/22/2014	23.0	11.26	9.05	6.16	33
Eagle Lake	7/22/2014	24.0	11.24	9.01	6.16	33
Eagle Lake	7/22/2014	25.0	11.23	8.99	6.16	33
Eagle Lake	7/22/2014	26.0	11.23	8.96	6.16	33
Eagle Lake	7/22/2014	27.0	11.22	8.96	6.16	31
Eagle Lake	7/22/2014	28.0	11.21	8.92	6.15	33
Eagle Lake	7/22/2014	28.5	11.21	8.46	6.20	33
Eagle Lake	8/18/2014	0.1	20.63	8.77	7.27	33
Eagle Lake	8/18/2014	0.5	20.63	8.75	7.11	33
Eagle Lake	8/18/2014	1.0	20.63	8.74	7.09	33
Eagle Lake	8/18/2014	2.0	20.63	8.73	7.06	33
Eagle Lake	8/18/2014	3.0	20.61	8.73	7.04	33
Eagle Lake	8/18/2014	4.0	20.60	8.71	7.03	33
Eagle Lake	8/18/2014	5.0	20.56	8.70	7.04	33
Eagle Lake	8/18/2014	6.0	20.55	8.70	7.00	33

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Eagle Lake	8/18/2014	7.0	20.53	8.69	6.99	33
Eagle Lake	8/18/2014	8.0	20.52	8.68	7.00	33
Eagle Lake	8/18/2014	9.0	20.46	8.65	6.97	33
Eagle Lake	8/18/2014	10.0	20.27	8.64	6.93	33
Eagle Lake	8/18/2014	11.0	18.81	8.76	6.66	33
Eagle Lake	8/18/2014	12.0	15.82	8.82	6.43	33
Eagle Lake	8/18/2014	12.0	15.80	8.87	6.29	33
Eagle Lake	8/18/2014	12.0	15.77	8.81	6.46	33
Eagle Lake	8/18/2014	13.0	13.57	8.49	6.33	33
Eagle Lake	8/18/2014	14.0	12.69	8.02	6.39	33
Eagle Lake	8/18/2014	15.0	12.44	7.93	6.34	33
Eagle Lake	8/18/2014	16.0	12.16	7.71	6.29	33
Eagle Lake	8/18/2014	17.0	12.05	7.67	6.25	33
Eagle Lake	8/18/2014	18.0	11.85	7.46	6.21	33
Eagle Lake	8/18/2014	19.0	11.72	7.35	6.18	33
Eagle Lake	8/18/2014	20.0	11.67	7.21	6.16	33
Eagle Lake	8/18/2014	21.0	11.64	7.16	6.11	33
Eagle Lake	8/18/2014	22.0	11.63	7.19	6.09	33
Eagle Lake	8/18/2014	23.0	11.59	7.02	6.04	34
Eagle Lake	8/18/2014	24.0	11.59	7.02	6.02	34
Eagle Lake	8/18/2014	25.0	11.58	7.00	6.01	34
Eagle Lake	8/18/2014	26.0	11.58	6.98	5.99	34
Eagle Lake	8/18/2014	27.0	11.58	6.96	5.99	34
Eagle Lake	8/18/2014	28.0	11.58	6.95	5.98	34
Eagle Lake	8/18/2014	29.0	11.57	6.95	5.96	34
Eagle Lake	8/18/2014	29.5	11.45	0.51	6.05	47
Eagle Lake	9/17/2014	0.1	18.70	9.06	7.20	34
Eagle Lake	9/17/2014	0.5	18.65	9.03	7.10	34

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Eagle Lake	9/17/2014	1.0	18.63	9.00	7.05	33
Eagle Lake	9/17/2014	2.0	18.45	9.02	6.99	33
Eagle Lake	9/17/2014	3.0	18.40	9.01	6.99	33
Eagle Lake	9/17/2014	4.0	18.38	9.00	6.98	33
Eagle Lake	9/17/2014	5.0	18.34	9.02	6.92	32
Eagle Lake	9/17/2014	6.0	18.26	9.01	6.92	33
Eagle Lake	9/17/2014	7.0	18.23	9.01	6.91	33
Eagle Lake	9/17/2014	8.0	18.20	9.02	6.89	33
Eagle Lake	9/17/2014	9.0	18.18	9.05	6.87	33
Eagle Lake	9/17/2014	10.0	18.17	9.02	6.89	32
Eagle Lake	9/17/2014	11.0	18.16	8.99	6.87	33
Eagle Lake	9/17/2014	12.0	18.11	8.94	6.88	32
Eagle Lake	9/17/2014	13.0	17.98	8.96	6.79	33
Eagle Lake	9/17/2014	14.0	17.57	8.78	6.68	33
Eagle Lake	9/17/2014	15.0	13.74	7.12	6.15	34
Eagle Lake	9/17/2014	16.0	12.94	6.54	5.82	33
Eagle Lake	9/17/2014	16.0	12.95	6.53	5.74	33
Eagle Lake	9/17/2014	17.0	12.56	6.29	5.43	33
Eagle Lake	9/17/2014	18.0	12.23	5.69	5.54	34
Eagle Lake	9/17/2014	19.0	11.95	5.28	5.48	34
Eagle Lake	9/17/2014	20.0	11.85	5.07	5.44	34
Eagle Lake	9/17/2014	21.0	11.78	4.78	5.42	34
Eagle Lake	9/17/2014	22.0	11.75	4.69	5.42	34
Eagle Lake	9/17/2014	23.0	11.73	4.60	5.40	34
Eagle Lake	9/17/2014	24.0	11.72	4.44	5.42	35
Eagle Lake	9/17/2014	25.0	11.70	4.36	5.43	35
Eagle Lake	9/17/2014	26.0	11.69	4.22	5.46	35
Eagle Lake	9/17/2014	26.8	11.64	0.06	5.96	49

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Eagle Lake	10/20/2014	0.1	14.15	9.70	7.29	33
Eagle Lake	10/20/2014	0.5	14.17	9.67	7.22	33
Eagle Lake	10/20/2014	1.0	14.17	9.66	7.23	31
Eagle Lake	10/20/2014	2.0	14.18	9.66	7.17	33
Eagle Lake	10/20/2014	3.0	14.20	9.66	7.13	33
Eagle Lake	10/20/2014	4.0	14.19	9.65	6.97	31
Eagle Lake	10/20/2014	5.0	14.19	9.65	6.96	33
Eagle Lake	10/20/2014	6.0	14.20	9.65	6.93	33
Eagle Lake	10/20/2014	7.0	14.20	9.64	6.93	33
Eagle Lake	10/20/2014	8.0	14.19	9.63	6.92	31
Eagle Lake	10/20/2014	9.0	14.20	9.64	6.84	31
Eagle Lake	10/20/2014	10.0	14.20	9.65	6.84	33
Eagle Lake	10/20/2014	11.0	14.16	9.63	6.82	33
Eagle Lake	10/20/2014	12.0	14.10	9.59	6.81	31
Eagle Lake	10/20/2014	13.0	14.09	9.56	6.77	33
Eagle Lake	10/20/2014	14.0	14.09	9.56	6.78	33
Eagle Lake	10/20/2014	15.0	14.09	9.54	6.76	33
Eagle Lake	10/20/2014	16.0	14.08	9.53	6.73	33
Eagle Lake	10/20/2014	17.0	14.08	9.54	6.72	33
Eagle Lake	10/20/2014	18.0	14.07	9.54	6.73	33
Eagle Lake	10/20/2014	19.0	14.05	9.52	6.72	33
Eagle Lake	10/20/2014	20.0	14.05	9.49	6.72	33
Eagle Lake	10/20/2014	21.0	14.04	9.46	6.68	31
Eagle Lake	10/20/2014	22.0	14.04	9.43	6.69	33
Eagle Lake	10/20/2014	23.0	14.04	9.43	6.67	33
Eagle Lake	10/20/2014	24.0	14.01	9.39	6.63	33
Eagle Lake	10/20/2014	25.0	13.97	9.32	6.64	33
Eagle Lake	10/20/2014	26.0	13.83	8.97	6.56	34

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Eagle Lake	10/20/2014	26.5	13.66	6.29	6.35	34
Echo Lake	4/28/2014	0.5	6.85	12.16	6.49	66
Echo Lake	5/22/2014	0.1	12.74	11.02	6.80	65
Echo Lake	5/22/2014	0.5	12.64	11.01	6.78	65
Echo Lake	5/22/2014	1.0	12.28	11.06	6.80	65
Echo Lake	5/22/2014	2.0	12.17	11.06	6.81	65
Echo Lake	5/22/2014	3.0	12.13	11.04	6.81	65
Echo Lake	5/22/2014	4.0	12.08	11.02	6.83	65
Echo Lake	5/22/2014	5.0	12.02	11.02	6.84	65
Echo Lake	5/22/2014	6.0	11.97	11.01	6.84	65
Echo Lake	5/22/2014	7.0	11.90	11.02	6.84	65
Echo Lake	5/22/2014	8.0	11.72	11.03	6.83	65
Echo Lake	5/22/2014	9.0	10.84	11.18	6.80	65
Echo Lake	5/22/2014	10.0	10.04	11.31	6.72	65
Echo Lake	5/22/2014	11.0	9.31	11.39	6.61	63
Echo Lake	5/22/2014	12.0	8.78	11.36	6.51	65
Echo Lake	5/22/2014	13.0	8.45	11.22	6.46	63
Echo Lake	5/22/2014	14.0	8.37	11.13	6.42	65
Echo Lake	5/22/2014	15.0	8.33	11.11	6.45	65
Echo Lake	5/22/2014	16.0	8.31	11.09	6.49	65
Echo Lake	5/22/2014	17.0	8.28	10.98	6.47	65
Echo Lake	5/22/2014	18.0	8.27	10.88	6.47	65
Echo Lake	5/22/2014	18.8	8.23	10.35	6.43	65
Echo Lake	6/23/2014	0.1	19.77	10.28	7.23	67
Echo Lake	6/23/2014	0.5	19.59	10.30	7.20	67
Echo Lake	6/23/2014	1.0	19.19	10.34	7.18	67
Echo Lake	6/23/2014	2.0	18.99	10.34	7.17	67
Echo Lake	6/23/2014	3.0	18.70	10.33	7.16	67

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Echo Lake	6/23/2014	4.0	18.57	10.32	7.15	67
Echo Lake	6/23/2014	5.0	18.42	10.34	7.14	67
Echo Lake	6/23/2014	6.0	18.09	10.26	7.10	67
Echo Lake	6/23/2014	6.0	18.09	10.24	7.10	67
Echo Lake	6/23/2014	7.0	16.79	10.51	7.07	67
Echo Lake	6/23/2014	8.0	15.40	10.74	7.10	66
Echo Lake	6/23/2014	9.0	12.63	11.01	6.99	66
Echo Lake	6/23/2014	10.0	10.80	10.97	6.91	66
Echo Lake	6/23/2014	11.0	10.34	10.87	6.89	66
Echo Lake	6/23/2014	11.0	10.36	10.83	6.92	66
Echo Lake	6/23/2014	12.0	9.84	10.89	6.82	66
Echo Lake	6/23/2014	13.0	9.31	10.47	6.76	66
Echo Lake	6/23/2014	13.0	9.28	10.37	6.76	66
Echo Lake	6/23/2014	14.0	9.22	10.23	6.72	66
Echo Lake	6/23/2014	15.0	9.19	10.24	6.69	65
Echo Lake	6/23/2014	16.0	9.14	10.20	6.65	66
Echo Lake	6/23/2014	17.0	9.09	10.09	6.56	66
Echo Lake	6/23/2014	18.0	9.05	9.90	6.51	66
Echo Lake	6/23/2014	19.0	9.04	9.80	6.44	66
Echo Lake	7/24/2014	0.1	22.84	8.47	7.26	67
Echo Lake	7/24/2014	0.5	22.85	8.51	7.21	67
Echo Lake	7/24/2014	1.0	22.84	8.50	7.18	67
Echo Lake	7/24/2014	2.0	22.85	8.50	7.16	68
Echo Lake	7/24/2014	3.0	22.85	8.50	7.15	68
Echo Lake	7/24/2014	4.0	22.84	8.51	7.13	68
Echo Lake	7/24/2014	5.0	22.80	8.50	7.12	68
Echo Lake	7/24/2014	6.0	22.53	8.52	7.10	68
Echo Lake	7/24/2014	7.0	21.12	8.61	7.00	67

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Echo Lake	7/24/2014	8.0	19.61	8.26	6.81	66
Echo Lake	7/24/2014	9.0	17.92	7.63	6.55	66
Echo Lake	7/24/2014	10.0	12.46	8.19	6.43	67
Echo Lake	7/24/2014	11.0	11.30	7.90	6.21	66
Echo Lake	7/24/2014	12.0	10.41	7.77	6.13	66
Echo Lake	7/24/2014	13.0	9.75	7.66	6.10	66
Echo Lake	7/24/2014	14.0	9.56	7.22	6.08	66
Echo Lake	7/24/2014	15.0	9.47	7.10	6.06	66
Echo Lake	7/24/2014	16.0	9.39	6.95	6.06	66
Echo Lake	7/24/2014	17.0	9.32	6.66	6.05	66
Echo Lake	7/24/2014	18.0	9.31	6.52	6.06	66
Echo Lake	7/24/2014	19.0	9.23	6.05	6.04	66
Echo Lake	7/24/2014	19.2	9.21	5.40	6.11	73
Echo Lake	8/20/2014	0.1	21.76	8.76	7.12	69
Echo Lake	8/20/2014	0.5	21.27	8.79	7.09	68
Echo Lake	8/20/2014	1.0	21.15	8.79	7.07	66
Echo Lake	8/20/2014	2.0	20.96	8.79	7.06	68
Echo Lake	8/20/2014	3.0	20.77	8.74	7.06	68
Echo Lake	8/20/2014	4.0	20.67	8.75	7.02	68
Echo Lake	8/20/2014	5.0	20.65	8.74	7.02	68
Echo Lake	8/20/2014	6.0	20.61	8.75	7.02	68
Echo Lake	8/20/2014	7.0	20.54	8.75	7.01	68
Echo Lake	8/20/2014	8.0	20.29	8.60	6.93	68
Echo Lake	8/20/2014	9.0	18.29	7.10	6.56	68
Echo Lake	8/20/2014	9.0	18.37	7.26	6.62	68
Echo Lake	8/20/2014	10.0	14.36	6.16	6.24	67
Echo Lake	8/20/2014	11.0	11.81	6.14	6.05	67
Echo Lake	8/20/2014	12.0	10.46	6.08	5.94	67

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Echo Lake	8/20/2014	13.0	9.88	5.29	5.90	67
Echo Lake	8/20/2014	14.0	9.80	4.81	5.93	67
Echo Lake	8/20/2014	15.0	9.67	4.57	5.90	67
Echo Lake	8/20/2014	16.0	9.60	4.36	5.90	67
Echo Lake	8/20/2014	17.0	9.56	4.14	5.89	67
Echo Lake	8/20/2014	18.0	9.55	4.09	5.90	67
Echo Lake	8/20/2014	18.8	9.45	0.24	6.12	81
Echo Lake	9/18/2014	0.1	18.35	9.00	7.07	68
Echo Lake	9/18/2014	0.5	18.34	8.99	7.02	68
Echo Lake	9/18/2014	1.0	18.32	8.99	7.00	68
Echo Lake	9/18/2014	2.0	18.28	8.98	6.97	68
Echo Lake	9/18/2014	3.0	18.20	8.98	6.96	68
Echo Lake	9/18/2014	4.0	18.02	8.94	6.94	68
Echo Lake	9/18/2014	5.0	17.87	8.84	6.90	68
Echo Lake	9/18/2014	6.0	17.85	8.86	6.89	68
Echo Lake	9/18/2014	7.0	17.84	8.84	6.88	68
Echo Lake	9/18/2014	8.0	17.82	8.81	6.88	68
Echo Lake	9/18/2014	9.0	17.81	8.78	6.84	67
Echo Lake	9/18/2014	10.0	17.77	8.78	6.85	68
Echo Lake	9/18/2014	11.0	16.03	7.49	6.57	68
Echo Lake	9/18/2014	11.0	15.81	6.40	5.96	68
Echo Lake	9/18/2014	12.0	11.14	4.35	6.04	67
Echo Lake	9/18/2014	13.0	10.26	3.44	5.90	67
Echo Lake	9/18/2014	14.0	9.96	2.51	5.77	67
Echo Lake	9/18/2014	15.0	9.85	2.31	5.64	68
Echo Lake	9/18/2014	16.0	9.74	2.03	5.53	68
Echo Lake	9/18/2014	17.0	9.67	1.78	5.54	69

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Echo Lake	9/18/2014	18.0	9.58	1.18	5.87	71
cho Lake	9/18/2014	19.0	9.51	0.65	5.99	76
Echo Lake	10/21/2014	0.1	13.65	9.89	7.55	64
Echo Lake	10/21/2014	0.5	13.65	9.75	7.33	68
Echo Lake	10/21/2014	1.0	13.65	9.75	7.16	68
Echo Lake	10/21/2014	1.0	13.65	9.75	7.16	68
Echo Lake	10/21/2014	2.0	13.64	9.73	7.10	68
Echo Lake	10/21/2014	3.0	13.64	9.71	7.03	64
Echo Lake	10/21/2014	4.0	13.64	9.69	6.99	68
Echo Lake	10/21/2014	5.0	13.63	9.67	6.94	68
Echo Lake	10/21/2014	6.0	13.63	9.65	6.89	68
Echo Lake	10/21/2014	7.0	13.62	9.63	6.88	68
Echo Lake	10/21/2014	8.0	13.62	9.61	6.85	68
Echo Lake	10/21/2014	9.0	13.62	9.63	6.82	68
Echo Lake	10/21/2014	10.0	13.62	9.62	6.81	68
Echo Lake	10/21/2014	11.0	13.61	9.61	6.80	68
Echo Lake	10/21/2014	12.0	13.52	9.61	6.77	68
Echo Lake	10/21/2014	13.0	13.44	9.59	6.75	68
Echo Lake	10/21/2014	14.0	13.29	9.46	6.70	68
Echo Lake	10/21/2014	15.0	13.01	8.52	6.50	68
Echo Lake	10/21/2014	16.0	10.01	0.89	6.07	72
Echo Lake	10/21/2014	17.0	9.59	0.26	6.04	76
Echo Lake	10/21/2014	18.0	9.50	0.17	6.09	81
Echo Lake	10/21/2014	19.0	9.39	0.13	6.15	89
Jordan Pond	4/24/2014	0.1	3.47	12.78	6.39	32
Jordan Pond	5/29/2014	0.0	12.00	11.31	7.07	32
Jordan Pond	5/29/2014	1.0	11.97	11.52	7.01	32
Jordan Pond	5/29/2014	2.0	11.93	11.67	6.99	32

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Jordan Pond	5/29/2014	3.0	11.90	11.36	6.97	32
Jordan Pond	5/29/2014	4.0	11.47	11.37	6.96	32
Jordan Pond	5/29/2014	5.0	11.39	11.36	6.96	32
Jordan Pond	5/29/2014	6.0	11.24	11.40	6.95	32
Jordan Pond	5/29/2014	7.0	10.35	11.83	6.94	32
Jordan Pond	5/29/2014	8.0	10.10	12.03	6.95	32
Jordan Pond	5/29/2014	9.0	9.34	12.30	6.95	32
Jordan Pond	5/29/2014	10.0	8.33	12.60	6.96	32
Jordan Pond	5/29/2014	11.0	7.66	12.80	6.96	32
Jordan Pond	5/29/2014	12.0	7.38	12.87	6.94	32
Jordan Pond	5/29/2014	12.0	7.40	12.85	6.91	32
Jordan Pond	5/29/2014	13.0	7.04	12.94	6.87	32
Jordan Pond	5/29/2014	14.0	5.99	13.17	6.85	32
Jordan Pond	5/29/2014	15.0	5.55	13.26	6.80	32
Jordan Pond	5/29/2014	16.0	5.36	13.26	6.77	32
Jordan Pond	5/29/2014	17.0	5.05	13.24	6.72	32
Jordan Pond	5/29/2014	18.0	4.97	13.21	6.70	32
Jordan Pond	5/29/2014	19.0	4.80	13.22	6.68	32
Jordan Pond	5/29/2014	20.0	4.68	13.23	6.68	32
Jordan Pond	5/29/2014	21.0	4.55	13.26	6.67	32
Jordan Pond	5/29/2014	22.0	4.54	13.24	6.67	32
Jordan Pond	5/29/2014	23.0	4.45	13.22	6.66	32
Jordan Pond	5/29/2014	24.0	4.39	13.21	6.66	32
Jordan Pond	5/29/2014	25.0	4.33	13.20	6.66	32
Jordan Pond	5/29/2014	26.0	4.31	13.18	6.65	32
Jordan Pond	5/29/2014	27.0	4.27	13.18	6.65	32
Jordan Pond	5/29/2014	28.0	4.26	13.18	6.64	32
Jordan Pond	5/29/2014	29.0	4.23	13.16	6.64	32

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Jordan Pond	5/29/2014	30.0	4.17	13.16	6.63	32
Jordan Pond	6/30/2014	0.1	19.11	9.64	7.15	33
Jordan Pond	6/30/2014	1.0	19.02	9.63	7.11	32
Jordan Pond	6/30/2014	1.0	19.01	9.62	7.12	33
Jordan Pond	6/30/2014	2.0	18.72	9.69	7.07	32
Jordan Pond	6/30/2014	3.0	18.23	9.73	7.06	32
Jordan Pond	6/30/2014	4.0	18.05	9.77	7.03	32
Jordan Pond	6/30/2014	5.0	17.15	9.96	7.00	32
Jordan Pond	6/30/2014	6.0	16.81	10.01	6.98	32
Jordan Pond	6/30/2014	7.0	16.62	10.01	6.96	32
Jordan Pond	6/30/2014	7.0	16.63	10.01	6.96	32
Jordan Pond	6/30/2014	8.0	16.23	10.12	6.95	32
Jordan Pond	6/30/2014	9.0	15.62	10.32	6.94	32
Jordan Pond	6/30/2014	10.0	12.01	12.09	6.82	32
Jordan Pond	6/30/2014	11.0	10.28	12.65	6.74	32
Jordan Pond	6/30/2014	12.0	8.13	13.09	6.74	32
Jordan Pond	6/30/2014	13.0	7.52	13.16	6.74	32
Jordan Pond	6/30/2014	14.0	6.98	13.32	6.75	32
Jordan Pond	6/30/2014	15.0	6.02	13.43	6.68	32
Jordan Pond	6/30/2014	16.0	5.52	13.44	6.63	32
Jordan Pond	6/30/2014	17.0	5.31	13.42	6.61	32
Jordan Pond	6/30/2014	18.0	5.10	13.34	6.58	32
Jordan Pond	6/30/2014	19.0	4.97	13.27	6.56	32
Jordan Pond	6/30/2014	20.0	4.85	13.14	6.51	32
Jordan Pond	6/30/2014	21.0	4.67	13.10	6.47	32
Jordan Pond	6/30/2014	22.0	4.59	13.10	6.47	32
Jordan Pond	6/30/2014	23.0	4.49	13.03	6.44	32
Jordan Pond	6/30/2014	24.0	4.45	13.01	6.43	32

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Jordan Pond	6/30/2014	25.0	4.39	12.95	6.42	32
Jordan Pond	6/30/2014	26.0	4.28	12.91	6.40	32
Jordan Pond	6/30/2014	27.0	4.27	12.88	6.39	32
Jordan Pond	6/30/2014	28.0	4.25	12.88	6.39	32
Jordan Pond	6/30/2014	29.0	4.25	12.83	6.38	32
Jordan Pond	6/30/2014	30.0	4.19	12.81	6.38	32
Jordan Pond	7/21/2014	0.1	22.01	8.80	7.10	33
Jordan Pond	7/21/2014	0.5	21.97	8.81	7.06	32
Jordan Pond	7/21/2014	1.0	21.90	8.81	7.05	32
Jordan Pond	7/21/2014	2.0	21.79	8.83	7.04	32
Jordan Pond	7/21/2014	3.0	21.38	8.86	7.03	32
Jordan Pond	7/21/2014	4.0	21.01	8.92	7.01	32
Jordan Pond	7/21/2014	5.0	20.80	8.92	7.00	32
Jordan Pond	7/21/2014	6.0	20.50	8.97	6.99	32
Jordan Pond	7/21/2014	7.0	19.91	9.04	6.95	32
Jordan Pond	7/21/2014	8.0	18.85	9.36	6.90	33
Jordan Pond	7/21/2014	9.0	17.32	9.88	6.80	32
Jordan Pond	7/21/2014	10.0	14.34	10.96	6.76	32
Jordan Pond	7/21/2014	11.0	10.35	12.53	6.78	32
Jordan Pond	7/21/2014	12.0	9.05	13.08	6.80	32
Jordan Pond	7/21/2014	13.0	7.67	13.34	6.80	32
Jordan Pond	7/21/2014	14.0	6.97	13.40	6.79	32
Jordan Pond	7/21/2014	15.0	6.53	13.33	6.75	32
Jordan Pond	7/21/2014	16.0	6.16	13.39	6.72	32
Jordan Pond	7/21/2014	17.0	5.65	13.44	6.72	32
Jordan Pond	7/21/2014	18.0	5.30	13.45	6.70	32
Jordan Pond	7/21/2014	19.0	5.13	13.40	6.69	32
Jordan Pond	7/21/2014	20.0	5.03	13.21	6.63	32

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Jordan Pond	7/21/2014	21.0	4.85	12.97	6.58	32
Jordan Pond	7/21/2014	22.0	4.75	12.97	6.56	32
Jordan Pond	7/21/2014	23.0	4.71	12.96	6.55	32
Jordan Pond	7/21/2014	24.0	4.66	12.95	6.54	32
Jordan Pond	7/21/2014	25.0	4.58	12.86	6.53	32
Jordan Pond	7/21/2014	26.0	4.49	12.80	6.51	32
Jordan Pond	7/21/2014	27.0	4.43	12.77	6.50	32
Jordan Pond	7/21/2014	28.0	4.37	12.75	6.49	32
Jordan Pond	7/21/2014	29.0	4.29	12.66	6.46	32
Jordan Pond	7/21/2014	30.0	4.23	12.63	6.46	32
Jordan Pond	8/27/2014	0.1	21.05	8.95	7.07	33
Jordan Pond	8/27/2014	0.5	21.05	8.96	7.02	33
Jordan Pond	8/27/2014	1.0	20.95	8.97	7.00	33
Jordan Pond	8/27/2014	2.0	20.77	8.98	6.95	34
Jordan Pond	8/27/2014	3.0	20.65	8.99	6.91	32
Jordan Pond	8/27/2014	4.0	20.58	8.99	6.88	32
Jordan Pond	8/27/2014	5.0	20.51	9.00	6.88	32
Jordan Pond	8/27/2014	6.0	20.46	9.02	6.86	32
Jordan Pond	8/27/2014	7.0	20.25	9.07	6.86	32
Jordan Pond	8/27/2014	8.0	19.78	9.17	6.83	32
Jordan Pond	8/27/2014	9.0	19.20	9.29	6.73	32
Jordan Pond	8/27/2014	10.0	17.54	9.84	6.63	33
Jordan Pond	8/27/2014	11.0	13.51	11.94	6.54	32
Jordan Pond	8/27/2014	12.0	10.29	12.94	6.57	32
Jordan Pond	8/27/2014	13.0	8.65	13.34	6.63	32
Jordan Pond	8/27/2014	14.0	7.65	13.49	6.65	32
Jordan Pond	8/27/2014	15.0	6.63	13.62	6.62	32
Jordan Pond	8/27/2014	16.0	6.01	13.51	6.61	32

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Jordan Pond	8/27/2014	17.0	5.53	13.33	6.55	32
Jordan Pond	8/27/2014	18.0	5.23	13.27	6.51	32
Jordan Pond	8/27/2014	19.0	5.11	13.31	6.48	32
Jordan Pond	8/27/2014	20.0	5.01	13.19	6.45	32
Jordan Pond	8/27/2014	21.0	4.92	13.12	6.41	32
Jordan Pond	8/27/2014	22.0	4.87	13.02	6.39	32
Jordan Pond	8/27/2014	23.0	4.78	13.00	6.38	32
Jordan Pond	8/27/2014	24.0	4.70	12.85	6.36	32
Jordan Pond	8/27/2014	25.0	4.62	12.72	6.32	32
Jordan Pond	8/27/2014	26.0	4.55	12.61	6.29	32
Jordan Pond	8/27/2014	27.0	4.49	12.61	6.29	32
Jordan Pond	8/27/2014	28.0	4.45	12.54	6.27	32
Jordan Pond	8/27/2014	29.0	4.39	12.41	6.26	32
Jordan Pond	8/27/2014	30.0	4.35	12.36	6.25	32
Jordan Pond	9/15/2014	0.0	17.70	9.33	6.67	32
Jordan Pond	9/15/2014	1.0	17.71	9.34	6.96	32
Jordan Pond	9/15/2014	2.0	17.69	9.32	6.98	32
Jordan Pond	9/15/2014	3.0	17.65	9.33	7.00	32
Jordan Pond	9/15/2014	4.0	17.59	9.34	7.01	32
Jordan Pond	9/15/2014	5.0	17.57	9.34	6.99	32
Jordan Pond	9/15/2014	6.0	17.56	9.34	6.98	32
Jordan Pond	9/15/2014	7.0	17.55	9.34	6.98	32
Jordan Pond	9/15/2014	8.0	17.54	9.34	6.96	32
Jordan Pond	9/15/2014	9.0	17.53	9.33	6.95	32
Jordan Pond	9/15/2014	10.0	17.53	9.33	6.96	32
Jordan Pond	9/15/2014	11.0	16.99	9.69	6.92	32
Jordan Pond	9/15/2014	12.0	13.09	11.74	6.88	32
Jordan Pond	9/15/2014	13.0	10.09	12.99	6.79	32

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Jordan Pond	9/15/2014	14.0	8.45	13.42	6.72	32
Jordan Pond	9/15/2014	15.0	7.21	13.41	6.25	32
Jordan Pond	9/15/2014	16.0	6.16	13.58	6.32	32
Jordan Pond	9/15/2014	17.0	5.64	13.40	6.37	32
Jordan Pond	9/15/2014	18.0	5.36	13.36	6.38	32
Jordan Pond	9/15/2014	19.0	5.12	13.31	6.37	32
Jordan Pond	9/15/2014	20.0	4.95	13.26	6.36	32
Jordan Pond	9/15/2014	21.0	4.82	13.05	6.32	32
Jordan Pond	9/15/2014	22.0	4.77	12.88	6.30	32
Jordan Pond	9/15/2014	23.0	4.65	12.69	6.27	32
Jordan Pond	9/15/2014	24.0	4.52	12.59	6.22	32
Jordan Pond	9/15/2014	25.0	4.46	12.54	6.21	32
Jordan Pond	9/15/2014	26.0	4.41	12.44	6.18	32
Jordan Pond	9/15/2014	27.0	4.36	12.37	6.14	32
Jordan Pond	9/15/2014	28.0	4.27	12.28	6.11	32
Jordan Pond	9/15/2014	29.0	4.23	12.10	6.07	32
Jordan Pond	9/15/2014	30.0	4.17	12.07	6.01	32
Jordan Pond	10/29/2014	0.1	10.52	10.91	6.80	32
Jordan Pond	10/29/2014	0.5	10.51	10.86	6.65	32
Jordan Pond	10/29/2014	1.0	10.51	10.85	6.59	32
Jordan Pond	10/29/2014	2.0	10.50	10.85	6.54	32
Jordan Pond	10/29/2014	3.0	10.48	10.84	6.47	32
Jordan Pond	10/29/2014	4.0	10.47	10.83	6.45	32
Jordan Pond	10/29/2014	5.0	10.47	10.82	6.38	32
Jordan Pond	10/29/2014	6.0	10.47	10.82	6.35	32
Jordan Pond	10/29/2014	7.0	10.47	10.83	6.30	32
Jordan Pond	10/29/2014	8.0	10.46	10.84	6.27	32
Jordan Pond	10/29/2014	9.0	10.46	10.83	6.27	32

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Jordan Pond	10/29/2014	10.0	10.46	10.81	6.27	32
Jordan Pond	10/29/2014	11.0	10.46	10.82	6.25	32
Jordan Pond	10/29/2014	12.0	10.46	10.81	6.26	32
Jordan Pond	10/29/2014	13.0	10.46	10.81	6.27	32
Jordan Pond	10/29/2014	14.0	10.46	10.81	6.28	32
Jordan Pond	10/29/2014	15.0	10.45	10.81	6.26	32
Jordan Pond	10/29/2014	16.0	10.43	10.81	6.27	32
Jordan Pond	10/29/2014	17.0	10.40	10.82	6.28	32
Jordan Pond	10/29/2014	18.0	9.89	10.96	6.23	32
Jordan Pond	10/29/2014	19.0	7.86	11.73	6.17	32
Jordan Pond	10/29/2014	20.0	5.87	12.45	6.07	32
Jordan Pond	10/29/2014	21.0	5.24	12.71	6.05	32
Jordan Pond	10/29/2014	22.0	5.00	12.46	5.98	32
Jordan Pond	10/29/2014	23.0	4.75	12.32	5.91	32
Jordan Pond	10/29/2014	24.0	4.60	12.12	5.86	32
Jordan Pond	10/29/2014	25.0	4.51	12.04	5.83	32
Jordan Pond	10/29/2014	26.0	4.44	11.91	5.78	32
Jordan Pond	10/29/2014	27.0	4.36	11.84	5.75	32
Jordan Pond	10/29/2014	28.0	4.32	11.79	5.72	32
Jordan Pond	10/29/2014	29.0	4.26	11.68	5.68	32
Jordan Pond	10/29/2014	30.0	4.20	11.59	5.65	32
Lake Wood	5/20/2014	0.0	14.85	9.72	6.17	21
Lake Wood	5/20/2014	0.5	14.82	9.69	6.17	21
Lake Wood	5/20/2014	1.0	14.79	9.69	6.19	21
Lake Wood	5/20/2014	2.0	14.76	9.61	6.41	21
Lake Wood	5/20/2014	2.0	14.76	9.68	6.20	21
Lake Wood	5/20/2014	3.0	14.73	9.70	6.22	21
Lake Wood	5/20/2014	3.7	14.69	8.60	6.29	22

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Lake Wood	6/16/2014	0.1	19.45	9.16	6.74	24
Lake Wood	6/16/2014	0.5	19.23	9.17	6.69	24
Lake Wood	6/16/2014	1.0	19.06	9.16	6.68	24
Lake Wood	6/16/2014	2.0	18.76	9.18	6.67	24
Lake Wood	6/16/2014	3.0	18.77	9.20	6.65	24
Lake Wood	6/16/2014	3.5	18.76	9.19	6.66	24
Lake Wood	7/23/2014	0.1	25.48	8.20	6.67	26
Lake Wood	7/23/2014	0.5	25.46	8.19	6.68	25
Lake Wood	7/23/2014	1.0	25.38	8.21	6.67	25
Lake Wood	7/23/2014	2.0	25.10	8.23	6.65	25
Lake Wood	7/23/2014	3.0	22.94	7.01	6.18	26
Lake Wood	7/23/2014	3.5	22.54	4.89	6.11	26
Lake Wood	8/25/2014	0.1	25.17	8.13	6.65	26
Lake Wood	8/25/2014	0.5	23.21	8.30	6.56	26
Lake Wood	8/25/2014	0.5	23.21	8.22	6.51	26
Lake Wood	8/25/2014	1.0	22.58	8.29	6.52	26
Lake Wood	8/25/2014	1.0	22.61	8.30	6.50	26
Lake Wood	8/25/2014	2.0	22.15	8.11	6.48	25
Lake Wood	8/25/2014	2.0	22.15	8.15	6.47	25
Lake Wood	8/25/2014	3.0	22.03	8.00	6.45	25
Lake Wood	8/25/2014	3.0	22.04	8.16	6.46	25
Lake Wood	9/22/2014	0.1	17.57	9.20	6.58	25
Lake Wood	9/22/2014	0.5	17.31	9.29	6.57	25
Lake Wood	9/22/2014	1.0	17.08	9.34	6.56	25
Lake Wood	9/22/2014	2.0	17.02	9.29	6.45	25
Lake Wood	9/22/2014	3.0	17.00	7.46	6.43	25
Lake Wood	10/24/2014	0.1	11.33	10.06	6.39	25
Lake Wood	10/24/2014	0.5	11.33	9.91	5.98	25

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Lake Wood	10/24/2014	1.0	11.34	9.90	5.90	25
Lake Wood	10/24/2014	2.0	11.32	9.92	5.85	25
Lake Wood	10/24/2014	3.0	11.24	9.92	5.73	26
Lake Wood	10/24/2014	3.3	11.11	8.88	5.62	28
Long Pond (MDI)	4/28/2014	0.3	6.40	12.53	6.68	42
Long Pond (MDI)	5/22/2014	0.1	12.57	11.02	6.85	42
Long Pond (MDI)	5/22/2014	0.5	12.51	11.06	6.79	42
Long Pond (MDI)	5/22/2014	1.0	12.32	11.06	6.77	42
Long Pond (MDI)	5/22/2014	2.0	11.51	11.14	6.76	42
Long Pond (MDI)	5/22/2014	3.0	11.34	11.15	6.75	42
Long Pond (MDI)	5/22/2014	4.0	11.30	11.14	6.74	42
Long Pond (MDI)	5/22/2014	5.0	11.27	11.14	6.74	42
Long Pond (MDI)	5/22/2014	6.0	11.18	11.16	6.74	42
Long Pond (MDI)	5/22/2014	7.0	11.11	11.15	6.73	42
Long Pond (MDI)	5/22/2014	8.0	10.90	11.17	6.71	42
Long Pond (MDI)	5/22/2014	9.0	10.79	11.20	6.70	42
Long Pond (MDI)	5/22/2014	10.0	10.47	11.30	6.68	42
Long Pond (MDI)	5/22/2014	11.0	9.96	11.40	6.66	42
Long Pond (MDI)	5/22/2014	12.0	9.81	11.41	6.63	42
Long Pond (MDI)	5/22/2014	13.0	9.38	11.49	6.61	42
Long Pond (MDI)	5/22/2014	14.0	8.65	11.69	6.58	42
Long Pond (MDI)	5/22/2014	15.0	8.44	11.72	6.56	42
Long Pond (MDI)	5/22/2014	16.0	7.66	11.85	6.52	42
Long Pond (MDI)	5/22/2014	17.0	7.47	11.87	6.50	42
Long Pond (MDI)	5/22/2014	18.0	7.38	11.88	6.48	42
Long Pond (MDI)	5/22/2014	19.0	7.31	11.89	6.47	42
Long Pond (MDI)	5/22/2014	20.0	7.26	11.88	6.47	42
Long Pond (MDI)	5/22/2014	20.0	7.27	11.88	6.46	42

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Long Pond (MDI)	5/22/2014	21.0	7.24	11.88	6.47	42
Long Pond (MDI)	5/22/2014	22.0	7.24	11.88	6.49	42
Long Pond (MDI)	5/22/2014	23.0	7.23	11.88	6.49	42
Long Pond (MDI)	5/22/2014	24.0	7.18	11.87	6.50	42
Long Pond (MDI)	5/22/2014	25.0	7.17	11.82	6.49	42
Long Pond (MDI)	5/22/2014	26.0	7.17	11.84	6.50	42
Long Pond (MDI)	5/22/2014	27.0	7.14	11.83	6.50	42
Long Pond (MDI)	5/22/2014	28.0	7.10	11.81	6.49	42
Long Pond (MDI)	5/22/2014	29.0	7.07	11.77	6.49	42
Long Pond (MDI)	5/22/2014	30.0	7.06	11.77	6.49	42
Long Pond (MDI)	6/23/2014	0.1	19.42	10.16	7.05	43
Long Pond (MDI)	6/23/2014	0.5	19.38	10.11	7.01	43
Long Pond (MDI)	6/23/2014	1.0	19.30	10.10	7.00	43
Long Pond (MDI)	6/23/2014	2.0	18.42	10.15	7.01	43
Long Pond (MDI)	6/23/2014	2.0	18.42	10.14	7.01	43
Long Pond (MDI)	6/23/2014	3.0	18.27	10.13	7.00	43
Long Pond (MDI)	6/23/2014	4.0	18.07	10.12	6.99	43
Long Pond (MDI)	6/23/2014	5.0	17.77	10.12	6.98	43
Long Pond (MDI)	6/23/2014	6.0	17.57	10.12	6.95	43
Long Pond (MDI)	6/23/2014	7.0	17.23	10.12	6.92	43
Long Pond (MDI)	6/23/2014	8.0	16.85	10.14	6.88	43
Long Pond (MDI)	6/23/2014	9.0	14.69	10.44	6.76	43
Long Pond (MDI)	6/23/2014	9.0	14.67	10.44	6.77	43
Long Pond (MDI)	6/23/2014	10.0	12.70	10.69	6.86	43
Long Pond (MDI)	6/23/2014	11.0	11.49	10.84	6.88	43
Long Pond (MDI)	6/23/2014	12.0	10.99	10.92	6.86	43
Long Pond (MDI)	6/23/2014	13.0	10.31	10.93	6.83	43
Long Pond (MDI)	6/23/2014	14.0	9.40	11.10	6.81	43

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Long Pond (MDI)	6/23/2014	15.0	8.79	11.27	6.82	43
Long Pond (MDI)	6/23/2014	16.0	8.46	11.33	6.78	43
Long Pond (MDI)	6/23/2014	17.0	8.17	11.41	6.71	43
Long Pond (MDI)	6/23/2014	18.0	7.93	11.41	6.66	43
Long Pond (MDI)	6/23/2014	19.0	7.81	11.40	6.53	43
Long Pond (MDI)	6/23/2014	20.0	7.68	11.41	6.50	43
Long Pond (MDI)	6/23/2014	21.0	7.65	11.39	6.47	43
Long Pond (MDI)	6/23/2014	22.0	7.61	11.41	6.45	43
Long Pond (MDI)	6/23/2014	23.0	7.55	11.39	6.43	43
Long Pond (MDI)	6/23/2014	24.0	7.53	11.38	6.41	43
Long Pond (MDI)	6/23/2014	25.0	7.50	11.38	6.40	43
Long Pond (MDI)	6/23/2014	26.0	7.49	11.38	6.40	43
Long Pond (MDI)	6/23/2014	27.0	7.47	11.36	6.39	43
Long Pond (MDI)	6/23/2014	28.0	7.45	11.31	6.38	43
Long Pond (MDI)	6/23/2014	29.0	7.44	11.31	6.37	43
Long Pond (MDI)	6/23/2014	30.0	7.40	11.28	6.36	43
Long Pond (MDI)	7/28/2014	0.1	20.42	8.67	7.01	43
Long Pond (MDI)	7/28/2014	0.5	20.46	8.62	6.97	43
Long Pond (MDI)	7/28/2014	1.0	20.46	8.60	6.95	43
Long Pond (MDI)	7/28/2014	2.0	20.46	8.61	6.92	43
Long Pond (MDI)	7/28/2014	3.0	20.46	8.60	6.89	43
Long Pond (MDI)	7/28/2014	4.0	20.46	8.60	6.86	43
Long Pond (MDI)	7/28/2014	5.0	20.45	8.59	6.85	43
Long Pond (MDI)	7/28/2014	6.0	20.44	8.58	6.83	43
Long Pond (MDI)	7/28/2014	7.0	20.43	8.58	6.82	43
Long Pond (MDI)	7/28/2014	8.0	20.05	8.50	6.74	43
Long Pond (MDI)	7/28/2014	9.0	19.25	8.36	6.62	41
Long Pond (MDI)	7/28/2014	10.0	16.65	8.36	6.44	43

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Long Pond (MDI)	7/28/2014	11.0	14.67	8.60	6.31	43
Long Pond (MDI)	7/28/2014	12.0	13.31	8.82	6.27	43
Long Pond (MDI)	7/28/2014	13.0	12.07	9.09	6.23	43
Long Pond (MDI)	7/28/2014	14.0	11.42	9.25	6.21	43
Long Pond (MDI)	7/28/2014	15.0	10.74	9.42	6.22	41
Long Pond (MDI)	7/28/2014	16.0	9.86	9.65	6.22	43
Long Pond (MDI)	7/28/2014	17.0	9.31	9.80	6.22	43
Long Pond (MDI)	7/28/2014	18.0	9.16	9.87	6.22	43
Long Pond (MDI)	7/28/2014	19.0	8.87	9.94	6.22	43
Long Pond (MDI)	7/28/2014	20.0	8.58	10.02	6.22	43
Long Pond (MDI)	7/28/2014	21.0	8.49	10.06	6.22	43
Long Pond (MDI)	7/28/2014	22.0	8.31	10.09	6.23	43
Long Pond (MDI)	7/28/2014	23.0	8.20	10.12	6.22	43
Long Pond (MDI)	7/28/2014	24.0	8.17	10.12	6.23	43
Long Pond (MDI)	7/28/2014	25.0	8.10	10.11	6.23	43
Long Pond (MDI)	7/28/2014	26.0	7.91	10.10	6.22	43
Long Pond (MDI)	7/28/2014	27.0	7.87	10.10	6.22	43
Long Pond (MDI)	7/28/2014	28.0	7.81	10.02	6.21	43
Long Pond (MDI)	7/28/2014	29.0	7.77	9.93	6.20	43
Long Pond (MDI)	7/28/2014	30.0	7.74	9.91	6.19	43
Long Pond (MDI)	8/20/2014	0.1	22.23	8.86	7.14	44
Long Pond (MDI)	8/20/2014	0.5	21.58	8.95	7.02	44
Long Pond (MDI)	8/20/2014	1.0	21.02	8.96	6.95	44
Long Pond (MDI)	8/20/2014	2.0	20.61	8.98	6.95	44
Long Pond (MDI)	8/20/2014	3.0	20.49	8.93	6.94	45
Long Pond (MDI)	8/20/2014	3.0	20.49	8.94	6.93	45
Long Pond (MDI)	8/20/2014	4.0	20.44	8.92	6.92	45
Long Pond (MDI)	8/20/2014	5.0	20.41	8.92	6.92	44

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Long Pond (MDI)	8/20/2014	6.0	20.34	8.92	6.90	44
Long Pond (MDI)	8/20/2014	7.0	20.30	8.88	6.88	45
Long Pond (MDI)	8/20/2014	8.0	20.17	8.80	6.84	44
Long Pond (MDI)	8/20/2014	9.0	19.55	8.54	6.68	44
Long Pond (MDI)	8/20/2014	10.0	18.92	8.19	6.53	44
Long Pond (MDI)	8/20/2014	11.0	14.70	8.03	6.28	44
Long Pond (MDI)	8/20/2014	12.0	13.73	7.94	6.18	43
Long Pond (MDI)	8/20/2014	13.0	12.76	8.19	6.15	43
Long Pond (MDI)	8/20/2014	14.0	11.67	8.52	6.15	43
Long Pond (MDI)	8/20/2014	15.0	10.87	8.75	6.14	43
Long Pond (MDI)	8/20/2014	16.0	10.36	8.91	6.07	43
Long Pond (MDI)	8/20/2014	17.0	9.91	9.08	5.91	43
Long Pond (MDI)	8/20/2014	18.0	9.67	9.12	5.91	43
Long Pond (MDI)	8/20/2014	19.0	9.23	9.26	5.96	43
Long Pond (MDI)	8/20/2014	20.0	9.04	9.35	6.01	43
Long Pond (MDI)	8/20/2014	21.0	8.78	9.41	6.02	43
Long Pond (MDI)	8/20/2014	22.0	8.45	9.45	6.01	43
Long Pond (MDI)	8/20/2014	22.0	8.37	9.37	5.98	43
Long Pond (MDI)	8/20/2014	23.0	8.37	9.48	6.01	43
Long Pond (MDI)	8/20/2014	24.0	8.21	9.50	6.00	43
Long Pond (MDI)	8/20/2014	25.0	8.08	9.50	5.99	43
Long Pond (MDI)	8/20/2014	26.0	7.96	9.45	5.99	43
Long Pond (MDI)	8/20/2014	27.0	7.84	9.29	5.97	43
Long Pond (MDI)	8/20/2014	28.0	7.76	9.21	5.96	43
Long Pond (MDI)	8/20/2014	29.0	7.71	9.10	5.95	43
Long Pond (MDI)	8/20/2014	30.0	7.67	8.96	5.93	43
Long Pond (MDI)	9/18/2014	0.1	18.28	9.08	6.77	43
Long Pond (MDI)	9/18/2014	0.5	18.28	9.04	6.75	43

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Long Pond (MDI)	9/18/2014	1.0	18.27	9.02	6.73	43
Long Pond (MDI)	9/18/2014	2.0	18.27	9.02	6.72	43
Long Pond (MDI)	9/18/2014	3.0	18.26	9.01	6.71	44
Long Pond (MDI)	9/18/2014	3.0	18.27	9.01	6.71	46
Long Pond (MDI)	9/18/2014	4.0	18.26	9.01	6.69	43
Long Pond (MDI)	9/18/2014	5.0	18.25	9.00	6.69	45
Long Pond (MDI)	9/18/2014	6.0	18.18	8.96	6.68	44
Long Pond (MDI)	9/18/2014	7.0	18.17	8.96	6.68	44
Long Pond (MDI)	9/18/2014	8.0	18.17	8.96	6.67	44
Long Pond (MDI)	9/18/2014	9.0	18.08	8.92	6.64	44
Long Pond (MDI)	9/18/2014	10.0	17.99	8.90	6.65	44
Long Pond (MDI)	9/18/2014	11.0	18.01	8.91	6.62	44
Long Pond (MDI)	9/18/2014	12.0	17.93	8.88	6.63	44
Long Pond (MDI)	9/18/2014	13.0	17.87	8.85	6.60	44
Long Pond (MDI)	9/18/2014	14.0	16.01	7.71	6.13	43
Long Pond (MDI)	9/18/2014	15.0	10.91	8.01	5.77	45
Long Pond (MDI)	9/18/2014	16.0	9.99	8.28	5.77	43
Long Pond (MDI)	9/18/2014	17.0	9.09	8.58	5.72	43
Long Pond (MDI)	9/18/2014	18.0	8.74	8.66	5.62	43
Long Pond (MDI)	9/18/2014	19.0	8.52	8.74	5.57	43
Long Pond (MDI)	9/18/2014	20.0	8.27	8.81	5.51	45
Long Pond (MDI)	9/18/2014	21.0	8.16	8.76	5.51	43
Long Pond (MDI)	9/18/2014	22.0	8.06	8.76	5.56	43
Long Pond (MDI)	9/18/2014	23.0	7.98	8.70	5.64	43
Long Pond (MDI)	9/18/2014	24.0	7.92	8.66	5.69	43
Long Pond (MDI)	9/18/2014	25.0	7.85	8.56	5.69	43
Long Pond (MDI)	9/18/2014	26.0	7.81	8.40	5.67	45
Long Pond (MDI)	9/18/2014	27.0	7.76	8.30	5.62	43

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Long Pond (MDI)	9/18/2014	28.0	7.74	8.24	5.59	43
Long Pond (MDI)	9/18/2014	29.0	7.70	8.19	5.57	43
Long Pond (MDI)	9/18/2014	30.0	7.68	8.07	5.56	43
Long Pond (MDI)	10/21/2014	0.1	13.82	9.90	6.61	43
Long Pond (MDI)	10/21/2014	0.5	13.82	9.89	6.61	43
Long Pond (MDI)	10/21/2014	1.0	13.82	9.89	6.63	46
Long Pond (MDI)	10/21/2014	2.0	13.82	9.89	6.65	43
Long Pond (MDI)	10/21/2014	3.0	13.82	9.90	6.64	43
Long Pond (MDI)	10/21/2014	4.0	13.82	9.88	6.61	43
Long Pond (MDI)	10/21/2014	5.0	13.82	9.84	6.64	43
Long Pond (MDI)	10/21/2014	6.0	13.81	9.84	6.59	43
Long Pond (MDI)	10/21/2014	7.0	13.80	9.84	6.60	43
Long Pond (MDI)	10/21/2014	8.0	13.79	9.83	6.61	43
Long Pond (MDI)	10/21/2014	9.0	13.79	9.82	6.58	43
Long Pond (MDI)	10/21/2014	10.0	13.79	9.83	6.57	43
Long Pond (MDI)	10/21/2014	11.0	13.78	9.84	6.60	43
Long Pond (MDI)	10/21/2014	12.0	13.77	9.84	6.62	43
Long Pond (MDI)	10/21/2014	13.0	13.75	9.81	6.58	43
Long Pond (MDI)	10/21/2014	14.0	13.74	9.79	6.57	43
Long Pond (MDI)	10/21/2014	15.0	13.73	9.79	6.60	43
Long Pond (MDI)	10/21/2014	16.0	13.63	9.76	6.60	43
Long Pond (MDI)	10/21/2014	17.0	12.85	9.70	6.49	43
Long Pond (MDI)	10/21/2014	18.0	12.06	9.11	6.31	43
Long Pond (MDI)	10/21/2014	19.0	9.91	8.43	6.11	43
Long Pond (MDI)	10/21/2014	20.0	8.87	8.13	5.97	43
Long Pond (MDI)	10/21/2014	21.0	8.39	8.09	5.91	43
Long Pond (MDI)	10/21/2014	22.0	8.20	8.02	5.86	43
Long Pond (MDI)	10/21/2014	23.0	7.99	8.01	5.80	43

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Long Pond (MDI)	10/21/2014	24.0	7.91	7.97	5.74	43
Long Pond (MDI)	10/21/2014	25.0	7.80	7.78	5.70	43
Long Pond (MDI)	10/21/2014	26.0	7.74	7.67	5.69	43
Long Pond (MDI)	10/21/2014	27.0	7.69	7.55	5.62	43
Long Pond (MDI)	10/21/2014	28.0	7.66	7.37	5.61	43
Long Pond (MDI)	10/21/2014	29.0	7.65	7.28	5.54	43
Long Pond (MDI)	10/21/2014	30.0	7.62	7.19	5.48	46
Round Pond	5/23/2014	0.1	16.58	9.84	6.48	36
Round Pond	5/23/2014	0.5	16.49	9.85	6.30	36
Round Pond	5/23/2014	1.0	16.29	9.90	6.29	36
Round Pond	5/23/2014	2.0	15.08	10.03	6.24	35
Round Pond	5/23/2014	3.0	14.29	9.81	6.13	35
Round Pond	5/23/2014	4.0	13.86	9.19	5.97	36
Round Pond	5/23/2014	5.0	12.98	3.49	5.91	49
Round Pond	5/23/2014	5.0	12.96	2.57	5.91	49
Round Pond	6/19/2014	0.1	21.35	9.30	6.69	37
Round Pond	6/19/2014	0.5	21.19	9.31	6.61	37
Round Pond	6/19/2014	1.0	20.80	9.33	6.56	37
Round Pond	6/19/2014	2.0	20.30	9.35	6.53	37
Round Pond	6/19/2014	2.0	20.42	9.18	6.40	37
Round Pond	6/19/2014	3.0	19.27	9.36	6.49	37
Round Pond	6/19/2014	4.0	18.27	8.71	6.38	37
Round Pond	6/19/2014	5.0	15.49	1.76	6.02	40
Round Pond	6/19/2014	5.1	15.55	1.54	6.23	54
Round Pond	7/28/2014	0.1	23.21	7.84	6.38	39
Round Pond	7/28/2014	0.5	23.21	7.84	6.28	39
Round Pond	7/28/2014	1.0	23.21	7.84	6.23	41
Round Pond	7/28/2014	2.0	23.13	7.81	6.20	41

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Round Pond	7/28/2014	3.0	22.50	7.28	6.04	39
Round Pond	7/28/2014	4.0	19.71	1.68	5.69	39
Round Pond	7/28/2014	5.0	16.95	0.18	6.23	63
Round Pond	7/28/2014	5.0	16.96	0.12	6.26	66
Round Pond	8/21/2014	2.0	21.63	8.35	6.22	39
Round Pond	8/21/2014	3.0	20.85	7.42	6.00	39
Round Pond	8/21/2014	4.0	20.20	4.67	5.73	40
Round Pond	8/21/2014	5.0	17.46	0.25	6.08	70
Round Pond	8/21/2014	5.4	16.68	0.16	6.06	85
Round Pond	8/26/2014	0.1	23.75	8.31	6.83	40
Round Pond	8/26/2014	0.5	23.73	8.33	6.56	40
Round Pond	8/26/2014	1.0	23.54	8.33	6.39	40
Round Pond	8/26/2014	2.0	21.88	8.18	6.08	39
Round Pond	8/26/2014	3.0	21.11	6.71	5.91	39
Round Pond	8/26/2014	4.0	19.91	2.31	5.60	41
Round Pond	8/26/2014	5.0	18.42	0.18	5.87	57
Round Pond	9/22/2014	0.1	17.73	9.11	6.28	40
Round Pond	9/22/2014	0.5	17.67	9.11	6.25	40
Round Pond	9/22/2014	1.0	17.50	9.08	6.17	40
Round Pond	9/22/2014	2.0	17.09	8.95	6.12	40
Round Pond	9/22/2014	3.0	16.62	8.68	6.02	40
Round Pond	9/22/2014	4.0	16.55	8.70	5.93	40
Round Pond	9/22/2014	5.0	16.46	8.64	5.92	40
Round Pond	9/22/2014	5.2	16.39	7.27	5.74	46
Round Pond	10/24/2014	0.1	11.54	9.76	5.98	38
Round Pond	10/24/2014	0.5	11.54	9.71	6.00	38
Round Pond	10/24/2014	1.0	11.54	9.70	6.02	38
Round Pond	10/24/2014	2.0	11.54	9.68	5.97	38

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Round Pond	10/24/2014	3.0	11.53	9.67	6.00	38
Round Pond	10/24/2014	4.0	11.51	9.65	5.97	38
Round Pond	10/24/2014	5.0	11.49	9.60	5.96	38
Round Pond	10/24/2014	5.0	11.48	9.62	5.95	38
Seal Cove Pond	4/28/2014	0.4	9.08	11.25	6.65	51
Seal Cove Pond	5/22/2014	0.1	14.63	10.24	6.70	43
Seal Cove Pond	5/22/2014	0.5	14.63	10.24	6.69	43
Seal Cove Pond	5/22/2014	1.0	14.59	10.23	6.68	43
Seal Cove Pond	5/22/2014	2.0	14.47	10.22	6.67	43
Seal Cove Pond	5/22/2014	3.0	14.35	10.20	6.66	43
Seal Cove Pond	5/22/2014	4.0	13.83	10.21	6.65	43
Seal Cove Pond	5/22/2014	5.0	13.52	10.23	6.65	43
Seal Cove Pond	5/22/2014	6.0	13.27	10.15	6.61	43
Seal Cove Pond	5/22/2014	7.0	13.21	10.09	6.58	43
Seal Cove Pond	5/22/2014	8.0	13.13	10.02	6.56	43
Seal Cove Pond	5/22/2014	9.0	12.90	9.89	6.50	42
Seal Cove Pond	5/22/2014	10.0	11.73	9.56	6.35	42
Seal Cove Pond	5/22/2014	11.0	10.09	9.41	6.24	44
Seal Cove Pond	5/22/2014	12.0	9.76	7.96	6.07	45
Seal Cove Pond	5/22/2014	13.0	9.68	7.26	6.01	45
Seal Cove Pond	5/22/2014	13.3	9.61	2.34	5.95	44
Seal Cove Pond	6/24/2014	0.1	20.39	9.10	7.00	45
Seal Cove Pond	6/24/2014	0.5	20.40	9.11	6.93	45
Seal Cove Pond	6/24/2014	1.0	20.36	9.12	6.91	45
Seal Cove Pond	6/24/2014	2.0	20.31	9.13	6.88	45
Seal Cove Pond	6/24/2014	3.0	19.96	9.17	6.86	45
Seal Cove Pond	6/24/2014	4.0	19.89	9.16	6.84	45
Seal Cove Pond	6/24/2014	5.0	19.57	8.91	6.70	45

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Seal Cove Pond	6/24/2014	6.0	17.14	7.83	6.28	45
Seal Cove Pond	6/24/2014	7.0	16.48	7.60	6.10	44
Seal Cove Pond	6/24/2014	8.0	15.68	7.20	5.99	44
Seal Cove Pond	6/24/2014	9.0	12.67	6.02	5.75	45
Seal Cove Pond	6/24/2014	10.0	12.36	5.82	5.73	45
Seal Cove Pond	6/24/2014	11.0	12.15	5.56	5.72	45
Seal Cove Pond	6/24/2014	12.0	11.99	5.26	5.71	45
Seal Cove Pond	6/24/2014	12.5	11.87	4.33	5.70	45
Seal Cove Pond	7/28/2014	0.1	22.08	8.25	7.04	44
Seal Cove Pond	7/28/2014	0.5	22.10	8.21	6.79	44
Seal Cove Pond	7/28/2014	1.0	22.10	8.20	6.75	44
Seal Cove Pond	7/28/2014	2.0	22.09	8.19	6.74	47
Seal Cove Pond	7/28/2014	3.0	22.08	8.17	6.72	44
Seal Cove Pond	7/28/2014	4.0	22.05	8.15	6.68	44
Seal Cove Pond	7/28/2014	5.0	22.00	8.10	6.68	44
Seal Cove Pond	7/28/2014	6.0	20.14	5.80	6.20	44
Seal Cove Pond	7/28/2014	7.0	18.28	4.10	5.95	44
Seal Cove Pond	7/28/2014	8.0	16.92	3.72	5.89	44
Seal Cove Pond	7/28/2014	8.0	16.93	3.80	5.90	44
Seal Cove Pond	7/28/2014	9.0	14.68	3.10	5.85	45
Seal Cove Pond	7/28/2014	10.0	13.35	2.43	5.83	46
Seal Cove Pond	7/28/2014	11.0	12.55	1.79	5.83	47
Seal Cove Pond	7/28/2014	12.0	12.25	1.34	5.84	48
Seal Cove Pond	7/28/2014	13.0	11.97	0.93	5.83	49
Seal Cove Pond	7/28/2014	13.3	11.90	0.64	5.96	55
Seal Cove Pond	8/21/2014	0.1	22.24	8.86	7.05	45
Seal Cove Pond	8/21/2014	0.5	22.21	8.85	7.02	44
Seal Cove Pond	8/21/2014	1.0	22.16	8.86	7.00	44

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Seal Cove Pond	8/21/2014	2.0	21.45	8.85	6.91	44
Seal Cove Pond	8/21/2014	3.0	21.33	8.82	6.88	44
Seal Cove Pond	8/21/2014	3.9	21.10	8.52	6.75	44
Seal Cove Pond	8/21/2014	5.1	20.76	8.30	6.66	44
Seal Cove Pond	8/21/2014	6.0	20.56	7.74	6.50	44
Seal Cove Pond	8/21/2014	7.0	20.36	7.03	6.34	44
Seal Cove Pond	8/21/2014	8.0	18.74	3.64	5.96	43
Seal Cove Pond	8/21/2014	8.0	18.70	3.70	5.96	45
Seal Cove Pond	8/21/2014	9.0	14.30	0.57	5.63	47
Seal Cove Pond	8/21/2014	9.0	14.27	0.59	5.68	47
Seal Cove Pond	8/21/2014	10.0	13.09	0.14	5.62	49
Seal Cove Pond	8/21/2014	11.0	12.73	0.11	5.68	49
Seal Cove Pond	8/21/2014	12.0	12.58	0.10	5.76	51
Seal Cove Pond	8/21/2014	12.8	12.47	0.08	6.05	73
Seal Cove Pond	9/22/2014	0.1	17.04	9.12	6.45	44
Seal Cove Pond	9/22/2014	0.5	17.01	9.12	6.45	44
Seal Cove Pond	9/22/2014	1.0	16.97	9.12	6.46	44
Seal Cove Pond	9/22/2014	2.0	16.92	9.10	6.49	44
Seal Cove Pond	9/22/2014	3.0	16.89	9.11	6.46	44
Seal Cove Pond	9/22/2014	4.0	16.86	9.10	6.47	44
Seal Cove Pond	9/22/2014	5.0	16.86	9.09	6.46	44
Seal Cove Pond	9/22/2014	6.0	16.85	9.09	6.43	44
Seal Cove Pond	9/22/2014	7.0	16.84	9.07	6.46	44
Seal Cove Pond	9/22/2014	8.0	16.73	9.01	6.45	44
Seal Cove Pond	9/22/2014	9.0	16.67	9.00	6.44	44
Seal Cove Pond	9/22/2014	10.0	16.53	8.82	6.37	44
Seal Cove Pond	9/22/2014	11.0	15.99	8.09	6.14	45
Seal Cove Pond	9/22/2014	12.0	15.81	7.24	5.91	45

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Seal Cove Pond	9/22/2014	12.0	15.81	7.78	5.98	45
Seal Cove Pond	10/27/2014	0.1	11.42	10.32	6.24	43
Seal Cove Pond	10/27/2014	0.5	11.42	10.24	6.32	42
Seal Cove Pond	10/27/2014	1.0	11.41	10.21	6.38	43
Seal Cove Pond	10/27/2014	2.0	11.41	10.20	6.38	43
Seal Cove Pond	10/27/2014	3.0	11.40	10.20	6.42	44
Seal Cove Pond	10/27/2014	4.0	11.40	10.20	6.43	44
Seal Cove Pond	10/27/2014	5.0	11.40	10.19	6.41	44
Seal Cove Pond	10/27/2014	6.0	11.40	10.20	6.39	44
Seal Cove Pond	10/27/2014	7.0	11.39	10.21	6.39	44
Seal Cove Pond	10/27/2014	8.0	11.37	10.19	6.41	44
Seal Cove Pond	10/27/2014	9.0	11.33	10.18	6.41	44
Seal Cove Pond	10/27/2014	10.0	11.31	10.17	6.41	44
Seal Cove Pond	10/27/2014	11.0	11.28	10.17	6.40	44
Seal Cove Pond	10/27/2014	12.0	11.25	10.17	6.39	44
Seal Cove Pond	10/27/2014	13.0	11.23	10.16	6.41	44
Upper Breakneck	5/28/2014	0.1	15.42	8.02	6.80	57
Upper Breakneck	5/28/2014	0.5	15.41	7.89	6.55	57
Upper Breakneck	5/28/2014	1.0	15.40	7.79	6.46	57
Upper Breakneck	5/28/2014	2.0	15.18	7.46	6.34	56
Upper Breakneck	5/28/2014	3.0	14.81	7.04	6.23	54
Upper Breakneck	5/28/2014	3.7	13.76	3.40	6.17	57
Upper Breakneck	5/28/2014	3.7	13.70	2.43	6.18	66
Upper Breakneck	6/18/2014	0.1	20.14	8.66	7.22	59
Upper Breakneck	6/18/2014	0.5	20.14	8.62	6.81	59
Upper Breakneck	6/18/2014	1.0	20.05	8.64	6.79	59
Upper Breakneck	6/18/2014	2.0	18.86	7.53	6.47	53
Upper Breakneck	6/18/2014	3.0	16.67	6.23	6.40	49

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Upper Breakneck	6/18/2014	3.8	15.72	3.74	6.37	45
Upper Breakneck	6/18/2014	3.8	15.69	4.20	6.40	45
Upper Breakneck	7/23/2014	0.1	23.31	8.58	6.56	42
Upper Breakneck	7/23/2014	0.5	23.11	8.67	6.54	41
Upper Breakneck	7/23/2014	1.0	22.30	8.66	6.44	40
Upper Breakneck	7/23/2014	2.0	17.93	7.79	5.85	23
Upper Breakneck	7/23/2014	3.0	15.75	2.39	5.68	28
Upper Breakneck	7/23/2014	3.5	15.06	0.17	5.86	36
Upper Breakneck	8/25/2014	0.1	22.02	8.16	6.56	51
Upper Breakneck	8/25/2014	0.1	22.04	8.20	6.56	51
Upper Breakneck	8/25/2014	0.5	21.54	8.20	6.46	53
Upper Breakneck	8/25/2014	1.0	21.22	7.96	6.42	52
Upper Breakneck	8/25/2014	2.0	20.11	4.36	5.95	49
Upper Breakneck	8/25/2014	2.0	20.07	4.32	5.71	49
Upper Breakneck	8/25/2014	3.0	18.11	0.67	5.58	43
Upper Breakneck	8/25/2014	3.5	16.91	0.12	5.82	55
Upper Breakneck	9/16/2014	0.1	15.93	7.75	6.27	51
Upper Breakneck	9/16/2014	0.5	15.92	7.79	6.26	51
Upper Breakneck	9/16/2014	1.0	15.89	7.91	6.32	51
Upper Breakneck	9/16/2014	2.0	15.84	7.93	6.31	51
Upper Breakneck	9/16/2014	3.0	15.75	7.53	6.26	51
Upper Breakneck	9/16/2014	3.0	15.76	6.94	6.21	51
Upper Breakneck	10/27/2014	0.1	9.35	8.20	5.15	44
Upper Breakneck	10/27/2014	0.5	9.35	8.17	5.12	44
Upper Breakneck	10/27/2014	1.0	9.32	8.11	5.11	44
Upper Breakneck	10/27/2014	2.0	9.14	7.52	5.07	44
Upper Breakneck	10/27/2014	3.0	8.87	7.28	5.02	44
Upper Breakneck	10/27/2014	3.5	8.82	7.12	5.04	45

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Upper Hadlock	4/23/2014	0.2	9.60	11.58	5.41	51
Upper Hadlock	5/20/2014	0.1	14.34	10.11	6.42	48
Upper Hadlock	5/20/2014	0.5	14.32	10.09	6.41	48
Upper Hadlock	5/20/2014	1.0	14.26	10.10	6.40	48
Upper Hadlock	5/20/2014	2.0	14.23	10.10	6.40	48
Upper Hadlock	5/20/2014	3.0	14.21	10.06	6.39	48
Upper Hadlock	5/20/2014	3.0	14.18	9.45	6.23	49
Upper Hadlock	5/20/2014	4.0	14.17	10.06	6.39	48
Upper Hadlock	5/20/2014	5.0	12.31	10.36	6.22	44
Upper Hadlock	5/20/2014	6.0	9.04	11.09	5.84	45
Upper Hadlock	5/20/2014	7.0	8.14	10.88	5.73	44
Upper Hadlock	5/20/2014	8.0	7.79	10.26	5.64	44
Upper Hadlock	5/20/2014	9.0	7.64	10.05	5.65	44
Upper Hadlock	5/20/2014	10.0	7.56	9.90	5.67	44
Upper Hadlock	5/20/2014	10.0	7.54	9.20	5.73	44
Upper Hadlock	5/20/2014	11.0	7.51	9.85	5.67	44
Upper Hadlock	5/20/2014	12.0	7.49	9.80	5.68	44
Upper Hadlock	5/20/2014	12.9	7.47	9.44	5.67	44
Upper Hadlock	6/16/2014	0.5	17.73	9.78	6.86	48
Upper Hadlock	6/16/2014	1.0	17.70	9.77	6.75	48
Upper Hadlock	6/16/2014	2.0	17.62	9.74	6.68	48
Upper Hadlock	6/16/2014	3.0	17.61	9.74	6.63	48
Upper Hadlock	6/16/2014	4.0	17.54	9.69	6.62	48
Upper Hadlock	6/16/2014	5.0	13.60	10.38	6.44	45
Upper Hadlock	6/16/2014	6.0	10.09	10.86	6.39	46
Upper Hadlock	6/16/2014	7.0	8.41	10.11	6.36	46
Upper Hadlock	6/16/2014	8.0	7.76	8.75	6.33	46
Upper Hadlock	6/16/2014	9.0	7.36	8.59	6.30	46

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Upper Hadlock	6/16/2014	10.0	7.25	8.21	6.31	46
Upper Hadlock	6/16/2014	11.0	7.19	7.94	6.28	46
Upper Hadlock	6/16/2014	12.0	7.11	7.84	6.26	46
Upper Hadlock	6/16/2014	13.0	7.07	7.54	6.22	47
Upper Hadlock	6/16/2014	13.1	7.06	7.01	6.26	50
Upper Hadlock	7/31/2014	0.1	21.74	8.38	6.63	38
Upper Hadlock	7/31/2014	0.5	21.73	8.38	6.55	38
Upper Hadlock	7/31/2014	1.0	21.72	8.37	6.53	38
Upper Hadlock	7/31/2014	2.0	21.61	8.31	6.47	38
Upper Hadlock	7/31/2014	3.0	19.32	8.75	5.99	32
Upper Hadlock	7/31/2014	4.0	16.49	5.80	5.64	34
Upper Hadlock	7/31/2014	5.0	14.89	5.03	5.67	36
Upper Hadlock	7/31/2014	6.0	12.42	5.85	5.66	43
Upper Hadlock	7/31/2014	7.0	9.96	5.65	5.60	47
Upper Hadlock	7/31/2014	8.0	8.73	5.03	5.60	47
Upper Hadlock	7/31/2014	9.0	8.22	4.42	5.58	47
Upper Hadlock	7/31/2014	10.0	7.88	4.11	5.57	47
Upper Hadlock	7/31/2014	11.0	7.74	3.74	5.57	47
Upper Hadlock	7/31/2014	12.0	7.72	3.50	5.59	47
Upper Hadlock	7/31/2014	12.2	7.66	2.41	5.56	57
Upper Hadlock	8/18/2014	0.1	20.41	8.65	6.83	38
Upper Hadlock	8/18/2014	0.5	20.41	8.65	6.66	38
Upper Hadlock	8/18/2014	1.0	20.42	8.63	6.58	38
Upper Hadlock	8/18/2014	2.0	20.34	8.60	6.53	38
Upper Hadlock	8/18/2014	3.0	20.24	8.55	6.51	38
Upper Hadlock	8/18/2014	4.0	18.59	5.80	6.04	38
Upper Hadlock	8/18/2014	5.0	15.25	4.12	5.76	38
Upper Hadlock	8/18/2014	6.0	12.66	4.51	5.64	43

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Upper Hadlock	8/18/2014	7.0	10.15	4.67	5.59	47
Upper Hadlock	8/18/2014	8.0	8.71	3.92	5.53	47
Upper Hadlock	8/18/2014	9.0	8.21	2.97	5.50	47
Upper Hadlock	8/18/2014	10.0	7.90	2.47	5.64	48
Upper Hadlock	8/18/2014	11.0	7.80	2.29	5.66	48
Upper Hadlock	8/18/2014	12.0	7.74	2.01	5.68	48
Upper Hadlock	8/18/2014	13.0	7.70	1.75	5.67	48
Upper Hadlock	8/18/2014	13.2	7.68	1.50	5.86	59
Upper Hadlock	9/17/2014	0.1	17.11	9.14	6.54	40
Upper Hadlock	9/17/2014	0.5	17.00	9.14	6.52	40
Upper Hadlock	9/17/2014	1.0	16.78	9.16	6.48	40
Upper Hadlock	9/17/2014	2.0	16.57	9.14	6.48	40
Upper Hadlock	9/17/2014	3.0	16.44	9.08	6.43	40
Upper Hadlock	9/17/2014	4.0	16.32	9.06	6.43	40
Upper Hadlock	9/17/2014	5.0	16.09	8.96	6.38	40
Upper Hadlock	9/17/2014	6.0	15.95	8.84	6.33	40
Upper Hadlock	9/17/2014	7.0	10.74	4.11	5.53	46
Upper Hadlock	9/17/2014	8.0	9.19	2.00	5.26	47
Upper Hadlock	9/17/2014	9.0	8.44	0.88	5.14	48
Upper Hadlock	9/17/2014	10.0	8.13	0.44	5.09	49
Upper Hadlock	9/17/2014	11.0	8.01	0.31	5.22	49
Upper Hadlock	9/17/2014	12.0	7.97	0.24	5.40	49
Upper Hadlock	10/20/2014	0.1	11.90	9.81	6.41	41
Upper Hadlock	10/20/2014	0.5	11.90	9.67	5.92	41
Upper Hadlock	10/20/2014	1.0	11.88	9.66	5.88	41
Upper Hadlock	10/20/2014	2.0	11.85	9.62	5.87	43
Upper Hadlock	10/20/2014	3.0	11.81	9.62	5.85	41
Upper Hadlock	10/20/2014	4.0	11.80	9.61	5.84	41

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Upper Hadlock	10/20/2014	5.0	11.78	9.56	5.87	41
Upper Hadlock	10/20/2014	6.0	11.77	9.54	5.87	41
Upper Hadlock	10/20/2014	7.0	11.73	9.55	5.84	41
Upper Hadlock	10/20/2014	8.0	11.60	9.24	5.81	42
Upper Hadlock	10/20/2014	9.0	11.52	8.86	5.75	42
Upper Hadlock	10/20/2014	10.0	11.31	8.43	5.70	43
Upper Hadlock	10/20/2014	11.0	10.97	7.89	5.71	44
Upper Hadlock	10/20/2014	11.8	10.10	5.61	5.58	48
Witch Hole Pond	4/29/2014	0.2	11.27	11.10	6.19	23
Witch Hole Pond	5/28/2014	0.1	15.72	9.19	6.50	24
Witch Hole Pond	5/28/2014	0.5	15.74	9.09	6.42	24
Witch Hole Pond	5/28/2014	1.0	15.73	9.10	6.40	24
Witch Hole Pond	5/28/2014	2.0	15.73	9.09	6.37	24
Witch Hole Pond	5/28/2014	3.0	15.62	9.07	6.37	24
Witch Hole Pond	5/28/2014	4.0	14.18	8.74	6.18	24
Witch Hole Pond	5/28/2014	5.0	12.58	7.97	6.03	24
Witch Hole Pond	5/28/2014	6.0	10.00	6.53	5.81	24
Witch Hole Pond	5/28/2014	7.0	9.21	5.26	5.75	24
Witch Hole Pond	5/28/2014	8.0	9.07	4.70	5.72	24
Witch Hole Pond	5/28/2014	8.9	9.00	4.13	5.70	25
Witch Hole Pond	5/28/2014	9.0	8.98	3.73	5.70	25
Witch Hole Pond	5/28/2014	9.1	8.92	2.60	5.69	26
Witch Hole Pond	6/18/2014	0.1	20.93	8.93	6.60	25
Witch Hole Pond	6/18/2014	0.5	20.91	8.93	6.58	25
Witch Hole Pond	6/18/2014	1.0	20.89	8.91	6.57	25
Witch Hole Pond	6/18/2014	1.0	20.89	8.90	6.57	25
Witch Hole Pond	6/18/2014	2.0	20.16	8.84	6.45	25
Witch Hole Pond	6/18/2014	2.0	20.22	8.89	6.48	25

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Witch Hole Pond	6/18/2014	3.0	17.67	8.50	6.33	25
Witch Hole Pond	6/18/2014	4.0	15.77	7.37	6.30	25
Witch Hole Pond	6/18/2014	5.0	13.07	5.82	6.20	24
Witch Hole Pond	6/18/2014	6.0	10.21	3.11	6.16	25
Witch Hole Pond	6/18/2014	8.0	9.43	1.95	6.17	25
Witch Hole Pond	6/18/2014	8.9	9.18	0.60	6.32	28
Witch Hole Pond	7/23/2014	0.1	24.40	8.18	6.45	25
Witch Hole Pond	7/23/2014	0.5	24.44	8.16	6.45	25
Witch Hole Pond	7/23/2014	1.0	24.40	8.16	6.45	23
Witch Hole Pond	7/23/2014	2.0	23.43	8.29	6.38	25
Witch Hole Pond	7/23/2014	3.0	21.84	5.54	5.85	25
Witch Hole Pond	7/23/2014	4.0	18.70	2.97	5.67	26
Witch Hole Pond	7/23/2014	5.0	13.83	1.22	5.55	26
Witch Hole Pond	7/23/2014	6.0	11.48	0.28	5.51	24
Witch Hole Pond	7/23/2014	7.0	10.07	0.10	5.67	29
Witch Hole Pond	7/23/2014	8.0	9.74	0.08	5.73	30
Witch Hole Pond	7/23/2014	9.0	9.54	0.07	5.85	33
Witch Hole Pond	7/23/2014	10.0	9.41	0.06	6.01	36
Witch Hole Pond	7/23/2014	10.1	9.36	0.05	6.09	38
Witch Hole Pond	8/25/2014	0.1	23.52	8.47	6.54	26
Witch Hole Pond	8/25/2014	0.5	22.37	8.48	6.38	25
Witch Hole Pond	8/25/2014	1.0	22.13	8.47	6.36	25
Witch Hole Pond	8/25/2014	2.0	21.49	8.11	6.21	25
Witch Hole Pond	8/25/2014	3.0	20.65	6.94	6.00	26
Witch Hole Pond	8/25/2014	4.0	19.37	2.17	5.61	26
Witch Hole Pond	8/25/2014	5.0	15.14	0.49	5.65	29
Witch Hole Pond	8/25/2014	6.0	11.62	0.15	5.53	33
Witch Hole Pond	8/25/2014	7.0	10.38	0.13	5.67	35

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A2 (continued). YSI sonde in-situ lake and pond water quality measurements collected at ACAD. Duplicate values are quality control check measurements collected on the upcast.

Site	Date	Depth (m)	Temp (C)	DO (mg/L)	pH	Specific Conductance (µS/cm)
Witch Hole Pond	8/25/2014	8.0	9.91	0.11	5.85	37
Witch Hole Pond	8/25/2014	8.5	9.78	0.09	5.97	45
Witch Hole Pond	9/16/2014	0.1	17.11	8.15	6.24	25
Witch Hole Pond	9/16/2014	0.5	17.11	8.15	6.20	25
Witch Hole Pond	9/16/2014	1.0	17.11	8.15	6.20	25
Witch Hole Pond	9/16/2014	2.0	17.10	8.14	6.19	25
Witch Hole Pond	9/16/2014	3.0	17.07	8.08	6.21	25
Witch Hole Pond	9/16/2014	4.0	16.99	8.04	6.16	25
Witch Hole Pond	9/16/2014	5.0	16.91	7.94	6.10	25
Witch Hole Pond	9/16/2014	6.0	12.45	1.43	5.85	34
Witch Hole Pond	9/16/2014	7.0	10.66	0.30	5.80	38
Witch Hole Pond	9/16/2014	8.0	10.06	0.14	5.78	40
Witch Hole Pond	9/16/2014	9.0	9.76	0.11	5.63	42
Witch Hole Pond	9/16/2014	9.5	9.66	0.08	5.81	43
Witch Hole Pond	10/27/2014	0.1	10.29	10.10	5.85	26
Witch Hole Pond	10/27/2014	0.5	10.34	9.63	5.85	26
Witch Hole Pond	10/27/2014	1.0	10.34	9.51	5.77	26
Witch Hole Pond	10/27/2014	2.0	10.34	9.47	5.81	26
Witch Hole Pond	10/27/2014	3.0	10.33	9.44	5.80	26
Witch Hole Pond	10/27/2014	4.0	10.34	9.42	5.85	26
Witch Hole Pond	10/27/2014	5.0	10.33	9.39	5.81	26
Witch Hole Pond	10/27/2014	6.0	10.31	9.41	5.84	26
Witch Hole Pond	10/27/2014	8.0	10.19	9.43	5.85	26
Witch Hole Pond	10/27/2014	8.4	10.21	6.86	5.69	29

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A3. Laboratory nutrient chemistry data for ACAD. “<MRL” indicates the result was below the method reporting limit (0.1 for TN, 1.0 for NO₃, 0.001 for NO₂, 0.0025 for NH₃, 1.0 for Chl a and 1.0 for SO₄). *Missing values indicate data are unavailable.*

Site Type	Site	Date	ANC (µeq/L)	Apparent Color (PCU)	DOC (mg/L)	TP (µg/L)	TN (mg/L)	NO ₃ (µeq/L)	NO ₃ -N [calc.] (mg/L)	NO ₂ (mg/L)	NH ₃ (mg/L)	Chl a (µg/L)	Cl (µeq/L)	SO ₄ (µeq/L)
Lake	Bubble Pond	6/26/2014	78.08	19	2.66	3.9	0.473	3.8	0.054	<MRL	<MRL	3.1	110	43
Lake	Bubble Pond	8/26/2014	85.87	15	2.60	3.9	0.169	<MRL	<MRL	<MRL	<MRL	2.6	105	44
Lake	Eagle Lake	6/26/2014	63.58	14	2.24	2.5	0.084	4.1	0.058	<MRL	<MRL	1.6	145	41
Lake	Eagle Lake	8/18/2014	66.35	11	1.73	3.6	0.112	<MRL	<MRL	<MRL	0.012	1.1	130	38
Lake	Echo Lake	6/23/2014	98.82	20	3.20	5	0.082	<MRL	<MRL	<MRL	<MRL	1	407	58
Lake	Echo Lake	8/20/2014	106.35	19	2.80	4.1	0.203	<MRL	<MRL	<MRL	0.015	2.5	388	57
Lake	Jordan Pond	6/30/2014	75.01	10	2.30	2.7	0.112	3.8	0.054	<MRL	<MRL	0.9	98	40
Lake	Jordan Pond	8/27/2014	80.32	9	2.35	1.4	0.123	<MRL	<MRL	<MRL	0.012	<MRL	120	50
Lake	Lake Wood	6/16/2014	65.25	21	2.29	5.9	0.142	<MRL	<MRL	<MRL	<MRL	1.6	82	36
Lake	Lake Wood	8/25/2014	77.11	29	2.67	10.2	0.238	1.3	0.018	<MRL	0.020	2.5	90	6.9
Lake	Long Pond (MDI)	6/23/2014	70.64	19	3.27	3.6	0.222	<MRL	<MRL	<MRL	<MRL	1.3	220	56
Lake	Long Pond (MDI)	8/20/2014	72.41	17	3.62	3.7	0.120	<MRL	<MRL	<MRL	0.025	2.6	212	56
Lake	Round Pond	6/19/2014	38.77	35	4.25	8.2	0.171	<MRL	<MRL	<MRL	<MRL	1.7	197	46
Lake	Round Pond	8/26/2014	54.91	47	5.93	10.9	0.196	<MRL	<MRL	<MRL	0.010	8.4	217	35
Lake	Seal Cove Pond	6/24/2014	73.59	32	4.55	5.9	0.696	<MRL	<MRL	<MRL	<MRL	2.6	230	52
Lake	Seal Cove Pond	8/21/2014	84.72	35	4.89	6.2	0.208	<MRL	<MRL	<MRL	<MRL	5.6	211	46
Lake	Upper Breakneck	6/18/2014	127.10	33	4.73	6.8	0.493	<MRL	<MRL	<MRL	0.005	1.2	329	21
Lake	Upper Breakneck	8/25/2014	158.19	36	5.82	7.8	0.327	<MRL	<MRL	<MRL	0.008	2.1	260	6.6
Lake	Upper Hadlock	6/16/2014	53.52	25	3.78	4.6	0.106	<MRL	<MRL	<MRL	<MRL	1.2	279	47

Appendix A. Acadia National (ACAD) Water Monitoring Data, 2014 (continued).

Table A3 (continued). Laboratory nutrient chemistry data for ACAD. “<MRL” indicates the result was below the method reporting limit (0.1 for TN, 1.0 for NO₃, 0.001 for NO₂, 0.0025 for NH₃, 1.0 for Chl a and 1.0 for SO₄). *Missing values indicate data are unavailable.*

Site Type	Site	Date	ANC (µeq/L)	Apparent Color (PCU)	DOC (mg/L)	TP (µg/L)	TN (mg/L)	NO ₃ (µeq/L)	NO ₃ -N [calc.] (mg/L)	NO ₂ (mg/L)	NH ₃ (mg/L)	Chl a (µg/L)	Cl (µeq/L)	SO ₄ (µeq/L)
Lake	Upper Hadlock	8/18/2014	74.22	32	6.25	4.8	0.219	<MRL	<MRL	<MRL	0.009	1.8	140	29
Lake	Witch Hole Pond	6/18/2014	55.92	43	3.99	8.2	0.419	<MRL	<MRL	<MRL	0.003	2.4	104	24
Lake	Witch Hole Pond	8/25/2014	76.41	42	3.97	10.1	0.341	<MRL	<MRL	<MRL	0.023	3.8	90	<MRL
Stream	Aunt Betty Pond Inlet	5/13/2014	91.60	43	4.33	6.8	0.202	<MRL	<MRL	<MRL	<MRL		91	31
Stream	Aunt Betty Pond Inlet	8/14/2014	191.69	64	5.48	11.6	0.278	<MRL	<MRL	<MRL	0.012		97	1.5
Stream	Breakneck Brook	5/12/2014	112.00	24	2.31	5.1	0.138	1.3	0.018	<MRL	<MRL		164	37
Stream	Breakneck Brook	8/5/2014	213.35	18	3.04	3.7	0.313	5.1	0.072	<MRL	0.018		167	17
Stream	Cadillac Stream	5/15/2014	47.50	3	1.25	<MRL	<MRL	<MRL	<MRL	<MRL	<MRL		97	48
Stream	Cadillac Stream	8/6/2014	109.67	4	0.90	2.1	0.059	<MRL	<MRL	<MRL	0.014		85	32
Stream	Hadlock Brook	5/15/2014	42.00	7	1.82	1.4	0.111	4.3	0.061	<MRL	<MRL		121	63
Stream	Hadlock Brook	8/14/2014	49.39	16	3.54	2.1	0.190	4.8	0.068	<MRL	0.016		106	43
Stream	Heath Brook	5/12/2014	35.10	95	7.84	5	0.285	<MRL	<MRL	<MRL	<MRL		144	49
Stream	Heath Brook	8/7/2014	76.65	169	14.03	14.6	0.591	1.4	0.02	<MRL	0.037		164	12
Stream	Hunters Brook	5/8/2014	83.10	20	1.61	2.9	<MRL	<MRL	<MRL	<MRL	<MRL		160	71
Stream	Hunters Brook	8/4/2014	157.80	13	2.31	2.4	0.039	1.6	0.023	<MRL	0.008		164	69
Stream	Kebo Brook	5/12/2014	84.90	2	0.73	<MRL	<MRL	<MRL	<MRL	<MRL	<MRL		91	47
Stream	Kebo Brook	8/6/2014	146.69	22	1.75	9.9	0.151	3.3	0.047	<MRL	0.026		81	38
Stream	Marshall Brook	5/19/2014	324.00	74	6.41	6.6	0.298	6.3	0.089	<MRL	<MRL		506	91

Appendix A. Acadia National (ACAD) Water Monitoring Data, 2014 (continued).

Table A3 (continued). Laboratory nutrient chemistry data for ACAD. “<MRL” indicates the result was below the method reporting limit (0.1 for TN, 1.0 for NO₃, 0.001 for NO₂, 0.0025 for NH₃, 1.0 for Chl a and 1.0 for SO₄). *Missing values indicate data are unavailable.*

Site Type	Site	Date	ANC (µeq/L)	Apparent Color (PCU)	DOC (mg/L)	TP (µg/L)	TN (mg/L)	NO ₃ (µeq/L)	NO ₃ -N [calc.] (mg/L)	NO ₂ (mg/L)	NH ₃ (mg/L)	Chl a (µg/L)	Cl (µeq/L)	SO ₄ (µeq/L)
Stream	Marshall Brook	8/7/2014	392.60	90	6.54	11.6	0.294	3.9	0.055	<MRL	0.035		635	77
Stream	Otter Creek	5/7/2014	61.00	11	1.35	1.9	<MRL	<MRL	<MRL	<MRL	<MRL		116	51
Stream	Otter Creek	8/4/2014	141.29	29	2.09	3.4	0.100	1.7	0.024	<MRL	0.025		120	33
Stream	Sargent Brook	5/13/2014	18.20	9	2.39	1.3	<MRL	1.3	0.018	<MRL	<MRL		106	58
Stream	Sargent Brook	8/14/2014	25.51	30	6.61	4.5	0.155	1.1	0.016	<MRL	0.012		116	40
Stream	Stanley Brook	5/8/2014	138.00	33	2.25	3.6	0.267	13	0.183	<MRL	<MRL		410	83
Stream	Stanley Brook	8/4/2014	220.15	19	1.67	2.4	0.286	18	0.254	<MRL	0.030		373	81

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A4. Stream stage and discharge data for ACAD. *Missing values indicate data are unavailable.*

Site	Date	Datum name	Time	Distance from datum (ft)	Total CS area (sqft)	Average velocity (f/s)	Discharge (cfs)
Aunt Betty Pond Inlet	5/13/2014	Bridge	14:00	-2.47	6.29	0.12	0.74
Aunt Betty Pond Inlet	5/13/2014	Bridge	15:03	-2.46	6.29	0.12	0.74
Aunt Betty Pond Inlet	6/5/2014	Bridge	11:29	-2.59	5.68	0.05	0.27
Aunt Betty Pond Inlet	6/5/2014	Bridge	12:15	-2.59	5.68	0.05	0.27
Aunt Betty Pond Inlet	7/14/2014	Bridge	9:36	-2.60	5.61	0.04	0.24
Aunt Betty Pond Inlet	7/14/2014	Bridge	10:30	-2.60	5.61	0.04	0.24
Aunt Betty Pond Inlet	8/14/2014	Bridge	9:36	-2.51	8.08	0.17	1.35
Aunt Betty Pond Inlet	8/14/2014	Bridge	10:23	-2.50	8.08	0.17	1.35
Aunt Betty Pond Inlet	9/10/2014	Bridge	9:10	-2.63	6.57	0.00	0.00
Aunt Betty Pond Inlet	10/8/2014	Bridge	13:34	-2.57	5.58	0.00	0.00
Aunt Betty Pond Inlet	10/8/2014	Bridge	14:22	-2.57	5.58	0.00	0.00
Breakneck Brook	5/12/2014	SD1	15:05	-0.29	3.25	0.46	1.48
Breakneck Brook	5/12/2014	SD1	15:56	-0.29	3.25	0.46	1.48
Breakneck Brook	6/3/2014	SD1	14:46	-0.40	2.60	0.21	0.55
Breakneck Brook	6/3/2014	SD1	15:36	-0.40	2.60	0.21	0.55
Breakneck Brook	7/10/2014	SD1	14:46	-0.30	3.41	0.45	1.52
Breakneck Brook	7/10/2014	SD1	16:41	-0.30	3.41	0.45	1.52
Breakneck Brook	8/5/2014	SD1	14:33	-0.52	2.12	0.13	0.28
Breakneck Brook	8/5/2014	SD1	15:20	-0.52	2.12	0.13	0.28
Breakneck Brook	9/8/2014	SD1	12:07	-0.62	1.37	0.02	0.04
Breakneck Brook	9/8/2014	SD1	13:13	-0.62	1.37	0.02	0.04
Breakneck Brook	10/7/2014	SD1	14:44	-0.63	0.99	0.16	0.16
Breakneck Brook	10/7/2014	SD1	15:20	-0.63	0.99	0.16	0.16
Cadillac Stream	5/15/2014	Global logger	13:41	0.57			0.06
Cadillac Stream	5/15/2014	Global logger	14:04	0.57			0.06
Cadillac Stream	5/15/2014	RP2	13:26	0.25			0.06
Cadillac Stream	5/15/2014	RP2	14:03	0.25			0.06
Cadillac Stream	5/15/2014	RP3	13:26	0.33			0.06

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A4 (continued). Stream stage and discharge data for ACAD. Missing values indicate data are unavailable.

Site	Date	Datum name	Time	Distance from datum (ft)	Total CS area (sqft)	Average velocity (f/s)	Discharge (cfs)
Cadillac Stream	5/15/2014	RP3	14:03	0.33			0.06
Cadillac Stream	6/13/2014	Global logger	11:21	0.57			0.01
Cadillac Stream	6/13/2014	RP2	11:17	0.23			0.01
Cadillac Stream	6/13/2014	RP3	11:17	0.33			0.01
Cadillac Stream	7/9/2014	Global logger	10:43	0.56			0.03
Cadillac Stream	7/9/2014	RP2	10:50	0.25			0.03
Cadillac Stream	7/9/2014	RP2	11:40	0.25			0.03
Cadillac Stream	7/9/2014	RP3	10:50	0.33			0.03
Cadillac Stream	8/6/2014	Global logger	10:02	0.52			0.00
Cadillac Stream	8/6/2014	RP2	9:54	0.22			0.00
Cadillac Stream	8/6/2014	RP2	10:28	0.22			0.00
Cadillac Stream	8/6/2014	RP3	9:54	0.31			0.00
Cadillac Stream	8/6/2014	RP3	10:29	0.31			0.00
Cadillac Stream	9/11/2014	Global logger	9:50	0.52			0.00
Cadillac Stream	9/11/2014	RP2	9:46	0.21			0.00
Cadillac Stream	9/11/2014	RP3	9:46	0.30			0.00
Cadillac Stream	10/15/2014	Global logger	14:22	0.54			0.00
Cadillac Stream	10/15/2014	RP2	14:32	0.23			0.00
Cadillac Stream	10/15/2014	RP3	14:32	0.31			0.00
Hadlock Brook	5/15/2014	Global logger	10:45	0.63			0.06
Hadlock Brook	5/15/2014	RM2	9:55	0.15			0.06
Hadlock Brook	5/15/2014	RM2	10:45	0.15			0.06
Hadlock Brook	5/15/2014	RM3	9:55	0.52			0.06
Hadlock Brook	5/15/2014	RM3	10:45	0.52			0.06
Hadlock Brook	5/15/2014	RP1	9:55	-1.22			0.06
Hadlock Brook	5/15/2014	RP1	10:22	-1.22			0.06
Hadlock Brook	6/12/2014	Global logger	16:10	0.60	1.29	0.04	0.05
Hadlock Brook	6/12/2014	RM2	15:54	0.18	1.29	0.04	0.05

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A4 (continued). Stream stage and discharge data for ACAD. Missing values indicate data are unavailable.

Site	Date	Datum name	Time	Distance from datum (ft)	Total CS area (sqft)	Average velocity (f/s)	Discharge (cfs)
Hadlock Brook	6/12/2014	RM2	16:42	0.18	1.29	0.04	0.05
Hadlock Brook	6/12/2014	RM3	15:55	-0.51	1.29	0.04	0.05
Hadlock Brook	6/12/2014	RM3	16:41	-0.50	1.29	0.04	0.05
Hadlock Brook	6/12/2014	RP1	15:53	-1.23	1.29	0.04	0.05
Hadlock Brook	6/12/2014	RP1	16:41	-1.23	1.29	0.04	0.05
Hadlock Brook	7/17/2014	Global logger	13:15	0.87			2.30
Hadlock Brook	7/17/2014	RM2	13:09	0.44			2.30
Hadlock Brook	7/17/2014	RM2	13:34	0.44			2.30
Hadlock Brook	7/17/2014	RM3	13:10	0.83			2.30
Hadlock Brook	7/17/2014	RM3	13:10	0.83			2.30
Hadlock Brook	7/17/2014	RP1	13:09	-0.94			2.30
Hadlock Brook	7/17/2014	RP1	13:34	-0.94			2.30
Hadlock Brook	8/14/2014	Global logger	13:04	0.67			0.38
Hadlock Brook	8/14/2014	RM2	12:57	0.25			0.38
Hadlock Brook	8/14/2014	RM2	13:24	0.25			0.38
Hadlock Brook	8/14/2014	RM3	12:57	0.63			0.38
Hadlock Brook	8/14/2014	RM3	13:24	0.63			0.38
Hadlock Brook	8/14/2014	RP1	12:57	-1.12			0.38
Hadlock Brook	8/14/2014	RP1	13:24	-1.12			0.38
Hadlock Brook	9/10/2014	Global logger	13:37	0.51			0.01
Hadlock Brook	9/10/2014	RM2	13:34	0.09			0.01
Hadlock Brook	9/10/2014	RM3	13:34	0.46			0.01
Hadlock Brook	9/10/2014	RP1	13:34	-1.28			0.01
Hadlock Brook	10/16/2014	RM2	15:02	0.11			0.03
Hadlock Brook	10/16/2014	RM3	15:01	0.49			0.03
Hadlock Brook	10/16/2014	RP1	15:02	-1.26			0.03
Heath Brook	5/12/2014	SD1	10:40	-2.67	2.17	0.44	0.96
Heath Brook	5/12/2014	SD1	11:19	-2.68	2.17	0.44	0.96

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A4 (continued). Stream stage and discharge data for ACAD. Missing values indicate data are unavailable.

Site	Date	Datum name	Time	Distance from datum (ft)	Total CS area (sqft)	Average velocity (f/s)	Discharge (cfs)
Heath Brook	6/9/2014	SD1	9:57	-2.77	1.89	0.22	0.42
Heath Brook	6/9/2014	SD1	10:52	-2.77	1.89	0.22	0.42
Heath Brook	7/14/2014	SD1	13:35	-2.70	2.17	0.27	0.59
Heath Brook	7/14/2014	SD1	14:43	-2.70	2.17	0.27	0.59
Heath Brook	8/7/2014	SD1	13:50	-2.73	2.05	0.23	0.47
Heath Brook	8/7/2014	SD1	14:41	-2.73	2.05	0.23	0.47
Heath Brook	9/8/2014	SD1	10:24	-2.74	1.77	0.08	0.15
Heath Brook	10/9/2014	SD1	13:18	-2.68	2.00	0.11	0.23
Heath Brook	10/9/2014	SD1	13:55	-2.68	2.00	0.11	0.23
Hunters Brook	5/8/2014	RM1	11:46	-0.59	4.31	0.60	2.56
Hunters Brook	5/8/2014	RM1	13:05	-0.59	4.31	0.60	2.56
Hunters Brook	6/2/2014	RM1	14:10	-0.72	2.93	0.28	0.83
Hunters Brook	6/2/2014	RM1	15:04	-0.72	2.93	0.28	0.83
Hunters Brook	6/2/2014	SD2	14:10	-0.32	2.93	0.28	0.83
Hunters Brook	6/2/2014	SD2	15:04	-0.32	2.93	0.28	0.83
Hunters Brook	7/7/2014	RM1	10:45	-0.46	5.59	0.90	5.00
Hunters Brook	7/7/2014	RM1	11:22	-0.47	5.59	0.90	5.00
Hunters Brook	7/7/2014	SD2	10:46	-0.09	5.59	0.90	5.00
Hunters Brook	7/7/2014	SD2	11:23	-0.09	5.59	0.90	5.00
Hunters Brook	8/4/2014	RM1	11:21	-0.72	3.06	0.28	0.86
Hunters Brook	8/4/2014	RM1	12:51	-0.72	3.06	0.28	0.86
Hunters Brook	8/4/2014	SD2	11:21	-0.31	3.06	0.28	0.86
Hunters Brook	8/4/2014	SD2	12:51	-0.31	3.06	0.28	0.86
Hunters Brook	9/3/2014	RM1	11:43	-0.79	2.63	0.15	0.35
Hunters Brook	9/3/2014	RM1	12:30	-0.79	2.63	0.15	0.35
Hunters Brook	9/3/2014	SD3	11:43	-0.37	2.63	0.15	0.35
Hunters Brook	9/3/2014	SD3	12:30	-0.37	2.63	0.15	0.35
Hunters Brook	10/6/2014	RM1	10:52	-0.78	2.78	0.11	0.28

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A4 (continued). Stream stage and discharge data for ACAD. Missing values indicate data are unavailable.

Site	Date	Datum name	Time	Distance from datum (ft)	Total CS area (sqft)	Average velocity (f/s)	Discharge (cfs)
Hunters Brook	10/6/2014	RM1	11:57	-0.78	2.78	0.11	0.28
Hunters Brook	10/6/2014	SD3	10:52	-0.36	2.78	0.11	0.28
Hunters Brook	10/6/2014	SD3	11:57	-0.36	2.78	0.11	0.28
Kebo Brook	5/12/2014	SD1	13:10	-2.33	3.22	0.28	0.91
Kebo Brook	5/12/2014	SD1	14:15	-2.33	3.22	0.28	0.91
Kebo Brook	6/4/2014	SD1	10:25	-2.43	2.97	0.15	0.44
Kebo Brook	6/4/2014	SD1	11:53	-2.43	2.97	0.15	0.44
Kebo Brook	7/17/2014	SD1	9:25	-2.07	19.05	0.78	14.82
Kebo Brook	7/17/2014	SD1	10:12	-2.07	19.05	0.78	14.82
Kebo Brook	8/6/2014	SD1	14:12	-2.53	3.50	0.05	0.10
Kebo Brook	8/6/2014	SD1	15:02	-2.51	3.50	0.05	0.10
Kebo Brook	9/9/2014	SD1	13:52	-2.63	1.88	0.02	0.05
Kebo Brook	10/6/2014	SD1	14:07	-2.59	0.97	0.01	0.03
Kebo Brook	10/6/2014	SD1	15:04	-2.58	0.97	0.01	0.03
Marshall Brook	5/19/2014	SD1	10:08	-1.09	5.88	0.55	3.25
Marshall Brook	5/19/2014	SD1	11:14	-1.09	5.88	0.55	3.25
Marshall Brook	6/9/2014	SD1	11:22	-1.21	5.36	0.29	1.53
Marshall Brook	6/9/2014	SD1	12:11	-1.21	5.36	0.29	1.53
Marshall Brook	7/15/2014	SD1	9:51	-1.19			
Marshall Brook	7/15/2014	SD1	10:43	-1.17			
Marshall Brook	8/7/2014	SD1	10:50	-1.28	5.10	0.28	1.43
Marshall Brook	8/7/2014	SD1	12:24	-1.28	5.10	0.28	1.43
Marshall Brook	9/4/2014	SD1	11:03	-1.45	4.04	0.12	0.39
Marshall Brook	10/9/2014	SD1	11:22	-1.33	4.67	0.14	0.70
Marshall Brook	10/9/2014	SD1	12:30	-1.33	4.67	0.14	0.70
Otter Creek	5/7/2014	USGS gage	15:25	1.89			2.60
Otter Creek	6/4/2014	USGS gage	14:25	1.67	3.04	0.25	0.75
Otter Creek	8/4/2014	USGS gage	16:10	1.63			0.54

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A4 (continued). Stream stage and discharge data for ACAD. Missing values indicate data are unavailable.

Site	Date	Datum name	Time	Distance from datum (ft)	Total CS area (sqft)	Average velocity (f/s)	Discharge (cfs)
Otter Creek	9/8/2014	USGS gage	14:25	1.54			0.19
Sargent Brook	5/13/2014	SD1	16:04	-0.25	1.77	0.07	0.13
Sargent Brook	5/13/2014	SD1	16:50	-0.25	1.77	0.07	0.13
Sargent Brook	6/5/2014	SD1	12:36	-0.27	1.47	0.04	0.05
Sargent Brook	6/5/2014	SD1	13:25	-0.27	1.47	0.04	0.05
Sargent Brook	7/14/2014	SD1	11:40	-0.26			
Sargent Brook	7/14/2014	SD1	12:35	-0.26			
Sargent Brook	8/14/2014	SD1	11:00	-0.13	2.23	0.21	0.48
Sargent Brook	8/14/2014	SD1	11:49	-0.13	2.23	0.21	0.48
Sargent Brook	9/10/2014	SD1	10:50	-0.34	1.50	0.00	0.00
Sargent Brook	10/8/2014	SD1	14:36	-0.20	1.90	0.08	0.15
Sargent Brook	10/8/2014	SD1	17:15	-0.20	1.90	0.08	0.15
Stanley Brook	5/8/2014	SD2	13:30	-0.92	3.71	0.68	2.50
Stanley Brook	5/8/2014	SD2	14:27	-0.92	3.71	0.68	2.50
Stanley Brook	6/2/2014	SD2	15:38	-1.02	2.83	0.41	1.17
Stanley Brook	6/2/2014	SD2	16:23	-1.02	2.83	0.41	1.17
Stanley Brook	7/7/2014	SD2	12:52	-0.76	5.35	0.79	4.23
Stanley Brook	7/7/2014	SD2	13:48	-0.76	5.35	0.79	4.23
Stanley Brook	8/4/2014	SD2	14:06	-1.08	2.97	0.43	1.26
Stanley Brook	8/4/2014	SD2	14:48	-1.08	2.97	0.43	1.26
Stanley Brook	9/5/2014	SD2	12:55	-1.12	2.09	0.22	0.48
Stanley Brook	9/5/2014	SD2	13:44	-1.13	2.09	0.22	0.48
Stanley Brook	10/6/2014	SD2	12:45	-1.14	13.74	0.17	0.57
Stanley Brook	10/6/2014	SD2	13:26	-1.14	13.74	0.17	0.57

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A5. Lake water transparency data for ACAD. “B” after transparency value indicates disk pattern still visible at pond bottom.

Site	Date	Secchi Depth (m)	(B=disk hit bottom)
Bubble Pond	5/30/2014	11.16	
Bubble Pond	6/26/2014	7.10	
Bubble Pond	7/22/2014	7.05	
Bubble Pond	8/26/2014	8.13	
Bubble Pond	9/15/2014	7.94	
Bubble Pond	10/29/2014	8.20	
Eagle Lake	5/29/2014	12.00	
Eagle Lake	6/26/2014	9.77	
Eagle Lake	7/22/2014	11.10	
Eagle Lake	8/18/2014	10.80	
Eagle Lake	9/17/2014	10.95	
Eagle Lake	10/20/2014	10.00	
Echo Lake	5/22/2014	8.25	
Echo Lake	6/23/2014	8.10	
Echo Lake	7/24/2014	7.20	
Echo Lake	8/20/2014	9.05	
Echo Lake	9/18/2014	8.72	
Echo Lake	10/21/2014	7.75	
Jordan Pond	5/29/2014	14.15	
Jordan Pond	6/30/2014	15.40	
Jordan Pond	7/21/2014	13.60	
Jordan Pond	9/15/2014	13.82	
Jordan Pond	10/29/2014	13.10	
Lake Wood	5/20/2014	3.90	B
Long Pond (MDI)	5/22/2014	10.30	
Long Pond (MDI)	6/23/2014	10.14	
Long Pond (MDI)	7/28/2014	7.70	
Long Pond (MDI)	8/20/2014	9.41	
Long Pond (MDI)	9/18/2014	8.65	

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2013 (continued).

Table A5 (continued). Lake water transparency data for ACAD. “B” after transparency value indicates disk pattern still visible at pond bottom.

Site	Date	Secchi Depth (m)	(B=disk hit bottom)
Long Pond (MDI)	10/21/2014	9.90	
Round Pond	5/23/2014	4.82	B
Seal Cove Pond	5/22/2014	7.00	
Seal Cove Pond	6/24/2014	5.57	
Seal Cove Pond	7/28/2014	5.77	
Seal Cove Pond	8/21/2014	5.45	
Seal Cove Pond	9/22/2014	6.30	
Seal Cove Pond	10/27/2014	6.80	
Upper Hadlock	5/20/2014	7.88	
Upper Hadlock	6/16/2014	7.70	
Upper Hadlock	7/31/2014	5.20	
Upper Hadlock	8/18/2014	6.07	
Upper Hadlock	9/17/2014	7.50	
Upper Hadlock	10/20/2014	6.45	
Witch Hole Pond	5/28/2014	4.91	
Witch Hole Pond	6/18/2014	4.75	
Witch Hole Pond	7/23/2014	4.10	
Witch Hole Pond	8/25/2014	4.18	
Witch Hole Pond	9/16/2014	4.15	
Witch Hole Pond	10/27/2014	4.30	

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2014 (continued).

Table A6. Light penetration profiles for ACAD.

Site	NETN Code	Date	Depth (m)	Deck cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	PAR cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	Proportion of penetration (PAR/Deck)
Jordan Pond	ACJORD	5/29/2014	0.01	1605.20	1738.80	1.08
Jordan Pond	ACJORD	5/29/2014	0.10	1577.10	1564.90	0.99
Jordan Pond	ACJORD	5/29/2014	0.50	1582.30	1650.50	1.04
Jordan Pond	ACJORD	5/29/2014	1.00	1585.80	1339.00	0.84
Jordan Pond	ACJORD	5/29/2014	2.00	1583.20	1019.00	0.64
Jordan Pond	ACJORD	5/29/2014	3.00	1573.20	811.01	0.52
Jordan Pond	ACJORD	5/29/2014	4.00	1580.90	635.05	0.40
Jordan Pond	ACJORD	5/29/2014	5.00	1571.30	522.49	0.33
Jordan Pond	ACJORD	6/30/2014	0.10	1946.10	2112.70	1.09
Jordan Pond	ACJORD	6/30/2014	0.50	1942.40	1770.40	0.91
Jordan Pond	ACJORD	6/30/2014	1.00	1937.80	1418.00	0.73
Jordan Pond	ACJORD	6/30/2014	2.00	1941.50	1146.90	0.59
Jordan Pond	ACJORD	6/30/2014	3.00	1945.20	846.43	0.44
Jordan Pond	ACJORD	6/30/2014	4.00	1933.60	781.45	0.40
Jordan Pond	ACJORD	6/30/2014	5.00	1945.50	569.10	0.29
Jordan Pond	ACJORD	6/30/2014	6.00	1934.80	456.44	0.24
Jordan Pond	ACJORD	6/30/2014	7.00	1934.20	404.18	0.21
Jordan Pond	ACJORD	6/30/2014	8.00	1720.40	321.77	0.26
Jordan Pond	ACJORD	6/30/2014	9.00	1940.00	265.92	0.14
Jordan Pond	ACJORD	6/30/2014	10.00	1926.30	188.08	0.10
Jordan Pond	ACJORD	6/30/2014	11.00	1926.10	159.32	0.08
Jordan Pond	ACJORD	6/30/2014	12.00	1919.50	127.47	0.07
Jordan Pond	ACJORD	6/30/2014	13.00	1907.80	106.21	0.06
Jordan Pond	ACJORD	6/30/2014	14.00	1910.10	88.00	0.05
Jordan Pond	ACJORD	6/30/2014	15.00	1905.40	72.88	0.04
Jordan Pond	ACJORD	6/30/2014	16.00	1908.20	55.76	0.03
Jordan Pond	ACJORD	6/30/2014	17.00	1888.40	43.77	0.02
Jordan Pond	ACJORD	6/30/2014	18.00	1904.50	37.31	0.02
Jordan Pond	ACJORD	6/30/2014	19.00	1904.70	29.34	0.02

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2012 (continued).

Table A6 (continued). Light penetration profiles for ACAD.

Site	NETN Code	Date	Depth (m)	Deck cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	PAR cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	Proportion of penetration (PAR/Deck)
Jordan Pond	ACJORD	6/30/2014	20.00	1918.30	24.56	0.01
Jordan Pond	ACJORD	6/30/2014	21.00	1910.90	19.27	0.01
Jordan Pond	ACJORD	6/30/2014	22.00	1908.40	16.60	0.01
Jordan Pond	ACJORD	6/30/2014	23.00	1895.20	13.00	0.01
Jordan Pond	ACJORD	7/21/2014	0.10	1862.30	2021.00	1.09
Jordan Pond	ACJORD	7/21/2014	0.50	1862.90	1700.20	0.91
Jordan Pond	ACJORD	7/21/2014	1.00	1860.40	1540.60	0.83
Jordan Pond	ACJORD	7/21/2014	2.00	1862.50	1119.60	0.60
Jordan Pond	ACJORD	7/21/2014	3.00	1861.30	912.75	0.49
Jordan Pond	ACJORD	7/21/2014	4.00	1863.20	634.93	0.34
Jordan Pond	ACJORD	7/21/2014	5.00	1848.10	417.90	0.23
Jordan Pond	ACJORD	7/21/2014	6.00	1833.20	360.97	0.20
Jordan Pond	ACJORD	7/21/2014	7.00	1826.50	285.93	0.16
Jordan Pond	ACJORD	7/21/2014	8.00	1819.80	212.77	0.12
Jordan Pond	ACJORD	7/21/2014	9.00	1816.80	159.30	0.09
Jordan Pond	ACJORD	7/21/2014	10.00	1821.40	122.10	0.07
Jordan Pond	ACJORD	7/21/2014	11.00	1813.80	97.70	0.05
Jordan Pond	ACJORD	7/21/2014	12.00	1812.00	77.61	0.04
Jordan Pond	ACJORD	7/21/2014	13.00	1802.40	60.30	0.03
Jordan Pond	ACJORD	7/21/2014	14.00	1804.10	49.03	0.03
Jordan Pond	ACJORD	7/21/2014	15.00	1794.20	40.24	0.02
Jordan Pond	ACJORD	7/21/2014	16.00	1799.30	31.32	0.02
Jordan Pond	ACJORD	7/21/2014	17.00	1789.90	25.98	0.01
Jordan Pond	ACJORD	7/21/2014	18.00	1795.70	21.14	0.01
Jordan Pond	ACJORD	7/21/2014	19.00	1788.00	16.51	0.01
Jordan Pond	ACJORD	7/21/2014	20.00	1801.10	13.40	0.01
Jordan Pond	ACJORD	8/27/2014	0.10	1758.60	1734.60	1.00
Jordan Pond	ACJORD	8/27/2014	0.50	1790.30	1481.40	0.83
Jordan Pond	ACJORD	8/27/2014	1.00	1770.90	1270.60	0.72

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2012 (continued).

Table A6 (continued). Light penetration profiles for ACAD.

Site	NETN Code	Date	Depth (m)	Deck cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	PAR cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	Proportion of penetration (PAR/Deck)
Jordan Pond	ACJORD	8/27/2014	2.00	1793.00	1025.30	0.57
Jordan Pond	ACJORD	8/27/2014	3.00	1791.00	857.31	0.48
Jordan Pond	ACJORD	8/27/2014	4.00	1783.10	627.03	0.35
Jordan Pond	ACJORD	8/27/2014	5.00	1787.90	498.48	0.28
Jordan Pond	ACJORD	8/27/2014	6.00	1793.90	402.98	0.22
Jordan Pond	ACJORD	8/27/2014	7.00	1805.20	285.00	0.16
Jordan Pond	ACJORD	8/27/2014	8.00	1801.90	262.15	0.15
Jordan Pond	ACJORD	8/27/2014	9.00	1806.50	205.66	0.11
Jordan Pond	ACJORD	8/27/2014	10.00	1824.00	165.46	0.09
Jordan Pond	ACJORD	8/27/2014	11.00	1821.50	132.60	0.07
Jordan Pond	ACJORD	8/27/2014	12.00	1833.90	101.82	0.06
Jordan Pond	ACJORD	8/27/2014	13.00	1840.30	85.96	0.05
Jordan Pond	ACJORD	8/27/2014	14.00	1821.30	70.52	0.04
Jordan Pond	ACJORD	8/27/2014	15.00	1831.90	56.18	0.03
Jordan Pond	ACJORD	8/27/2014	16.00	1822.60	45.41	0.02
Jordan Pond	ACJORD	8/27/2014	17.00	1824.80	36.68	0.02
Jordan Pond	ACJORD	8/27/2014	18.00	1837.10	30.01	0.02
Jordan Pond	ACJORD	8/27/2014	19.00	1849.30	23.94	0.01
Jordan Pond	ACJORD	8/27/2014	20.00	1854.10	19.07	0.01
Jordan Pond	ACJORD	8/27/2014	21.00	1838.50	15.25	0.01
Jordan Pond	ACJORD	8/27/2014	22.00	1889.20	12.89	0.01
Jordan Pond	ACJORD	9/15/2014	0.10	1662.10	1855.50	1.12
Jordan Pond	ACJORD	9/15/2014	0.50	1736.40	1571.00	0.90
Jordan Pond	ACJORD	9/15/2014	1.00	1809.70	1467.50	0.81
Jordan Pond	ACJORD	9/15/2014	2.00	1736.70	1126.80	0.65
Jordan Pond	ACJORD	9/15/2014	3.00	1813.90	713.86	0.39
Jordan Pond	ACJORD	9/15/2014	4.00	1803.90	614.61	0.34
Jordan Pond	ACJORD	9/15/2014	5.00	1927.20	488.75	0.25
Jordan Pond	ACJORD	9/15/2014	6.00	1705.20	413.45	0.24

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2012 (continued).

Table A6 (continued). Light penetration profiles for ACAD.

Site	NETN Code	Date	Depth (m)	Deck cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	PAR cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	Proportion of penetration (PAR/Deck)
Jordan Pond	ACJORD	9/15/2014	7.00	1677.40	320.10	0.19
Jordan Pond	ACJORD	9/15/2014	8.00	1685.70	249.20	0.15
Jordan Pond	ACJORD	9/15/2014	9.00	1711.40	207.72	0.12
Jordan Pond	ACJORD	9/15/2014	10.00	1755.30	168.01	0.10
Jordan Pond	ACJORD	9/15/2014	11.00	1775.30	132.05	0.07
Jordan Pond	ACJORD	9/15/2014	12.00	1784.00	113.94	0.06
Jordan Pond	ACJORD	9/15/2014	13.00	1761.30	91.72	0.05
Jordan Pond	ACJORD	9/15/2014	14.00	643.92	26.91	0.04
Jordan Pond	ACJORD	9/15/2014	15.00	441.11	13.78	0.03
Jordan Pond	ACJORD	9/15/2014	16.00	1812.70	48.18	0.03
Jordan Pond	ACJORD	9/15/2014	17.00	1866.40	40.23	0.02
Jordan Pond	ACJORD	9/15/2014	18.00	1886.60	32.85	0.02
Jordan Pond	ACJORD	9/15/2014	19.00	1911.70	26.79	0.01
Jordan Pond	ACJORD	9/15/2014	20.00	897.91	9.81	0.01
Jordan Pond	ACJORD	9/15/2014	21.00	2019.90	17.44	0.01
Jordan Pond	ACJORD	9/15/2014	22.00	1197.60	9.42	0.01
Jordan Pond	ACJORD	10/29/2014	0.10	161.84	160.25	0.99
Jordan Pond	ACJORD	10/29/2014	1.00	148.39	99.52	0.67
Jordan Pond	ACJORD	10/29/2014	2.00	132.88	62.73	0.47
Jordan Pond	ACJORD	10/29/2014	3.00	106.71	37.07	0.35
Jordan Pond	ACJORD	10/29/2014	4.00	101.94	28.30	0.28
Jordan Pond	ACJORD	10/29/2014	5.00	90.91	19.88	0.22
Jordan Pond	ACJORD	10/29/2014	6.00	80.99	13.34	0.16
Jordan Pond	ACJORD	10/29/2014	7.00	94.33	12.31	0.13
Jordan Pond	ACJORD	10/29/2014	8.00	119.63	12.17	0.10
Jordan Pond	ACJORD	10/29/2014	9.00	122.81	9.73	0.08
Jordan Pond	ACJORD	10/29/2014	10.00	110.97	6.77	0.06
Jordan Pond	ACJORD	10/29/2014	11.00	116.12	5.56	0.05
Jordan Pond	ACJORD	10/29/2014	12.00	121.46	4.53	0.04

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2012 (continued).

Table A6 (continued). Light penetration profiles for ACAD.

Site	NETN Code	Date	Depth (m)	Deck cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	PAR cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	Proportion of penetration (PAR/Deck)
Jordan Pond	ACJORD	10/29/2014	13.00	133.44	3.96	0.03
Jordan Pond	ACJORD	10/29/2014	14.00	120.57	2.73	0.02
Jordan Pond	ACJORD	10/29/2014	15.00	136.75	2.36	0.02
Jordan Pond	ACJORD	10/29/2014	16.00	157.09	2.23	0.01
Jordan Pond	ACJORD	10/29/2014	17.00	200.99	2.17	0.01
Jordan Pond	ACJORD	10/29/2014	18.00	214.92	1.86	0.01
Jordan Pond	ACJORD	10/29/2014	19.00	190.78	1.15	0.01
Lake Wood	ACWOOD	6/16/2014	0.10	1322.10	1216.90	0.92
Lake Wood	ACWOOD	6/16/2014	0.50	1013.10	715.66	0.71
Lake Wood	ACWOOD	6/16/2014	1.00	1103.40	636.62	0.58
Lake Wood	ACWOOD	6/16/2014	2.00	1160.30	415.64	0.36
Lake Wood	ACWOOD	6/16/2014	3.00	1429.60	297.84	0.21
Lake Wood	ACWOOD	6/16/2014	3.66	1529.70	266.96	0.17
Lake Wood	ACWOOD	7/23/2014	0.10	1309.80	1399.00	1.07
Lake Wood	ACWOOD	7/23/2014	0.10	1139.40	1478.10	1.30
Lake Wood	ACWOOD	7/23/2014	0.50	1223.30	1102.10	0.90
Lake Wood	ACWOOD	7/23/2014	1.00	1227.20	840.38	0.69
Lake Wood	ACWOOD	7/23/2014	2.00	1272.80	567.52	0.45
Lake Wood	ACWOOD	7/23/2014	3.00	1234.90	215.36	0.17
Lake Wood	ACWOOD	7/23/2014	3.50	1222.50	136.47	0.11
Lake Wood	ACWOOD	8/25/2014	0.10	1508.40	1632.40	1.08
Lake Wood	ACWOOD	8/25/2014	0.50	1510.00	1328.10	0.88
Lake Wood	ACWOOD	8/25/2014	1.00	1570.90	820.86	0.52
Lake Wood	ACWOOD	8/25/2014	2.00	1377.00	445.25	0.32
Lake Wood	ACWOOD	8/25/2014	3.00	1501.00	250.60	0.17
Lake Wood	ACWOOD	8/25/2014	3.50	1527.80	246.95	0.16
Lake Wood	ACWOOD	9/22/2014	0.10	1365.30	1230.70	0.89
Lake Wood	ACWOOD	9/22/2014	0.50	1715.40	1277.00	0.74
Lake Wood	ACWOOD	9/22/2014	1.00	342.12	210.33	0.62

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2012 (continued).

Table A6 (continued). Light penetration profiles for ACAD.

Site	NETN Code	Date	Depth (m)	Deck cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	PAR cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	Proportion of penetration (PAR/Deck)
Lake Wood	ACWOOD	9/22/2014	2.00	400.00	112.09	0.28
Lake Wood	ACWOOD	9/22/2014	3.00	1366.60	164.46	0.12
Lake Wood	ACWOOD	9/22/2014	3.20	1437.90	129.35	0.09
Lake Wood	ACWOOD	10/24/2014	0.01	144.26	139.10	0.96
Lake Wood	ACWOOD	10/24/2014	0.10	139.41	121.19	0.87
Lake Wood	ACWOOD	10/24/2014	0.50	129.90	86.05	0.66
Lake Wood	ACWOOD	10/24/2014	1.00	132.12	59.31	0.45
Lake Wood	ACWOOD	10/24/2014	2.00	127.64	35.19	0.28
Lake Wood	ACWOOD	10/24/2014	3.00	127.17	21.25	0.17
Lake Wood	ACWOOD	10/24/2014	3.50	124.99	15.17	0.12
Round Pond	ACROUN	5/23/2014	0.01	482.53	451.28	0.94
Round Pond	ACROUN	5/23/2014	0.10	462.67	363.41	0.79
Round Pond	ACROUN	5/23/2014	0.50	458.17	263.39	0.57
Round Pond	ACROUN	5/23/2014	1.00	459.61	166.57	0.36
Round Pond	ACROUN	5/23/2014	2.00	456.95	81.74	0.18
Round Pond	ACROUN	5/23/2014	3.00	452.09	58.42	0.13
Round Pond	ACROUN	5/23/2014	4.00	446.54	27.43	0.06
Round Pond	ACROUN	5/23/2014	4.80	438.68	11.24	0.03
Round Pond	ACROUN	6/19/2014	0.10	1794.90	1839.80	1.03
Round Pond	ACROUN	6/19/2014	0.50	1783.30	1574.10	0.88
Round Pond	ACROUN	6/19/2014	1.00	1822.50	1143.60	0.63
Round Pond	ACROUN	6/19/2014	2.00	1807.30	431.96	0.24
Round Pond	ACROUN	6/19/2014	3.00	1798.60	223.44	0.12
Round Pond	ACROUN	6/19/2014	4.00	1798.00	123.74	0.07
Round Pond	ACROUN	6/19/2014	5.00	1830.50	60.95	0.03
Round Pond	ACROUN	7/28/2014	0.10	813.87	774.81	0.95
Round Pond	ACROUN	7/28/2014	0.50	678.08	349.77	0.52
Round Pond	ACROUN	7/28/2014	1.00	622.20	157.92	0.25
Round Pond	ACROUN	7/28/2014	2.00	585.80	57.63	0.10

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2012 (continued).

Table A6 (continued). Light penetration profiles for ACAD.

Site	NETN Code	Date	Depth (m)	Deck cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	PAR cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	Proportion of penetration (PAR/Deck)
Round Pond	ACROUN	7/28/2014	3.00	512.85	20.72	0.04
Round Pond	ACROUN	7/28/2014	4.00	545.89	7.81	0.01
Round Pond	ACROUN	7/28/2014	5.00	535.83	3.19	0.01
Round Pond	ACROUN	7/28/2014	5.70	569.19	3.06	0.01
Round Pond	ACROUN	8/21/2014	0.10	906.20	967.38	1.07
Round Pond	ACROUN	8/21/2014	0.50	1098.70	734.22	0.67
Round Pond	ACROUN	8/21/2014	1.00	816.51	266.88	0.33
Round Pond	ACROUN	8/21/2014	2.00	1221.50	177.55	0.15
Round Pond	ACROUN	8/21/2014	3.00	1420.60	87.55	0.06
Round Pond	ACROUN	8/21/2014	4.00	1425.10	21.94	0.02
Round Pond	ACROUN	8/21/2014	5.00	1268.30	5.36	0.00
Round Pond	ACROUN	9/22/2014	0.10	1512.00	1414.80	0.93
Round Pond	ACROUN	9/22/2014	0.50	1477.00	830.33	0.56
Round Pond	ACROUN	9/22/2014	1.00	1535.20	505.45	0.33
Round Pond	ACROUN	9/22/2014	2.00	1453.40	244.12	0.17
Round Pond	ACROUN	9/22/2014	3.00	1432.30	97.96	0.07
Round Pond	ACROUN	9/22/2014	4.00	1471.90	42.96	0.03
Round Pond	ACROUN	9/22/2014	5.00	1498.80	20.00	0.01
Round Pond	ACROUN	9/22/2014	5.20	1606.10	16.26	0.01
Round Pond	ACROUN	10/24/2014	0.10	214.68	189.05	0.88
Round Pond	ACROUN	10/24/2014	0.50	209.95	131.06	0.62
Round Pond	ACROUN	10/24/2014	1.00	216.64	81.02	0.37
Round Pond	ACROUN	10/24/2014	2.00	211.30	34.39	0.16
Round Pond	ACROUN	10/24/2014	3.00	263.47	19.31	0.07
Round Pond	ACROUN	10/24/2014	4.00	238.90	8.91	0.04
Round Pond	ACROUN	10/24/2014	5.00	236.84	4.24	0.02
Round Pond	ACROUN	10/24/2014	5.52	238.35	2.58	0.01
Upper Breakneck	ACUBRK	5/28/2014	0.01	621.38	641.90	1.03
Upper Breakneck	ACUBRK	5/28/2014	0.10	623.69	606.91	0.97

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2012 (continued).

Table A6 (continued). Light penetration profiles for ACAD.

Site	NETN Code	Date	Depth (m)	Deck cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	PAR cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	Proportion of penetration (PAR/Deck)
Upper Breakneck	ACUBRK	5/28/2014	0.50	633.82	438.26	0.69
Upper Breakneck	ACUBRK	5/28/2014	1.00	463.68	241.34	0.52
Upper Breakneck	ACUBRK	5/28/2014	1.50	340.28	145.76	0.43
Upper Breakneck	ACUBRK	5/28/2014	2.00	332.20	113.69	0.34
Upper Breakneck	ACUBRK	5/28/2014	2.50	462.31	74.41	0.18
Upper Breakneck	ACUBRK	5/28/2014	3.00	584.08	55.47	0.09
Upper Breakneck	ACUBRK	5/28/2014	3.70	535.65	35.89	0.07
Upper Breakneck	ACUBRK	6/18/2014	0.10	2136.80	1912.70	0.90
Upper Breakneck	ACUBRK	6/18/2014	0.50	1795.40	1119.60	0.65
Upper Breakneck	ACUBRK	6/18/2014	1.00	1502.00	666.48	0.44
Upper Breakneck	ACUBRK	6/18/2014	2.00	2238.30	492.66	0.22
Upper Breakneck	ACUBRK	6/18/2014	3.00	1417.40	140.62	0.10
Upper Breakneck	ACUBRK	6/18/2014	3.70	1667.70	68.61	0.04
Upper Breakneck	ACUBRK	7/23/2014	0.10	1834.20	1515.50	0.83
Upper Breakneck	ACUBRK	7/23/2014	0.50	1823.60	1029.10	0.56
Upper Breakneck	ACUBRK	7/23/2014	1.00	1786.10	556.52	0.31
Upper Breakneck	ACUBRK	7/23/2014	2.00	1752.30	150.04	0.09
Upper Breakneck	ACUBRK	7/23/2014	3.00	1854.50	94.35	0.05
Upper Breakneck	ACUBRK	7/23/2014	3.60	1838.00	45.57	0.02
Upper Breakneck	ACUBRK	8/25/2014	0.10	935.59	1191.90	2.94
Upper Breakneck	ACUBRK	8/25/2014	0.50	1131.70	802.90	0.71
Upper Breakneck	ACUBRK	8/25/2014	1.00	1145.30	477.67	0.42
Upper Breakneck	ACUBRK	8/25/2014	2.00	1188.50	159.95	0.13
Upper Breakneck	ACUBRK	8/25/2014	3.00	1127.90	65.54	0.06
Upper Breakneck	ACUBRK	8/25/2014	3.70	1120.60	42.68	0.04
Upper Breakneck	ACUBRK	9/16/2014	0.10	439.88	382.26	0.87
Upper Breakneck	ACUBRK	9/16/2014	0.50	455.41	230.73	0.51
Upper Breakneck	ACUBRK	9/16/2014	1.00	462.20	147.62	0.32
Upper Breakneck	ACUBRK	9/16/2014	2.00	452.40	71.14	0.16

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2012 (continued).

Table A6 (continued). Light penetration profiles for ACAD.

Site	NETN Code	Date	Depth (m)	Deck cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	PAR cell ($\mu\text{mol s}^{-1} \text{m}^{-2}$)	Proportion of penetration (PAR/Deck)
Upper Breakneck	ACUBRK	9/16/2014	3.00	444.34	32.99	0.07
Upper Breakneck	ACUBRK	10/27/2014	0.10	403.37	507.50	1.26
Upper Breakneck	ACUBRK	10/27/2014	0.50	501.21	303.26	0.63
Upper Breakneck	ACUBRK	10/27/2014	1.00	453.49	108.61	0.24
Upper Breakneck	ACUBRK	10/27/2014	2.00	321.43	16.98	0.05
Upper Breakneck	ACUBRK	10/27/2014	3.00	386.32	5.56	0.01
Upper Breakneck	ACUBRK	10/27/2014	3.91	567.04	3.51	0.01

Appendix B. Acadia National Park (ACAD) Blank and Replicate Water Samples, 2014.

Table B1. Blank sample analysis results (Acadia NP). * reporting limit lowered to 1 ueq/L in August 2014 ** estimated value

Site	Date	ANC (µeq/L)	A Color (PCU)	DOC (mg/L)	Chla (µg/L)	Cl (µeq/L)	SO ₄ (µeq/L)	TP (µg/L)	TN (mg/L)	NO ₂ (mg/L)	NO ₃ (µeq/L)	NH ₃ (mg/L)
ACCADS	5/15/2014	-2.40	0	<MRL 0.5		<MRL 2	<MRL 2	<MRL 1	<MRL 0.1	<MRL 0.005	<MRL 1	<MRL 0.08
ACSEAL	6/24/2014	-2.27	0	0.65	<MRL 1	0.7**	<MRL 2	<MRL 1	<MRL 0.1	<MRL 0.005	<MRL 1	<MRL 0.0025
ACABIN	8/14/2014	-1.43	1	<MRL 0.5		5	1.5*	<MRL 1	0.045**	<MRL 0.001	<MRL 1	<MRL 0.0025
ACEAGL	8/18/2014	5.56	3	<MRL 0.5	<MRL 1	3	1.5*	<MRL 1	<MRL 0.1	<MRL 0.001	<MRL 1	0.01

Table B2. Replicate sample analysis results and measurement quality analysis (Acadia NP).

Site	Date	Color Reg	Color Rep	Diff (PCU)	% Diff	DOC Reg	DOC Rep	Diff (mg/L)	% Diff	ANC Reg	ANC Rep	Diff (µeq/L)	% Diff	Chla Reg	Chla Rep	Diff (µg/L)	% Diff
ACKEBO	5/12/2014	2	2.0	0.00	0.0%	0.73	0.61	0.12	16.4%	84.9	84.1	0.800	0.9%				
ACLONG	6/23/2014	19	18.0	1.00	5.3%	3.27	3.37	-0.10	3.1%	70.6	70.7	-0.100	0.1%	1.3	1.4	-0.10	8.0%
ACMRSL	8/7/2014	90	92.0	-2.00	2.2%	6.54	6.46	0.08	1.2%	392.6	393.5	-0.870	0.2%				
ACWOOD	8/25/2014	29	28.0	1.00	3.4%	2.67	2.65	0.02	0.7%	77.1	77.2	-0.040	0.1%	2.5	2.3	0.20	8.0%

Site	Date	TP Reg	TP Rep	Diff (µg/L)	% Diff	TN Reg	TN Rep	Diff (mg/L)	% Diff	NO ₃ Reg	NO ₃ Rep	Diff (µeq/L)	% Diff
ACKEBO	5/12/2014	< MRL	< MRL			< MRL	< MRL			< MRL	< MRL		
ACLONG	6/23/2014	3.6	3.6	0.0	0.0%	0.22	0.15	0.07	33.3%	< MRL	< MRL		
ACMRSL	8/7/2014	11.6	12.7	-1.1	9.5%	0.29	0.33	-0.04	11.9%	3.9	3.3	0.60	15.4%
ACWOOD	8/25/2014	10.2	11.1	-0.9	8.8%	0.24	0.23	0.01	4.6%	1.3	< MRL		

Appendix A. Acadia National Park (ACAD) Water Monitoring Data, 2012 (continued).

Site	Date	NO ₂ Reg	NO ₂ Rep	Diff (mg/L)	% Diff	NH ₃ Reg	NH ₃ Rep	Diff (mg/L)	% Diff	SO ₄ Reg	SO ₄ Rep	Diff (µeq/L)	% Diff
ACKEBO	5/12/2014	< MRL	< MRL			< MRL	< MRL			47.0	47.0	0.0	0.0%
ACLONG	6/23/2014	< MRL	< MRL			< MRL	< MRL			56.0	56.0	0.0	0.0%
ACMRSL	8/7/2014	< MRL	< MRL			0.035	0.027	0.008	22.9%	77.0	76.0	1.0	1.3%
ACWOOD	8/25/2014	< MRL	< MRL			0.020	0.016	0.004	20.0%	6.9	6.7	0.2	2.9%

Site	Date	Cl Reg	Cl Rep	Diff (µeq/L)	% Diff
ACKEBO	5/12/2014	91	91	0.0	0.0%
ACLONG	6/23/2014	220	220	0.0	0.0%
ACMRSL	8/7/2014	635	629	6.0	0.9%
ACWOOD	8/25/2014	90	105	-15.0	16.7%

The Department of the Interior protects and manages the nation's natural resources and cultural heritage; provides scientific and other information about those resources; and honors its special responsibilities to American Indians, Alaska Natives, and affiliated Island Communities.

NPS 123/132886, May 2016

National Park Service
U.S. Department of the Interior



Natural Resource Stewardship and Science

1201 Oakridge Drive, Suite 150
Fort Collins, CO 80525

www.nature.nps.gov

2016

NationalParkService.
CENTENNIAL

EXPERIENCE YOUR AMERICA™