

Historic Resources Survey Report Hawkinsville, Pulaski County, Georgia

Prepared For:

The City of Hawkinsville
96 Broad Street
P.O. Box 120
Hawkinsville, GA 31036

Prepared By:


Terracon

2105 Newpoint Place, Suite 600
Lawrenceville, Georgia 30043
(770) 623- 4655

Project No. 49197855

Authors:

Jonathan Brown, M.H.P., Mills Dorn M.H.P., Kade Ottaway



Jonathan Brown, M.H.P.
Principal Investigator

September 2020

TABLE OF CONTENTS

TABLE OF CONTENTS.....	1
TABLE OF FIGURES	2
1.0 INTRODUCTION.....	3
2.0 EXECUTIVE SUMMARY	4
3.0 PROJECT DESCRIPTION.....	6
4.0 PREVIOUS PRESERVATION PROJECTS	6
5.0 DEVELOPMENTAL HISTORY	7
6.0 METHODOLOGY.....	10
7.0 RECOMMENDATIONS FOR FUTURE PRESERVATION EFFORTS	11
8.0 SURVEY RESULTS AND ARCHITECTURAL ANALYSIS	12
9.0 RESOURCE TYPES	12
9.1 TABLE 1: LIST OF RESOURCE TYPES	14
9.2 QUEEN ANNE COTTAGE TYPE.....	15
9.3 GEORGIAN COTTAGE TYPE.....	16
9.4 GABLED WING COTTAGE TYPE.....	17
9.5 SADDLEBAG TYPE.....	18
9.6 CENTRAL HALLWAY TYPE	19
9.7 NEW SOUTH COTTAGE TYPE	20
9.8 SHOTGUN TYPE	21
9.9 EXTENDED HALL AND PARLOR TYPE.....	22
9.10 BUNGALOW TYPE	23
9.11 GEORGIAN HOUSE TYPE.....	24
9.12 SIDE GABLED COTTAGE TYPE.....	25
9.13 MOBILE HOME TYPE.....	26
9.14 AMERICAN SMALL HOUSE TYPE	27
9.15 RANCH TYPE.....	28
9.16 SPLIT LEVEL TYPE	29
9.17 FRONT GABLE CHURCH.....	30
9.18 MULTIFAMILY DWELLING	31
9.19 COMMUNITY RECREATION CENTER	32
9.20 SCHOOL BUILDING/EQUALIZATION	33
9.21 CLUBHOUSE TYPE.....	34
9.22 STORAGE SHED TYPE.....	35
9.23 COMMERCIAL PROPERTY TYPE.....	36
9.24 CEMETERY	37
10.0 BUILDING STYLES	38
10.1 TABLE 2: LIST OF BUILDING STYLES	38
10.2 FOLK VICTORIAN.....	39
10.3 COLONIAL REVIVAL.....	40
10.4 NEOCLASSICAL REVIVAL	41
10.5 CRAFTSMAN	42

10.6	MODERN MOVEMENT- CONTEMPORARY	43
11.0	BIBIOGRAPHY	44
	APPENDIX A: SURVEY TABLE	46
	APPENDIX B: SURVEY MAP	47

TABLE OF FIGURES

Figure 1: GNAHRGIS ID No. 269362, Shotgun House, located at 57 Henry Way.....	3
Figure 2: Project boundary with surveyed historic resources.	5
Figure 3: GNAHRGIS ID No. 55080, Norfolk Southern Depot, located at 116 North Lumpkin Street.....	11
Figure 4: GNAHRGIS ID No. 271562, Lumpkin Street School, located at 163 North Lumpkin Street.....	12
Figure 5: GNAHRGIS ID No. 55160, Queen Anne Type, located at 58 Martin Luther King Jr. Boulevard....	15
Figure 6: GNAHRGIS ID No. 273596, Georgian Cottage Type, located at 226 North Dooley Street.	16
Figure 7: GNAHRGIS ID No. 55137, Gabled Wing Cottage Type, located at 413 Second Street.	17
Figure 8: GNAHRGIS ID No. 272057, Saddlebag Type, located at 8 Dozier Street.	18
Figure 9: GNAHRGIS ID No. 55108, Central Hallway Type, located at 265 North Dooley Street.	19
Figure 10: GNAHRGIS ID No. 55156, New South Cottage Type, located at 63 MLK Boulevard.....	20
Figure 11: GNAHRGIS ID No. 273605, Shotgun Type, located at 34 Texas Alley.	21
Figure 12: GNAHRGIS ID No. 55105, Extended Hall and Parlor Type, located at 227 North Dooley Street.	22
Figure 13: GNAHRGIS ID No. 273615, Bungalow Type, located at 231 North Dooley Street.	23
Figure 14: GNAHRGIS ID No. 273617, Georgian House Type, located at 223 North Dooley Street.	24
Figure 15: GNAHRGIS ID No. 272062, Side Gabled Cottage Type, located at 23 Railroad Street.	25
Figure 16: GNAHRGIS ID No. 273426, Manufactured House Type, located at 154 North Lumpkin Street. .	26
Figure 17: GNAHRGIS ID No. 55105, American Small House Type, located at 225 North Dooley Street. ..	27
Figure 18: GNAHRGIS ID No. 268262, Ranch Type, located at 34 Knotty Pine Drive.....	28
Figure 19: GNAHRGIS ID No. 273602, Split Level Type, located at 23 Carter Street.....	29
Figure 20: GNAHRGIS ID No. 269371, Front Gable church Type, located at 43 Henry Way.....	30
Figure 21: GNAHRGIS ID No. 271580, Multifamily Dwelling Type, located at 62 Sixth Street.	31
Figure 22: GNAHRGIS ID No. 271589, Community Recreation Center, located at 62 Sixth Street.....	32
Figure 23: GNAHRGIS ID No. 271562, School Building/Equalization, located at 163 Lumpkin Street.....	33
Figure 24: GNAHRGIS ID No. 271936, Clubhouse Type, located at 23 Dozier Street.....	34
Figure 25: GNAHRGIS ID No. 269406, Storage Shed Type, located on Anderson Lane.....	35
Figure 26: GNAHRGIS ID No. 268143, Commercial Property Type, located at 132 Progress Avenue.....	36
Figure 27: GNAHRGIS ID No. 268205, Orange Hill Cemetery, located on Sixth Avenue.	37
Figure 28: GNAHRGIS ID No. 273596, Folk Victorian Style, located at 226 North Dooley Street.....	39
Figure 29: GNAHRGIS ID No. 268215, Colonial Revival Style, located at 22 Colson Street.	40
Figure 30: GNAHRGIS ID No. 273617, Neoclassical Revival Style, located at 223 North Dooley Street.	41
Figure 31: GNAHRGIS ID No. 55177, Craftsman Style, located at 68 Progress Avenue.....	42
Figure 32: GNAHRGIS ID No. 273642, Modern Movement- Contemporary Style, 64 Progress Avenue.	43

1.0 INTRODUCTION



Figure 1: GNAHRGIS ID No. 269362, Shotgun House, located at 57 Henry Way.


The Hawkinsville Historic Resource Survey was funded through a grant received from the Georgia Natural Resources Historic Preservation Division (HPD) in June of 2019 as well as funds from the City of Hawkinsville. The goal of the survey is to assist the City with future planning efforts related to historic preservation and provide guidance for the protection of culturally and historically significant resources. The City of Hawkinsville issued a request for proposals (RFP) for a Phase I Historic Resource Survey to be conducted according to HPD standards. The scope of work for the survey would include buildings, structures, sites, and objects constructed within 40 years and within a predetermined boundary within the city of Hawkinsville. On September 30, 2019, Terracon Consultants Inc (Terracon) submitted a proposal to the City of Hawkinsville to be considered for the proposed contract involving the Phase I Historic Resource Survey. On October 1, 2019 the City of Hawkinsville informed Terracon that they had won the bid to conduct the Phase I survey.

Field survey was conducted between November 18 and November 22 by Jonathan Brown and Kade Ottaway. The surveyed resources were photographed and documented in the field.

2.0 EXECUTIVE SUMMARY


Terracon Consultants, Inc. conducted a Historic Resources Survey for the City of Hawkinsville in Hawkinsville, Pulaski County, Georgia, which identified 287 total historic-age resources that were included in the survey (Figure 2). The term “historic-age resource” refers to anything in the built environment that is over 40 years old, as determined by HPD standards. Therefore, the year 1979 was used as a cut-off date for the purposes of this survey. Prior to this survey, two other surveys were conducted in the city of Hawkinsville. The first survey was conducted in 1976 and the second survey was conducted in 1990. Of the 287 total historic-age resources surveyed as part of this survey, 47 were resurveyed from the prior surveys. Of those resurveyed, 17 were determined to be no longer extant. Therefore, a total of 270 historic-age resources were identified as being extant at the time of the survey within the survey area.

This survey is a Phase I survey for the City of Hawkinsville. Work was performed in compliance with the Secretary of the Interior's *Standards for Archaeology and Historic Preservation, which include the Standards for Evaluation, Identification, and Registration*. The project work was prepared in accordance to (a) *National Register Bulletin: Guidelines for Local Surveys: A Basis for Preservation Planning*; (b) the HPD guidance materials for identifying and documenting Georgia's historic resources, including the “Georgia Historic Resources Manual, July 2019,” “Tips for Using Georgia's Natural, Archaeological, and Historic Resources Geographic Information System (GNAHRGIS) as part of a Georgia Historic Resources Survey,” and the Historic Resources Surveys and GNAHRGIS “Primer”; as well as GNAHRGIS. The 270 surveyed extant historic-age resources were entered in GNAHRGIS. The survey information was entered under Survey ID 2410, “City of Hawkinsville Phase I, 2019.”



LEGEND

- PROJECT BOUNDARY
- SURVEYED PARCELS
- TAX PARCELS



THIS DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

Project Mng:	JDM	Project No.	49197855
Drawn By:	RLW	Scale:	AS SHOWN
Checked By:	RLW/MRF	File No.	49197855-2
Approved By:	JDM	Date:	SEPTEMBER 2020

Terracon
Consulting Engineers and Scientists

2105 Newpoint Place, Ste. 600 Lawrenceville, GA 30043
(770) 623-0755 (770) 623-9628

CULTURAL RESOURCES	FIG. No.
HISTORIC RESOURCES SURVEY REPORT HAWKINSVILLE PULASKI COUNTY, GEORGIA	2

3.0 PROJECT DESCRIPTION

The goal of this survey was to identify any historic-age resources within a defined area of the city of Hawkinsville. The city of Hawkinsville is located in the northeast portion of Pulaski County in the Upper Coastal Plains region of the state of Georgia. The Ocmulgee River runs in a southerly direction east of the city. The city of Hawkinsville includes 5.04 square miles of land and is the county seat of Pulaski County. The city consists of a downtown area and includes a commercial district. Civic buildings, including Hawkinsville City Hall, Pulaski County Courthouse, the United States Post Office, and the M. E. Roden Memorial Library are located adjacent to the commercial district to the west. An industrial area is located north of the commercial district. This industrial area serves the cotton and peanut industry and processes these two commodities for shipment. Residential areas are located adjacent to the commercial and industrial areas. Residences consist of single-family houses as well as multi-family residences. Included in these residential areas are churches, schools, cemeteries, parks, day care facilities, and some industrial and commercial buildings mixed throughout.

The survey area, within the city limits of Hawkinsville, is bounded by Pinewood Drive, 6th Street, North Jackson Street, 1st Street, 3rd Street, Texas Alley, 2nd Street, and Golden Isles Parkway. The boundaries of the survey area were determined by the City of Hawkinsville to include as many historic-age resources as the budget for the project would allow. Within the survey area are a total of 270 historic-age resources. The majority of historic-age resources within the survey area are residences and include both single family and multi-family dwellings. The 6th Street Federal Housing Apartments, located at 62 6th Street, is the only historic-age apartment complex located in the survey area. Also included in the survey area are commercial and industrial buildings, churches, three cemeteries, and one building previously used as a school.

4.0 PREVIOUS PRESERVATION PROJECTS

Previous to this survey, a 1976 survey and a 1992 survey were performed in the city of Hawkinsville. Additionally, six total properties have been listed in the NRHP. These six properties include Hawkinsville City Hall- Auditorium (NRHP #73000638), the Hawkinsville Commercial and Industrial Historic District (NRHP #04001349), the Hawkinsville Public School (NRHP #08000492), the Merritt-Ragan House (NRHP #91001156), Pulaski County Courthouse (NRHP #80001224), St. Thomas African Methodist Episcopal Church (NRHP #00001477), and Taylor Hall (NRHP #78001000). Hawkinsville City Hall- Auditorium and the Pulaski County Courthouse are both contributing properties to the Hawkinsville Commercial and Industrial Historic District. Additionally, the Design Guidelines, Downtown Historic District, Hawkinsville, Georgia were developed and presented to the City of Hawkinsville in 2010 and was funded in part by a 2009 Historic Preservation Fund grant from the Georgia State Historic Preservation Office and a subgrant from the City of Hawkinsville, Georgia.

Georgia's Railroads, 1833-2015 Historic Context and Statewide Survey identified four railroad lines running through the city of Hawkinsville including the *Hawkinsville & Western Railroad* (abandoned in 1920), *Hawkinsville & Florida Southern Railway* (abandoned in 1923), *Wrightsville & Tennille Railroad* (abandoned in 1941), and *Norfolk Southern* (abandoned in 1996). These four railroad lines are no longer extant within the city of Hawkinsville. The Norfolk Southern depot was identified in the context and is still extant and located at 116 North Lumpkin Street within the Hawkinsville Commercial and Industrial Historic District.

The 1976 survey identified eighteen resources within this survey's project area. The 1992 survey identified thirty-one resources within the survey's project area and sixteen of these thirty-one surveyed resources were included in the 1976 survey. Of those resources surveyed in the 1976 and 1992 surveys, five were found to be razed and are no longer extant. Of the resources surveyed in 1992, twelve were found to be razed and no longer extant.

One resource, the Lumpkin Street School, located at 163 North Lumpkin Street, has begun the process of being nominated for inclusion in the NRHP. It has been identified for its significance as a former equalization school. A National Register of Historic Places Preliminary Eligibility Application was submitted to HPD in 2018.

In 1989 the City of Hawkinsville adopted its Historic Preservation Ordinance. The ordinance established the Historic Preservation Commission (HPC) which consists of seven appointed members who serve three year terms. The purpose of the HPC is to promote local history by initiating local designation, conducting design review process, improving public education and awareness, securing preservation related grant funding, and supporting preservation planning and research. The HPC also commissioned the development of the city's "Design Guidelines: Hawkinsville Downtown Historic District" which provides "information on local preservation measures, the design review process, and the visual character which defines Hawkinsville's Downtown Historic District" (Design Guidelines, nd).

Because the City of Hawkinsville met the necessary requirements, including enacting a historic preservation ordinance and forming a local preservation commission, Hawkinsville was able to apply to become a Certified Local Government (CLG). On December 2, 2004, Hawkinsville was awarded CLG status. CLG status allows the City of Hawkinsville to apply for a number of different preservation grants and funding opportunities at the state and federal levels including the grant for this Phase I Historic Resources Survey.

5.0 DEVELOPMENTAL HISTORY

The creation of Pulaski County, Georgia occurred in 1808 from land that was originally part of Laurens County. Pulaski became Georgia's 36th county and was named after Count Casimir Pulaski, a Polish soldier who died in Savannah during the American Revolution. The county seat

was established in Hartford which is located east of the banks of the Ocmulgee River (Remier, 2019).

The area that would later become Pulaski County was the location of the capital of the Creek Indian Confederacy. The fertile land and large numbers of wildlife in the area made the area a perfect location for the Creeks. The fertile Creek lands, however, were also desirable to non-native settlers who saw opportunities to farm the land that belonged to the Creeks. Tensions were high in the areas controlled by the Creeks as more outsiders began settling in lands that had previously belonged to the Creeks. By 1813 the Creeks were divided on whether or not to adhere to the issue of removal. War broke out as a faction of the Creeks who were adamant about remaining on their lands, began attacking not only non-native settlements but loyalist Creeks as well. United States forces, led by General Andrew Jackson, were able to suppress the insurgency and the Treaty of Fort Jackson was signed in 1814. The treaty would cede 23 million acres of land and would establish the United States government as the controlling agency in the region. In 1825 the second Treaty of Indian Springs was signed by Creek leadership which ceded all remaining Creek land in Georgia. By 1827 the Creeks were effectively removed from Georgia (National Parks Service, nd).

Located on the western banks of the Ocmulgee River, the town of Hawkinsville was incorporated in 1830. The name Hawkinsville was given to the city in honor of Colonel Benjamin Hawkins. Col. Hawkins served as an agent for Indian affairs south of the Ohio River from 1796 – 1803. By 1836 the county seat was moved from Hartford to Hawkinsville. Hawkinsville was determined to be a more desirable location as it is located on a bluff and less prone to flooding (Gibbs and Provost, 2008).

Economically Hawkinsville relied on agriculture to support the cities growth, initially agriculture in Pulaski County involved the production of timber and corn. As this agriculture grew Hawkinsville became a center for shipping the commodities. The city's proximity to the Ocmulgee River transitioned the economy of Hawkinsville into one of the first wholesale centers in Georgia. Steamboats could navigate the Ocmulgee easily making the river a necessary source of transportation in the region. This led to the creation of roads and highways connecting the city to other areas of the state (Gibbs, Provost, 2008).

The high point of trade in Hawkinsville came during the 1850s. During this period the city was located in the center of the cotton belt and became a center for the distribution of the commodity. Soon after this however, the expansion of the railroads in Georgia brought competition to river travel in Hawkinsville. Hawkinsville's close proximity to the river and the expansion of the railroads boosted the town's economy. Additionally, Hawkinsville's economy was largely driven by the institution of slavery to the point that no other area in Middle Georgia had a higher concentration of slaves than Hawkinsville and Pulaski County. Not surprisingly, the citizens of Hawkinsville voted for Georgia's secession from the Union in 1861 and efforts were initiated to form regiments that would later fight for the Confederacy (Gibbs, Provost, 2008).

Historic Resources Survey Report

City of Hawkinsville ■ Pulaski County, GA

September 25, 2020 ■ Terracon Project No. 49197855



In November 1861, the 49th Infantry Regiment was organized with men from Pulaski and surrounding counties. This regiment, under the leadership of General J.R. Anderson and E.L. Thomas, took part in campaigns including Seven Pines, Cold Harbor, Petersburg, Appomattox, Second Manassas, Fredericksburg, Chancellorsville, and Gettysburg. Some of the men who fought in this regiment are buried in the Orange Hill Cemetery in Hawkinsville including Captain Robert Sanders Anderson and Julius Bagby. Captain Ruel Wooten Anderson, who also fought for the Confederacy is also buried here (National Parks Service, nd).

After the Civil War and the impact of General William T. Sherman's March to the Sea leading to the destruction of the railroads, travel shortly resumed on the river. The city's close proximity to the Ocmulgee made the city an important inland port. The combination of steamboat travel and railroads provided the city of Hawkinsville with numerous economic advantages, most notably logistical operations related to movement of raw agricultural materials. Additionally, the conditions of the river here made travelling via steamboat ideal. The city's close proximity to the river benefitted Hawkinsville but was not without its dangers. In January 1925 a flood occurred that led to the destruction of many of the city's industries and halted travel east from Hawkinsville. Most notably, the timber industry in the area was especially impacted by this flood as rising waters fell trees, submerged sawmills, and swept cut lumber downstream (Remier, 2018).

Other economic developments in Hawkinsville came in the form of equestrian sports. In 1894 the Pulaski County Fair Association established equestrian speed demonstrations. By the 1920s these events led to the construction of stables and a racetrack. During this period harness racing became a large event in the city and harness racers traveled across the United States to train for the winter at the Hawkinsville racetrack (Remier, 2018). Hawkinsville also continued to prosper economically from the production of cotton. However, the 1930s saw cotton crops decimated as a result of the boll weevil. Farmers were forced to look for alternative crops that could grow well in the region and that would also be beneficial economically. Farmers realized that peanuts would grow well in the region's climate (Gibbs, Provost, 2008). In 1968 the Heart of Georgia Peanut and Gin Company was founded in Hawkinsville. Located at the intersection of Jackson Street and Second Street, the facility processes, packages, and distributes peanuts and cotton (Bloomberg, n.d.). During the mid-twentieth century harness racing was taking place from fall to spring in Hawkinsville and in 1975 a grant was won by the city to construct the Lawrence L. Bennett Harness Horse Training Facility, opening in 1977. This continues to bring horsemen to the city from across the country (Remier, 2018).

Today the city of Hawkinsville and Pulaski County is home to approximately 11,069 people and is the terminal of several highways connecting other Georgia county capitals. The main employer for the area is the Warner Robin Air Force Base located nearby. The city is home to several buildings nominated to the NRHP. The Ocmulgee River still plays an important role in the city and has become the center of community recreation for the city as well as the county (Remier, 2018).

6.0 METHODOLOGY

The survey was conducted according to the procedures outlined in *The Georgia Historic Resources Survey Manual*. The survey involved the use of USGS topographic maps, land parcel data available through the Pulaski County database, historic aerials, and Sandborn maps to identify potentially historic parcels and structures. The area was surveyed over the course of several days with systematic coverage of the project area. Each assigned resource within the determined boundaries was assessed for historic significance and architectural integrity. A structure with architectural integrity is one that generally retains its original location, design, setting, materials, workmanship, feeling, and association. Included in the survey are historic-age resources that may have compromised integrity or that may be lacking in historic significance and have been noted in GNAHRGIS.

All identified resources were approximately 40 years old or older at the time the fieldwork was performed in November 2019. Therefore, the earliest construction date for inclusion in the survey was 1979. Empty land parcels were not accounted for in the survey. However, land parcels may have been identified as “vacant lots” in the Pulaski County land parcel database and contained resources identified as historic-age; these resources have been included in the survey. Each historic-age resource was photographed, field notes were taken using the Georgia Historic Resource Survey Form, and a resource number was assigned. Sources utilized for age determination and architectural style and type description included Lee and Virginia McAlester’s *A Field Guide to American Houses*, the *Georgia Historic Resources Survey Manual*, HPD’s *House Types in Georgia*, *A Visual Guide to Architecture* by Francis D.K. Ching, *Georgia’s Living Places: Historic Houses in their Landscaped Settings*, *Residential Architectural Styles in Georgia*, and *Guidelines for Evaluation: The Ranch House in Georgia* by New South Associates.



Figure 3: GNAHRGIS ID No. 55080, Norfolk Southern Depot, located at 116 North Lumpkin Street.

7.0 RECOMMENDATIONS FOR FUTURE PRESERVATION EFFORTS

A local initiative has begun the process of nominating the Lumpkin Street School, located at 163 North Lumpkin Street, for inclusion in the NRHP. The former school appears to be significant for its role as an equalization school during the Civil Rights era and can be considered an important cornerstone for African American history in the area. Further documentation is required to advance the nomination process including proper research, photographic, and data records to determine its significance and determine whether a case can be made for inclusion in the NRHP.

Additionally, a possible historic district is located in the northwestern portion of the survey area that includes 35 historic-age resources. These 35 historic-age resources all date from the same era (1970s) and are all of the same house type (Ranch). Though some have undergone additions and alterations, made to the exteriors, they are mostly in good condition and retain enough integrity to be included in a comprehensive boundary. Though the houses in this area do retain a good degree of integrity, it should be noted that many of them are not yet 50 years old and will, therefore, not yet be of historic-age to meet NRHP standards. Furthermore, additional studies will be required to understand and determine the significance of this area.



Figure 4: GNAHRGIS ID No. 271562, Lumpkin Street School, located at 163 North Lumpkin Street.

8.0 SURVEY RESULTS AND ARCHITECTURAL ANALYSIS

The survey identified a total of 287 historic-age resources. Of the 287 total historic-age resources surveyed as part of this survey, 47 were resurveyed from the prior surveys conducted in 1976 and 1990. Of those resurveyed, 17 were determined to be no longer extant. Therefore, a total of 270 historic-age resources were identified as being extant at the time of the survey within the survey area. The historic-age resources identified in the survey include mostly single-family residences with light commercial scattered throughout. In addition to these single-family residential resources are several multifamily residences, churches, cemeteries, a former school, and civic properties. The date of construction for these buildings ranged from the 1890s to 1980.

9.0 RESOURCE TYPES

Building type refers to the overall form of the building, the outline of the main or original part of the building, as well as the general layout of the rooms. A building type is determined by many factors, including plan, stories, arrangement of roofs, porches, windows, etc. and date of construction. Additionally, some buildings may have subtypes. Subtypes are determined by a standard type of building with several variations within the standard type (House Types in Georgia, nd). The most prevalent example in the survey area is the Ranch House type (Sullivan, Reed, and Fedor, 2010).

The survey identified 187 total single-family residential houses, or 69% of the total resources surveyed, that were originally used as single-family residences and that are currently in use as

Historic Resources Survey Report

City of Hawkinsville ■ Pulaski County, GA

September 25, 2020 ■ Terracon Project No. 49197855



single family residences. There were 14 different types of houses identified in the survey including Queen Ann Cottage, Georgian Cottage, Gabled Wing Cottage, Saddlebag, Central Hallway, New South Cottage, Shotgun, Extended Hall Parlor, Bungalow, Georgian House, Side Gabled Cottage, Manufactured House, American Small House, Ranch, and Split Level. The original house type of 28 of the 187 single family residences could not be determined due to additions or alterations that obscured the original construction. Additionally, 14 buildings, or 5% of the total resources surveyed were identified as multi-family residences (10 associated with public housing and 4 duplexes). In total there were 200 historic-age properties currently used for residential purposes surveyed.

Currently there are 12 total commercial buildings, or 4% of the total resources surveyed, within the survey area. Of the 12 commercial buildings, 5 were originally used as single-family residences. Two of these 12 commercial resources have unknown original uses. Of the 7 buildings originally used as commercial properties, one was a gas station/convenience store, one was a retail store, one was a mechanic's shop, and the rest were warehouses/garages.

Four buildings included in the survey were currently used as religious facilities. These included Mt. Pleasant Baptist Church, Pentecostal Episcopal Church of God, New Mount Zion Community Church, and Christian Hope Baptist Missionary Church. All four churches identified in the survey were front gable church types. It is unknown if the Christian Hope Baptist Missionary Church was originally used as a church. Three cemeteries were also included in the survey. They include Orange Hill Cemetery, Pine Bloom Cemetery, and the North Dooley Street Cemetery.

The survey identified 50 properties out of the 270 total surveyed resources, or 19%, that were vacant at the time of the survey. These vacant properties include 41 resources that were originally used as residences (28 single-family residences and 13 multi-family residences), 3 resources originally used for commercial purposes, 1 building formerly used as a school, 1 building formerly used for recreational/entertainment purposes, 1 building originally used as a meeting hall, and 1 resource was identified as a secondary structure that appeared to have been associated with a non-extant building. The remaining two properties had unknown original uses.

A total of 29 buildings could not be identified by building type due to vegetation, additions to the original form of the building, building decay, or a combination of the three.

9.1 Table 1: List of Resource Types

Type	Amount	Date Range
Queen Anne Cottage	2	1890s
Georgian Cottage	5	1890s
Gabled Wing Cottage	8	1900s-1910s
Saddlebag	13	1900s-1930s
Central Hallway	5	1900s-1930s
New South Cottage	3	1900s-1910s
Shotgun	4	1910s-1930s
Extended Hall and Parlor	1	~1920
Bungalow	8	1920s-1930s
Front Gable Bungalow Subtype	5	1920s-1930s
Side Gable Bungalow Subtype	1	~1930
Hipped Bungalow Subtype	2	1920s-1930s
Georgian	1	~1930
Side Gabled Cottage	3	1930s
Manufactured House	10	1960s-1980s
American Small House	41	1930s-1950s
Ranch	86	1940s-1970s
Linear Ranch Subtype	51	1950s- 1970s
Linear Ranch with Clusters Subtype	4	1970s
Compact Ranch Subtype	30	1960s-1980
Rambling Ranch Subtype	1	1948
Split Level House	1	1972
Multifamily Dwellings	27	1940s-1960s
Duplex	16	1940s-1960s
Two-Story Duplex	1	~1960
Apartment Building	10	~1950
Community Recreation Center	1	~1950
Front Gable Church	4	1930s-1965
School Building/Equalization	1	~1950
Clubhouse type/other social/civic clubhouse type	1	~1960
Storage Shed	1	~1920
Commercial Properties	12	~1950-1977
Single Retail (One Story)	4	1960s- 1977
Commercial Warehouse	6	1960s-1970s
One-Story Office Building	1	1956
Road Related Commercial Building- Sales and Service	1	~1950
Unknown	29	1890s-1970s
Cemetery	3	~1880-1890

9.2 Queen Anne Cottage Type

The Queen Anne cottage type is characterized by a square main mass with projecting gables on the front and side. The rooms are arranged asymmetrically, and there is no central hallway- two traits that distinguish the Queen Anne cottage from the New South cottage. The roof is either pyramidal or hipped, and the chimneys are usually found in the interior. The Queen Anne appears in both urban and rural areas as popular middle-class housing in the 1880s and 1890s (House Types in Georgia, nd).

The survey identified 2 Queen Anne Cottage type houses within the project area, or 1% of the 219 identified single family residences surveyed. The dates of construction are typically in the 1890s. These Queen Anne Cottage types appeared to have some alterations done to their exteriors including some additions though they were typically appended to the rear of the houses which aided in obscuring any of the increase in the overall mass and form of the structures. The most common alteration is the inclusion of metal awnings over the windows which are present on both of the only two examples in the survey area.



Figure 5: GNAHRGIS ID No. 55160, Queen Anne Type, located at 58 Martin Luther King Jr. Boulevard.

9.3 Georgian Cottage Type

The Georgian cottage type is named for its floor plan associated with 18th century English Georgian architecture. The Georgian cottage consists of central hallway with two rooms on either side. The plan shape is square or nearly square, the roof is usually hipped but sometimes gabled, and chimneys are sometimes in the exterior walls but usually in the interior of the house, between each pair of rooms. Houses of this type were constructed in almost all periods of Georgia's history, well into the 20th century, but the greatest concentration is between 1850 and 1890 (House Types in Georgia, nd).

The survey identified 5 Georgian cottage type houses within the project area, or 2% of the 219 identified single family residences surveyed. The dates of construction are generally in the 1890s. These Georgian cottage types appeared to be in good condition and had few additions appended to them. Though some examples may have adopted more modern buildings materials, they have generally retained their historic form and massing and most examples still exhibit their historic Folk Victorian style elements.



Figure 6: GNAHRGIS ID No. 273596, Georgian Cottage Type, located at 226 North Dooley Street.

9.4 Gabled Wing Cottage Type

Of the late 19th century house types in Georgia, the gabled wing cottage perhaps has the most examples. The overall plan shape is T or L shaped, and it usually, though not always, has a gabled roof. The gabled wing cottage consists of a gable front at one end of a recessed wing that is parallel to the façade. The front door, located in the recessed wing, may lead into a hallway or directly into the room in the wing. The gabled ell cottage is fairly evenly distributed across Georgia and was popular in both rural and urban areas and in both modest and affluent neighborhoods. Its period of greatest popularity was between the years 1875 and 1915 (House Types in Georgia, nd).

The survey identified 8 Gabled Wing Cottage type houses within the project area, or 4% of the 219 identified single family residences surveyed. The dates of construction range from the early 1900s to approximately 1915. These Gabled Wing Cottage types appeared to be in good condition and had few additions appended to them. The most common alteration to these house types appeared to be the use of vinyl covering the exterior walls.



Figure 7: GNAHRGIS ID No. 55137, Gabled Wing Cottage Type, located at 413 Second Street.

9.5 Saddlebag Type

The saddlebag house derives its name from a central chimney flanked by two rooms, which seem to hang suspended on either side of the chimney. The rooms are usually square, and the roof is usually gabled. There are two subtypes, one with an exterior door into each room and one with a single, central door into a vestibule beside the chimney. The saddlebag houses in Georgia seem to have been constructed mainly in three periods, with the examples in each period linked to three general settings. The earliest saddlebag houses, built in the 1830s and 1840s in rural agricultural areas, are rare in Georgia. In the last few decades of the century, saddlebags were popular for modest housing in the outlying fringes of Georgia's towns and cities. The most surviving examples come from the the period of mill village construction, from about 1910 to 1930 (House Types in Georgia, nd).

The survey identified 13 Saddlebag type houses within the project area, or 6% of the 219 identified single family residences surveyed. The dates of construction range from the early 1900s to the early 1930s. These Saddlebag types appeared to be in good condition and rarely had additions appended to them. The most notable alteration to these house types appeared to be the removal of one of the two original doors on the façade or the removal of the central chimney.



Figure 8: GNAHRGIS ID No. 272057, Saddlebag Type, located at 8 Dozier Street.

9.6 Central Hallway Type

The central hallway type consists of a central hallway or passageway between two rooms. It is distinguished from other types with central hallways by being only one room deep. The central hallway type most frequently has a gabled roof and exterior end chimneys on both gable ends. The type seems to be fairly evenly distributed across the state, appearing mainly on average sized farmsteads and on principal residential streets in Georgia's towns and cities. Most examples of this type were built between 1830 and 1930, with clusters occurring between 1840 to 1860 and 1870 to 1890 (House Types in Georgia, nd).

The survey identified 5 Central Hallway type houses within the project area, or 2% of the 219 identified single family residences surveyed. The dates of construction range from the early 1900s to the 1930s. These Central Hallway types appeared to be in good condition but would generally have numerous additions appended to them. The most common alteration to these house types appeared to be the use of vinyl covering the exterior walls.



Figure 9: GNAHRGIS ID No. 55108, Central Hallway Type, located at 265 North Dooley Street.

9.7 New South Cottage Type

The New South cottage has a central square mass, usually with a hipped roof, and gabled projections. The main distinguishing trait of the New South cottage is its emphasis on symmetry, the key element of which is the central hallway plan. The central hallway is flanked by pairs of rooms, one or both of which might project forward. A pair of gables in the façade, either over projecting rooms or flush with the wall of the main mass, provided additional symmetry to this house type. The greatest numbers are located in a central band across the state in the Piedmont and Upper Coastal Plain and in the state's largest cities and towns. This house type was most popular between the 1890s and 1920s (House Types in Georgia, nd).

The survey identified 3 New South Cottage type houses within the project area, or 1% of the 219 identified single family residences surveyed. The dates of construction range from the early 1900s to approximately 1914. These New South Cottage types appeared to have many alterations done to their exteriors including numerous additions which has significantly compromised their historic form and massing.



Figure 10: GNAHRGIS ID No. 55156, New South Cottage Type, located at 63 MLK Boulevard.

9.8 Shotgun Type

Shotgun houses are characterized by their one room wide and two or more room depth layout. There is no hallway, and all doors typically line up front to back. The roof is usually gables, but hipped roofs were also used. The shotgun house was especially popular in the larger cities of Georgia, but it may be found in small and medium-sized towns as well. Shotgun houses were built mainly for low income workers between the 1870s and 1920s (House Types in Georgia, nd).

The survey identified 4 Shotgun type houses within the project area, or 2% of the 219 identified single family residences surveyed. The dates of construction range from the 1910s to the 1930s. These Shotgun types appeared to be in good condition despite being some examples exhibiting signs of neglect. Many appeared to retain many of the historic building materials and because most of them lack any additions, they mostly retain their historic form and massing. The most common alteration was infill used in the foundation between the historic brick piers.



Figure 11: GNAHRGIS ID No. 273605, Shotgun Type, located at 34 Texas Alley.

9.9 Extended Hall and Parlor Type

The Extended Hall and Parlor type is characterized by its long, rectangular shape with the façade in the narrow end, but there is no recessed front porch. The hall and parlor plan is three or more rooms deep, and the roof may be hipped or gabled. Most surviving examples of the Extended Hall and Parlor type date from the 1920s to 1930s and can be found throughout the state in both rural areas and the outlying parts of towns (House Types in Georgia, nd).

The survey identified 1 Extended Hall and Parlor type house within the project area, or 1% of the 219 identified single family residences surveyed. The date of construction for this house type is approximately 1920. This Extended Hall and Parlor type appeared to have some alterations done to their exterior including an addition though it was appended to the rear of the house which aided in obscuring any of the increase in the overall mass and form of the structures. The historic windows appear to be intact throughout and the exterior walls are covered in clapboard.



Figure 12: GNAHRGIS ID No. 55105, Extended Hall and Parlor Type, located at 227 North Dooley Street.

9.10 Bungalow Type

The Bungalow house forms are long and low with irregular floor plans within an overall rectangular shape. Integral porches are common, as are low pitched roofs with wide overhangs. The Bungalow type is divided into four subtypes based on roof form and orientation: front gable, side gable, hip, and cross gable. The front and side gabled versions of the Bungalow greatly outnumber the hipped bungalows, while cross gable Bungalows are rare. Bungalows were very popular in all regions of Georgia between 1900 and 1930 and can be found in rural and urban areas (House Types in Georgia, nd).

The survey identified 8 Bungalow type houses within the project area, or 4% of the 219 identified single family residences surveyed. The dates of construction range from the 1920s to the 1930s. These Bungalow types appeared to be in good condition but usually had additions appended to them. Additionally, some examples featured modern vinyl siding.



Figure 13: GNAHRGIS ID No. 273615, Bungalow Type, located at 231 North Dooley Street.

9.11 Georgian House Type

With the exception of its two-story height, the Georgian house has all the characteristics of the Georgian cottage. Although the two-story house is less numerous than the one-story cottage, it too was popular from the first decades of the 19th century well into the 20th century. However, most examples of this type were constructed in the periods 1850-1860 and 1900-1930, chiefly in the larger towns and cities (House Types in Georgia, nd).

The survey identified 1 Georgian House type within the project area, or 1% of the 219 identified single family residences surveyed. The date of construction for this house type is approximately 1930. This Georgian House type appeared to have several additions and alterations done to its exterior including several noticeable additions which have significantly altered its form and mass. A handicap accessible ramp has been added to the façade and the windows and exterior wall material have all been replaced with modern vinyl replacements.



Figure 14: GNAHRGIS ID No. 273617, Georgian House Type, located at 223 North Dooley Street.

9.12 Side Gabled Cottage Type

The Side Gabled cottage has a compact square mass consisting of four rooms without a hallway and was economical to build. It has a traditional appearance due to its broad gabled roof and gabled ends at the sides. Only rarely does it have a hipped roof. The floor plan has two variants: a hall and parlor plan with a central doorway and a foursquare plan with equal sized rooms, indicated by two front doors. The Side Gabled cottage was a popular workers' house type in mill villages and in small towns, although high style examples for the affluent can be found. This type was most popular between 1895 and 1930 (House Types in Georgia, nd).

The survey identified 3 Side Gabled Cottage type houses within the project area, or 1% of the 219 identified single family residences surveyed. The dates of construction are typically in the 1930s. These Side Gable Cottage types appeared to have some alterations done to their exteriors including some additions though they were typically appended to the rear of the houses which aided in obscuring any of the increase in the overall mass and form of the structures.



Figure 15: GNAHRGIS ID No. 272062, Side Gabled Cottage Type, located at 23 Railroad Street.

9.13 Mobile Home Type

As the name implies, the mobile home was designed to be transported and are typically manufactured and assembled off site at an assembly plant. The home is then transported to a location to be placed at a permanent or semi-permanent site. The mobile home has a long, narrow, rectangular shape and usually has a nearly flat roof. The bedrooms are usually grouped in one end and the entry and living spaces in the other (House Types in Georgia, nd). This house type generally lacks a chimney and porches are typically added on after being placed. The mobile home type is prevalent in Georgia from the 1960s to the present.

The survey identified 10 mobile home type houses within the project area, or 5% of the 219 identified single family residences surveyed. The dates of construction range from the early 1960s to the early 1980s. These mobile home types appeared to be in good condition and rarely had additions appended to them. The most notable alteration to these house types appeared to be an addition of a front porch.



Figure 16: GNAHRGIS ID No. 273426, Manufactured House Type, located at 154 North Lumpkin Street.

9.14 American Small House Type

The American Small House type is compact, nearly square though sometimes rectangular in plan, one story high, and usually gable roofed, simply and tightly massed. It contains at a minimum three major rooms and generally a maximum of five rooms. The American Small House type is typically two rooms across by two rooms deep. This house type was popular from the late 1930s to the early 1950s with most examples being constructed in the 1940s (The American Small House, nd).

The survey identified 41 American Small House type houses within the project area, or 18% of the 219 identified single family residences surveyed. The dates of construction range from the early 1930s to the late 1950s. These American Small House types appeared to be in good condition, but many had additions added to them which has disrupted their historic form and massing. Additionally, many had their exterior walls covered in vinyl siding.



Figure 17: GNAHRGIS ID No. 55105, American Small House Type, located at 225 North Dooley Street.

9.15 Ranch Type

The Ranch house type has a long, narrow, rectangular shape, with or without projections. The bedrooms are generally clustered on one end, the principal entry and living spaces near the center, and the garage or carport at the other end. The roof is typically very low pitched and is usually a gable or hipped design but can vary widely with butterfly, shed, or flat roof types. There are eight different subtypes of the Ranch house types and include the Compact, Linear, Linear with Clusters, Courtyard, Half Courtyard, Bungalow, Rambling, and Alphabet Ranch. The Ranch type was popular in rural and urban environments and were popular in Georgia starting in the 1930s. Most of the Ranch homes constructed in Georgia were built between 1940 and 1960 (Sullivan, Reed, and Fedor, 2010).

The survey identified 87 Ranch type houses within the project area, or 40% of the 219 identified single family residences surveyed. The dates of construction range from the late 1940s to the late 1970s. Of the 87 Ranch type houses identified, 51 were linear Ranch types, 30 were compact Ranch types, 4 were linear with clusters Ranch types, 1 was a rambling Ranch type, and 1 was a split-level Ranch type. These Ranch types appeared to be in good condition and retained a good degree of integrity. The most common alteration among these Ranch types was enclosing the integral carport or adding an extra room to the rear of the house. Additionally, several had their exterior walls covered in vinyl siding.



Figure 18: GNAHRGIS ID No. 268262, Ranch Type, located at 34 Knotty Pine Drive.

9.16 Split Level Type

The Split Level house type is a three level house with a main or ground level, one story high, a two story section with bedrooms and bathrooms half a flight up from the main level. A lower level is featured half a flight down from the main level and may feature a garage, additional bedrooms, a recreational room, and/or utility rooms. This house type was constructed in Georgia between the mid-1950s to the 1980s (House Types in Georgia, nd).

The survey identified one Split Level house type within the project area, or 1% of the 219 identified single family residences surveyed. The date of construction for this house type was 1972. This Ranch type appeared to be in good condition and retained a good degree of integrity. The most common alteration among these Ranch types was enclosing the integral carport or adding an extra room to the rear of the house. Additionally, several had their exterior walls covered in vinyl siding.



Figure 19: GNAHRGIS ID No. 273602, Split Level Type, located at 23 Carter Street.

9.17 Front Gable Church

The Front Gable church is the simplest and most common type of church in Georgia. This church type is a straightforward box with one or two doors in the front and three to five windows on the sides. They were popular in all periods statewide but especially in rural or small towns. Steeples or belfries are common additions appended to the original construction (Historic Church Types in Georgia, nd).

The survey identified four Front Gable type churches within the project area. The dates of construction range from the late 1930s to 1965. These Front Gable church types appeared to be in good condition and retained a good degree of integrity. The most common alteration among these Front Gable church types was additions made to the rear elevations. Additionally, some had their exterior walls covered in vinyl siding.



Figure 20: GNAHRGIS ID No. 269371, Front Gable church Type, located at 43 Henry Way.

9.18 Multifamily Dwelling

Based strictly on design, multifamily housing refers to a building that contains more than one dwelling unit. Multiple units can be stacked one on top of the other within the same building, or they can be side by side. One common way of differentiating multifamily products is according to their size and density. At one end of the spectrum are large single-family houses that have been subdivided into apartments. Such apartments were common early in the 20th century. At the other end of the spectrum are very-high-density high-rise apartment buildings, which may contain hundreds of units and sometimes even other uses, such as offices or stores. In between are low-rise multifamily buildings, commonly referred to as garden apartments. Housing units can include duplexes, garden apartments, condominiums, and apartments.

The survey identified 27 multifamily dwellings within the project area. The dates of construction range from the 1940s to the 1960s. Of the 27 multifamily dwellings, 10 are apartment buildings associated with the Sixth Street Federal Housing Apartments. The remaining multifamily dwellings were all duplexes. These multifamily dwellings ranged from poor condition to good condition and retained a fair degree of integrity. There did not appear to be many additions or alterations to these multifamily dwellings.



Figure 21: GNAHRGIS ID No. 271580, Multifamily Dwelling Type, located at 62 Sixth Street.

9.19 Community Recreation Center

A Community Recreation Center relates to a place, structure, area, or other facility under the jurisdiction of a governing body of a public authority used for community recreation whether or not it may be used primarily for other purposes, playgrounds, playing fields or courts, beaches, lakes, rivers, swimming pools, gymnasiums, auditoriums, libraries, parks adjacent to school sites, recreational community gardens, rooms for arts and crafts, camps, and meeting places (California, 2010).

The survey identified 1 Community Recreation Center within the project area. The date of construction is ca. 1950 and is associated with Sixth Street Federal Housing Apartments. The Community Recreation Center appeared to be in good condition and did appear to have had an addition appended to its southern end. The Community Recreation Center appeared to be vacant and not in use.



Figure 22: GNAHRGIS ID No. 271589, Community Recreation Center, located at 62 Sixth Street.

9.20 School Building/Equalization

In the decades after World War II, several states in the Deep South built new schools for African Americans in an attempt to maintain two racially segregated school systems. As it fiercely resisted racial integration, the state of Georgia built hundreds of black schools, more than any other state. The Georgia Department of Education established new statewide curricula for teachers and students and formed guidelines for architects and builders, who designed and constructed hundreds of International Style schools throughout Georgia. The state's campaign to modernize its schools, both black and white, resulted in some of the first modern schools constructed in rural communities across Georgia. The State School Building Authority adopted design standards for classrooms and other school facilities and it established requirements for types of construction, fire safety, lighting, and sanitation and included classrooms, library, cafeteria, administrative areas, and sanitary, storage and service facilities (Moffson, 2010 and Collins, 1954).

The survey identified 1 School Building/Equalization within the project area. The date of construction is ca. 1950. The School Building/Equalization appeared to be in good condition and did appear to have had an additional building built in close proximity and associated with it. The School Building/Equalization appeared to be vacant and not in use.



Figure 23: GNAHRGIS ID No. 271562, School Building/Equalization, located at 163 Lumpkin Street.

9.21 Clubhouse Type

A Clubhouse Type refers to any building that houses a civic or social club that is involved in volunteerism and/or fellowship. These buildings serve as meeting halls and, since each organization has its own unique principals, guidelines, and memberships, the buildings they are associated with can vary in style and type (Williams, 2006).

The survey identified 1 Clubhouse Type within the project area. The date of construction is ca. 1960. The Clubhouse Type appeared to be in poor condition and did not appear to have had any additions or alterations. The Clubhouse Type appeared to be vacant and not in use and tax assessor records show it is owned by local Masonic Lodge #646.



Figure 24: GNAHRGIS ID No. 271936, Clubhouse Type, located at 23 Dozier Street.

9.22 Storage Shed Type

A Storage Shed Type refers to any building that is used for storage but can also be used as a shelter or a workshop. It may be a separate building or a lean-to against another structure that may have one or more open sides. This building type is generally a secondary building and will, therefore, generally be associated with another building that serves as the primary building (Harris, 2006).

The survey identified 1 Storage Shed Type within the project area. The date of construction is ca. 1920. The Clubhouse Type appeared to be in poor condition and did not appear to have had any additions or alterations. The Storage Shed Type appeared to be vacant and not in use. Any buildings it was historically associated with have been razed.



Figure 25: GNAHRGIS ID No. 269406, Storage Shed Type, located on Anderson Lane.

9.23 Commercial Property Type

A Commercial Property Type refers to any building that is used for commercial purposes and can include retail store fronts, office buildings, and warehouses, among others. Different Commercial Property Types include the Community Store, Corner Store, Retail and Office, Single Retail, Multiple Retail, and Office Tower (Historic Commercial Types in Georgia, nd).

The survey identified 12 Commercial Property Types within the project area. The date of construction ranges from ca. 1950- 1977. The Commercial Property Types appeared to be in fair condition and did not appear to have had many additions or alterations.



Figure 26: GNAHRGIS ID No. 268143, Commercial Property Type, located at 132 Progress Avenue.

9.24 Cemetery

A Cemetery refers to any land or structure used or intended to be used for the interment of human remains. Internment can include earth burial, mausoleum entombment and niche or columbarium inurnment. Earth burials can be marked by a variety of monuments including headstones, pulpit markers, table tombs, footstones, in ground lawn markers, plaque markers, ledgers, pedestals, and obelisks. (Virginia, nd).

The survey identified 3 Cemeteries within the project area. The dates of construction range from ca. 1880- 1890. The Cemeteries appeared to be in good condition.




Figure 27: GNAHRGIS ID No. 268205, Orange Hill Cemetery, located on Sixth Avenue.

10.0 BUILDING STYLES

Building style refers to the decoration or ornamentation that has been used on a building in a systematic pattern or arrangement. Additionally, style also refers to the design of the overall form of a building and includes the proportion, scale, massing, symmetry or asymmetry, and the relationships among parts such as solids, voids or height, depth, and width. Floor plan, interior layout, and construction materials and techniques can also be used to define style (GA HPD, 1991).

Building types, not including Ranch or Split-Level types, that did not exhibit any academic style were identified as having no academic style. Ranch house and Split-Level type houses that did not exhibit any academic style were noted as plain style.

In total, there were 220 historic-age resources that were originally used as single-family residences. The academic styles present include Folk Victorian (7), Colonial Revival (1), Neo Classical Revival (1), and Craftsman (10). The survey also identified 102 that had no academic style, 91 that were plain style, and 6 that are unknown. The 6 buildings that were determined to be unknown could not be identified by building style due to vegetation, additions that obscure the original style elements, building decay, or a combination of the three.

The remaining 50 historic-age resources include multifamily residences, churches, commercial buildings, school, cemeteries, and civic buildings. The academic styles present include Modern Movement- Contemporary (1) and no academic style (153).

10.1 Table 2: List of Building Styles

Styles	Amount	Date Range
Folk Victorian	7	1890s-1910s
Colonial Revival	1	1971
Neoclassical Revival	1	1930
Craftsman	10	1890s-1950s
Modern Movement- Contemporary	1	1956
No Academic Style	153	~1890s-1980
Plain Style	91	~1940-1980
Unknown	6	~1924-1960s

10.2 Folk Victorian

Folk Victorian houses were simple house types with Victorian-era decorative detailing which was generally taken from more elaborate styles like Queen Anne or Italianate which were popular during the mid to late 1800s. Decorative details are added to the porch, in the gables, and around the window and door openings. The details include turned jigsawn woodwork such as brackets, spindlework, porch posts, other bric-a-brac, and gingerbread. It was popular in both rural and urban areas of Georgia from the 1870s to the 1910s (GA HPD, 1991).



Figure 28: GNAHRGIS ID No. 273596, Folk Victorian Style, located at 226 North Dooley Street.

10.3 Colonial Revival

The Colonial Revival style was an expression of renewed interest in colonial architecture which was itself inspired by English precedents. The Colonial Revival style was popular in Georgia from the 1890s through the 1940s and beyond. This style exhibits symmetric elements with a focus on the central entryway which is elaborated with a pediment supported by pilasters or columns. The use of broken pediments, fanlights and sidelights is common. Classical cornices with dentils or modillions are usually present and these features tend to be larger than the original colonial details. Windows used for this style feature double hung sashes and usually in six over six or nine over nine configuration and may be paired. Walls are composed of masonry, masonry veneer, or wood and the roof may be hipped or side gabled with dormers (GA HPD, 1991).



Figure 29: GNAHRGIS ID No. 268215, Colonial Revival Style, located at 22 Colson Street.

10.4 Neoclassical Revival

The Neoclassical Revival style was very popular in the state of Georgia and grew out of a renewed interest in classically inspired architecture and a reaction against the Victorian styles. This style is noted as drawing inspiration from the Early Classical Revival and Greek Revival styles of the early 1800s and would often combine elements and features of Greek and Roman inspiration. Sometimes the Georgian and Federal styles were used as sources as well. The Neoclassical Revival style was used in Georgia's rural areas, cities, and small towns from the 1890s through the 1930s. The most common feature of the Neoclassical Revival style is the use of a dominant full height front portico with classical columns. The front portico may be at the entryway or may cover the entire façade. The portico may have a triangular pediment or be part of the overall roof. A full height entry portico is often coupled with a one-story full façade porch. The façade is usually symmetrical, and the central entrance is surrounded with pilasters and columns and elaborated with fanlights, sidelights, and transoms. There is almost always a classical cornice with dentils or modillions. The roof is usually hipped and may have a balustrade. A porte cochere and side porches supported by columns are also common (GA HPD, 1991).



Figure 30: GNAHRGIS ID No. 273617, Neoclassical Revival Style, located at 223 North Dooley Street.

10.5 Craftsman

The Craftsman style is American in origin and the most popular style in the 20th century. This style was created and popularized in California and spread throughout the country via pattern books and magazines. The Craftsman style was a break from the revival styles and characterized a movement towards modern architecture. This style was influenced by the English Arts and Crafts movement as well as Japanese architecture practices. The Craftsman style was utilized in houses in rural, small town, and city settings from the 1910s through the 1930s. The Craftsman style uses a wide variety of materials both for structural and aesthetic purposes. The low pitched roof is usually gabled or hipped which gives the style a generally horizontal look and the widely overhanging eaves are open with exposed rafters. The large gables have decorative brackets or braces at the eaves and may be covered with half timbering. Roof dormers can be found in some examples. The exterior walls are most often wood but may be covered with shingles or a masonry veneer of stone or brick. The porches on Craftsman style buildings have short square columns set on heavy masonry piers extending to the ground. Craftsman style houses are most often asymmetrical with a generally open and functional plan and the style is most often associated with the Bungalow house type (GA HPD, 1991).



Figure 31: GNAHRGIS ID No. 55177, Craftsman Style, located at 68 Progress Avenue.

10.6 Modern Movement- Contemporary

The Modern Movement- Contemporary style is characterized by a low pitched and sometimes flat roof with widely overhanging eaves. The roof beams are commonly exposed, and windows are generally present in the gable ends. The exterior walls are typically composed of natural materials like wood, brick, stone, or concrete block. The layout is typically asymmetrical and the entryway may be recessed or obscured (McAlester, 2013).



Figure 32: GNAHRGIS ID No. 273642, Modern Movement- Contemporary Style, located at 64 Progress Avenue.

11.0 BIBLIOGRAPHY

"The American Small House," Georgia Historic Preservation Division. <https://georgiashpo.org/sites/default/files/hpd/pdf/AmericanSmallHouse.pdf>. Accessed July 24, 2020.

"Battle Unit Details." National Parks Service, U.S. Department of the Interior, www.nps.gov/civilwar/search-battle-units-detail.htm?battleUnitCode=CGA0049RI. Accessed September 21, 2020.

California, 2010 California Code Education Code. 2010.

"Design Guidelines: Hawkinsville Downtown Historic District," City of Hawkinsville. <https://hawkinsville-pulaski.org/wp-content/uploads/2016/06/Downtown-Design-Guidelines.pdf>. Accessed July 25, 2020.

Georgia Department of Education, Collins, M. D. *Eighty-Second and Eighty-Third Annual Reports of the Department of Education of the General Assembly to the State of Georgia*, State Department of Education, 1954.

Georgia Department of Natural Resources. Historic Preservation Division. *Georgia's Living Places: Historic Houses in Their Landscaped Settings*. 1991. www.gashpo.org. Accessed June 3, 2020.

Georgia Department of Natural Resources. Historic Preservation Division. *Historic Church Types in Georgia*. 2004. www.gashpo.org. Accessed June 3, 2020.

Georgia Department of Natural Resources. Historic Preservation Division. *Historic Church Types in Georgia*. 2004. www.gashpo.org. Accessed June 3, 2020.

Georgia Department of Natural Resources. Historic Preservation Division. *House Types in Georgia*. 2004. www.gashpo.org. Accessed June 3, 2020.

"Georgia Historic Resources Survey Manual," Atlanta: Georgia Department of Natural Resources, Historic Preservation Division, 2019

Gibbs, Phillip A., and Tracie L. Provost. *Hawkinsville*. Arcadia Pub., 2008.

Harris, Cyril M. *Dictionary of Architecture and Construction*. McGraw-Hill, 2006.

Hawkinsville-Pulaski County. "Economic Development." Accessed June 1, 2020. <https://www.hawkinsvillega.gov/workforce.php>.

Historic Resources Survey Report

City of Hawkinsville ■ Pulaski County, GA

September 25, 2020 ■ Terracon Project No. 49197855



Hawkinsville-Pulaski County. "History." Accessed June 1, 2020. <https://hawkinsville-pulaski.org/visitors/history/#:~:text=Pulaski%20County%20was%20created%20in,of%20the%20Creek%20Indian%20Confederacy>.

"Heart of Georgia Peanut and Gin Co - Company Profile and News." Bloomberg.com. www.bloomberg.com/profile/company/0375324D:US. Accessed September 22, 2020.

McAlester, Virginia. *A Field Guide to American Houses*. New York: Alfred A. Knopf, 2013.

Moffson, Steven. *Equalization Schools in Georgia's African-American Communities, 1951-1970*, Atlanta: Georgia Department of Natural Resources, Historic Preservation Division, 2010.

National Parks Service. "Muscogee (Creek) Removal." Accessed July 28, 2020 <https://www.nps.gov/ocmu/learn/historyculture/index.htm>.

Remier, Nancy Lawson. "Hawkinsville." Accessed June 1, 2020. <https://www.georgiaencyclopedia.org/articles/counties-cities-neighborhoods/hawkinsville>.

Remier, Nancy Lawson. "Pulaski County." Accessed June 1, 2020. <https://www.georgiaencyclopedia.org/articles/counties-cities-neighborhoods/pulaski-county>.

"Residential Architectural Styles in Georgia", *Georgia's Living Places: Historic Houses in Their Landscaped Settings*, Atlanta: Georgia Department of Natural Resources, Historic Preservation Division, 1991.

"Search For Soldiers." National Parks Service, U.S. Department of the Interior, www.nps.gov/civilwar/search-soldiers.htm. Accessed September 22, 2020.

Schmitz, Adrienne. *Multifamily Housing Development Handbook*. Urban Land Institute, 2000.

Sullivan, Patrick, Mary Beth Reed, and Tracey Fedor. *Guidelines for Evaluation: The Ranch House in Georgia*. Stone Mountain Georgia: New South Associates, 2010.

Virginia, Professions and Occupations, § 54.1-2310. Definitions.

Williams, Wiley J. "Civic Clubs," *Encyclopedia of North Carolina*. <https://www.ncpedia.org/civic-clubs>. Accessed September 22, 2020.

APPENDIX A: SURVEY TABLE

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
1	268139	N/A	N/A		32.29046626142228, -83.47791326074656	114 Progress Ave.	Appears not to meet	1977	Commercial-Department-General Store	Commercial-Department-General Store	No Academic Style	Commercial Building Type- Single Retail (one story)	N/A
2	268143	N/A	N/A		32.291374301579246, -83.47895679139916	132 Progress Ave.	Appears not to meet	1960	Commercial-Department-General Store	Commercial-Department-General Store	No Academic Style	Commercial Building Type- Single Retail (one story)	N/A
3	268144	N/A	N/A		32.291733504165265, -83.47822818719783	15 6th St.	Appears not to meet	1950	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
4	268152	N/A	N/A		32.29117186140914, -83.47790808909781	12 6th St.	Appears not to meet	1970	Unknown	Commercial storage-warehouse	No Academic Style	Commercial building-warehouse	N/A
5	268159	N/A	N/A		32.291886757368914, -83.47663005204994	29 6th St.	May meet	1973	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear with Clusters
6	268164	N/A	N/A		32.29380489980157, -83.47698843435721	28 Fairway Dr.	Appears not to meet	1973	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
7	268189	N/A	N/A		32.29252552027425, -83.47644412822301	12 Fairway Dr.	Appears not to meet	1978	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
8	268199	N/A	N/A		32.29226122609774, -83.47631870323373	6 Fairway Dr.ive	Appears not to meet	1978	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
9	268200	N/A	N/A		32.29185548341193, -83.47617172883471	35 6th St	Appears not to meet	1976	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
10	268201	N/A	N/A		32.292233151187745, -83.4759785873752	9 Knotty Pine Dr.	Appears not to meet	1973	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
11	268203	N/A	N/A		32.292451964309635, -83.47605312948218	11 Knotty Pine Dr.	Appears not to meet	1974	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
12	268211	N/A	N/A		32.29268045606051, -83.47615612462084	15 Knotty Pine Dr.	Appears not to meet	1971	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
13	268222	N/A	N/A		32.29296570805426, -83.47624603358383	19 Knotty Pine Dr.	Appears not to meet	1972	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
14	268224	N/A	N/A		32.29319036141584, -83.4763478047478	21 Knotty Pine Dr.	Appears not to meet	1971	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
15	268225	N/A	N/A		32.2934320687916, -83.47645044032981	25 Knotty Pine Dr.	Appears not to meet	1972	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
16	268227	N/A	N/A		32.29362538241586, -83.47651568688748	29 Knotty Pine Dr.	Appears not to meet	1975	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
17	268237	N/A	N/A		32.29380023327954, -83.47660698695682	31 Knotty Pine Dr.	Appears not to meet	1974	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
18	268239	N/A	N/A		32.29400936223534, -83.47668894032975	35 Knotty Pine Dr.	Appears not to meet	1973	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
19	268244	N/A	N/A		32.29460939352812, -83.4769880038936	43 Knotty Pine Dr.	Appears not to meet	1972	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear with Clusters
20	268245	N/A	N/A		32.29508762086139, -83.47659258739206	15 Pineywood Dr.	Appears not to meet	1979	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
21	268247	N/A	N/A		32.29508167473121, -83.47630786940854	19 Pineywood Dr.	Appears not to meet	1979	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
22	268252	N/A	N/A		32.29503016256818, -83.47565991519987	27 Pineywood Dr.	Appears not to meet	1978	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
23	268256	N/A	N/A		32.29500464359948, -83.47484201844051	35 Pineywood Dr.	Appears not to meet	1979	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear with Clusters
24	268257	N/A	N/A		32.29446180871942, -83.47360049256949	52 Pineywood Dr.	Appears not to meet	~1970	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Manufactured House	N/A
25	268258	N/A	N/A		32.294604872468376, -83.47515798863778	34 Pineywood Dr.	Appears not to meet	1979	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
26	268259	N/A	N/A		32.29458916038874, -83.47585750374945	24 Pineywood Dr.	Appears not to meet	1980	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
27	268260	N/A	N/A		32.29468143512459, -83.47615239800193	22 Pineywood Dr.	Appears not to meet	1977	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
28	268261	N/A	N/A		32.294558972631734, -83.47647766906731	42 Knotty Pine Dr.	Appears not to meet	1972	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
29	268262	N/A	N/A		32.294043699321655, -83.47629124340561	34 Knotty Pine Dr.	May meet	1971	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear with Clusters

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
30	268263	N/A	N/A		32.29355856197648, -83.4761064400413	28 Knotty Pine Dr.	Appears not to meet	1972	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
31	268264	N/A	N/A		32.29338202626768, -83.47603197224173	24 Knotty Pine Dr.	Appears not to meet	1971	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
32	268265	N/A	N/A		32.29317609664604, -83.4759524866684	20 Knotty Pine Dr.	Appears not to meet	1971	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
33	268266	N/A	N/A		32.29300046611999, -83.4758700822885	18 Knotty Pine Dr.	Appears not to meet	1971	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
34	268267	N/A	N/A		32.29278229460764, -83.47576883513058	14 Knotty Pine Dr.	Appears not to meet	1970	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
35	268270	N/A	N/A		32.2925963946597, -83.4757073587629	12 Knotty Pine Dr.	Appears not to meet	1970	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
36	268274	N/A	N/A		32.292398387976625, -83.47563488314258	10 Knotty Pine Dr.	Appears not to meet	1970	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
37	268277	N/A	N/A		32.292243636619965, -83.47556154717405	6 Knotty Pine Dr.	Appears not to meet	1969	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
38	268282	N/A	N/A		32.292071423483044, -83.4755047643032	4 Knotty Pine Dr.	Appears not to meet	1971	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
39	268284	N/A	N/A		32.29187183651972, -83.47541594434053	2 Knotty Pine Dr.	Appears not to meet	1973	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
40	268205	N/A	N/A	Orange Hill Cemetery	32.29248053794688, -83.47114207635785	Sixth St.	Appears not to meet	~1880	Cemetery	Cemetery	N/A	N/A	N/A
41	268206	N/A	N/A	Pine Bloom Cemetery	32.29248053794688, -83.46738698373689	Sixth St.	Appears not to meet	~1880	Cemetery	Cemetery	N/A	N/A	N/A
42	268207	N/A	N/A		32.291804793998836, -83.46803373772147	132 6th St.	Appears not to meet	1972	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Manufactured House	N/A
43	268209	N/A	N/A		32.29178022645228, -83.46847497945497	126 6th St.	Appears not to meet	1972	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Manufactured House	N/A
44	268212	N/A	N/A		32.29030999506615, -83.47687006702486	20 Colson St.	Appears not to meet	1971	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
45	268215	N/A	N/A		32.29011800907047, -83.47669037038924	22 Colson St.	Appears not to meet	1971	Domestic residential- single family residence	Domestic residential- single family residence	Colonial Revival	Ranch	Linear
46	268223	N/A	N/A		32.28980909371023, -83.47635015596312	28 Colson St.	Appears not to meet	1971	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
47	268226	N/A	N/A		32.289633909701536, -83.47621783957385	32 Colson St.	Appears not to meet	~1955	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
48	268228	N/A	N/A		32.28952727216449, -83.47604324049136	34 Colson St.	Appears not to meet	1975	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
49	268229	N/A	N/A		32.28934271360067, -83.4762285308139	7 Highland Ave.	Appears not to meet	1976	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
50	268230	N/A	N/A		32.28933336103813, -83.47688477185505	96 Progress Ave.	Appears not to meet	1945	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
51	268231	N/A	N/A		32.289510121794976, -83.47709724741638	98 Progress Ave.	Appears not to meet	1974	Domestic residential- single family residence	Commerce and Trade- business/ office	Plain	Ranch	Linear

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
52	55179	443	267	Maugin Thompson House/ Angel Heights Funeral Services	32.289751907814, -83.477386766141	104 Progress Ave.	Appears to meet	1920	Domestic residential- single family residence	Commerce and Trade- business/ office	No Academic Style	Unable to determine house type	N/A
53	268248	N/A	N/A		32.290094945731745, -83.47590386754437	29 Colson St.	Appears not to meet	1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
54	268287	N/A	N/A		32.289760457105025, -83.47571834478758	15 Highland Ave.	Appears not to meet	1975	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
55	268289	N/A	N/A		32.28991432315473, -83.4755518483571	19 Highland Ave.	Appears not to meet	1969	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
56	268290	N/A	N/A		32.29038521528195, -83.47560633844869	23 Highland Ave.	Appears not to meet	1958	Domestic residential- single family residence	Vacant/not in use	Plain	Ranch	Linear
57	268294	N/A	N/A		32.29074601357145, -83.47522060894877	35 Highland Ave.	May meet	1958	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
58	268295	N/A	N/A		32.29105794036327, -83.47526060658278	39 Highland Ave.	Appears not to meet	1958	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
59	268298	N/A	N/A		32.2912556621101, -83.4752350628699	41 Highland Ave.	Appears not to meet	1962	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
60	268301	N/A	N/A		32.29143870266958, -83.4751789892296	44A Sixth St.	Appears not to meet	1969	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
61	268308	N/A	N/A		32.29146012331667, -83.4754048871809	44B Sixth St.	Appears not to meet	1964	Domestic residential- single family residence	Domestic residential- multiple dwelling	No Academic Style	Duplex	N/A
62	268312	N/A	N/A		32.291469063997475, -83.47466798987107	54 Sixth St.	Appears not to meet	1972	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
63	268316	N/A	N/A		32.29126664863401, -83.47472392080537	42 Highland Ave.	Appears not to meet	1960	Domestic residential- single family residence	Vacant/not in use	Plain	Ranch	Linear
64	268318	N/A	N/A		32.29112255987505, -83.47470796127742	40 Highland Ave.	Appears not to meet	~1955	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
65	268322	N/A	N/A		32.290985694602306, -83.4747168934144	38 Highland Ave.	Appears not to meet	1958	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
66	268323	N/A	N/A		32.29072200961668, -83.47469984678729	34 Highland Ave.	Appears not to meet	1958	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
67	268325	N/A	N/A		32.29057717796671, -83.47467841020708	32 Highland Ave.	Appears not to meet	1958	Domestic residential- single family residence	Domestic residential- single family residence	Plain	American Small House	N/A
68	268326	N/A	N/A		32.29033822383561, -83.47464044018562	28 Highland Ave.	Appears not to meet	1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
69	268328	N/A	N/A		32.29002898827293, -83.47492839396251	24 Highland Ave.	Appears not to meet	1955	Domestic residential- single family residence	Domestic residential- single family residence	Plain	American Small House	N/A
70	268332	N/A	N/A		32.28987600389237, -83.47506095239066	22 Highland Ave.	Appears not to meet	1951	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
71	268333	N/A	N/A	6th St. Federal Housing Apartments	32.29147206511278, -83.473590858066	62 Sixth St.	Appears not to meet	~1950	Domestic residential- housing associated with public housing	Domestic residential- housing associated with public housing	No Academic Style	Apartment Complex	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
72	271580	N/A	N/A	6th St. Federal Housing Apartments	32.291263386146206, -83.47377324828174	62 Sixth St.	Appears not to meet	~1950	Domestic residential-housing associated with public housing	Domestic residential-housing associated with public housing	No Academic Style	Apartment Complex	N/A
73	271581	N/A	N/A	6th St. Federal Housing Apartments	32.29101850797333, -83.47365523108509	62 Sixth St.	Appears not to meet	~1950	Domestic residential-housing associated with public housing	Domestic residential-housing associated with public housing	No Academic Style	Apartment Complex	N/A
74	271582	N/A	N/A	6th St. Federal Housing Apartments	32.290587741956166, -83.47377861269837	62 Sixth St.	Appears not to meet	~1950	Domestic residential-housing associated with public housing	Domestic residential-housing associated with public housing	No Academic Style	Apartment Complex	N/A
75	271583	N/A	N/A	6th St. Federal Housing Apartments	32.290791768334635, -83.47364986666707	62 Sixth St.	Appears not to meet	~1950	Domestic residential-housing associated with public housing	Domestic residential-housing associated with public housing	No Academic Style	Apartment Complex	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
76	271584	N/A	N/A	6th St. Federal Housing Apartments	32.290578632557214, -83.47410584219963	62 Sixth St.	Appears not to meet	~1950	Domestic residential-housing associated with public housing	Domestic residential-housing associated with public housing	No Academic Style	Apartment Complex	N/A
77	271585	N/A	N/A	6th St. Federal Housing Apartments	32.29080990752658, -83.4742292238143	62 Sixth St.	Appears not to meet	~1950	Domestic residential-housing associated with public housing	Domestic residential-housing associated with public housing	No Academic Style	Apartment Complex	N/A
78	271586	N/A	N/A	6th St. Federal Housing Apartments	32.29103211233356, -83.4742345882323	62 Sixth St.	Appears not to meet	~1950	Domestic residential-housing associated with public housing	Domestic residential-housing associated with public housing	No Academic Style	Apartment Complex	N/A
79	271587	N/A	N/A	6th St. Federal Housing Apartments	32.29125431659606, -83.4741004777816	62 Sixth St.	Appears not to meet	~1950	Domestic residential-housing associated with public housing	Domestic residential-housing associated with public housing	No Academic Style	Apartment Complex	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
80	271588	N/A	N/A	6th St. Federal Housing Apartments	32.291476520313836, -83.47421849497823	62 Sixth St.	Appears not to meet	~1950	Domestic residential-housing associated with public housing	Domestic residential-housing associated with public housing	No Academic Style	Apartment Complex	N/A
81	271589	N/A	N/A		32.29028840431, -83.47411120661764	62 Sixth St.	Appears not to meet	~1950	Recreation, Culture, Entertainment	Vacant/not in use	No Academic Style	Community Recreation Center	N/A
82	269339	N/A	N/A		32.29144153720964, -83.47318485039266	7 Poplar St.	Appears not to meet	1967	Domestic residential-multi family residence	Vacant/not in use	No Academic Style	Duplex	N/A
83	271590	N/A	N/A		32.29128051309452, -83.47317680376688	9 Poplar St.	Appears not to meet	1967	Domestic residential-multi family residence	Vacant/not in use	No Academic Style	Duplex	N/A
84	271593	N/A	N/A		32.29109758051428, -83.47316778267513	13 Poplar St.	Appears not to meet	1967	Domestic residential-multi family residence	Vacant/not in use	No Academic Style	Duplex	N/A
85	271594	N/A	N/A		32.2909762545208, -83.47315437163005	15 Poplar St.	Appears not to meet	1967	Domestic residential-multi family residence	Vacant/not in use	No Academic Style	Duplex	N/A
86	271595	N/A	N/A		32.29085773080309, -83.47315705383905	17 Poplar St.	Appears not to meet	1967	Domestic residential-multi family residence	Vacant/not in use	No Academic Style	Duplex	N/A
87	271596	N/A	N/A		32.29073420700881, -83.47316040660034	19 Poplar St.	Appears not to meet	1967	Domestic residential-multi family residence	Vacant/not in use	No Academic Style	Duplex	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
88	271597	N/A	N/A		32.290618710848236, -83.4731635917235	21 Poplar St.	Appears not to meet	1965	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Duplex	N/A
89	271598	N/A	N/A		32.290477495123085, -83.47316208298086	23 Poplar St.	Appears not to meet	1965	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Duplex	N/A
90	271599	N/A	N/A		32.290335214495975, -83.47314755218217	25 Poplar St.	Appears not to meet	~1965	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Duplex	N/A
91	269353	N/A	N/A		32.28911921101739, -83.47488971654279	19 MLK Blvd.	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
92	269355	N/A	N/A		32.28963739225781, -83.4742507260647	3 James St.	Appears not to meet	1967	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
93	269356	N/A	N/A		32.289807200428776, -83.47414804775084	4 James St.	Appears not to meet	1967	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Manufactured House	N/A
94	269357	N/A	N/A		32.28976994586199, -83.4744652121862	5 James St.	Appears not to meet	~1970	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Manufactured House	N/A
95	269358	N/A	N/A		32.28992892827627, -83.47433403869117	6 James St.	Appears not to meet	1967	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
96	269360	N/A	N/A		32.289149659133685, -83.47431575936157	37 Poplar St.	Appears not to meet	1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
97	269361	N/A	N/A		32.29106550985668, -83.47289399815226	71 Henry Way	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unable to Determine/ Possible Saddlebag	N/A
98	269362	N/A	N/A		32.29004720842054, -83.47286596171001	57 Henry Way	Appears to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Shotgun	N/A
99	269364	N/A	N/A		32.28990849452692, -83.47288741938226	55 Henry Way	Appears not to meet	1950	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
100	269365	N/A	N/A		32.289438539777706, -83.47286836164659	49 Henry Way	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	Craftsman	Bungalow	Front Gable
101	269368	N/A	N/A		32.289259394479096, -83.4728988404106	45 Henry Way	Appears not to meet	1970	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
102	269371	N/A	N/A	Mt. Pleasant Baptist Church	32.289025115283046, -83.47296492117121	43 Henry Way	Appears not to meet	~1950	Religion- Religious Facility	Religion- religious facility	No Academic Style	Front Gable Church	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
103	269376	N/A	N/A		32.28937350200578, -83.47254853260294	48 Henry Way	Appears not to meet	1962	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
104	269381	N/A	N/A		32.28997663762737, -83.47258608352922	56 Henry Way	May meet	~1915	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Gabled Wing Cottage	T-plan
105	269386	N/A	N/A		32.29051049318614, -83.47259625405279	64 Henry Way	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	Craftsman	Side Gabled Cottage	N/A
106	269399	N/A	N/A		32.2910349000544, -83.47256408644337	70 Henry Way	Appears not to meet	1961	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Manufactured House	N/A
107	269400	N/A	N/A		32.29118598050842, -83.47250507784507	72 Henry Way	Appears not to meet	~1930	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Bungalow	Unknown- possibly hipped
108	269401	N/A	N/A		32.291296039252366, -83.47252653551723	74 Henry Way	Appears not to meet	~1930	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Bungalow	Gable-Front Oriented
109	269402	N/A	N/A		32.291190353359866, -83.47207985636646	6 Anderson Lane	Appears not to meet	1966	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Manufactured House	N/A
110	269403	N/A	N/A		32.29103950987847, -83.47208136449527	8 Anderson Lane	Appears not to meet	~1955	Domestic residential- single family residence	Vacant/not in use	Plain	American Small House	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
111	269404	N/A	N/A		32.291081484228386, -83.47171915840423	11 Anderson Lane	Appears not to meet	1967	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Manufactured House	N/A
112	269405	N/A	N/A		32.29134668030053, -83.47162821134954	5 Anderson Lane	May meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
113	269406	N/A	N/A		32.291478188555196, -83.47184010586172	Anderson Lane	Appears not to meet	~1920	Domestic residential- secondary structure	Vacant/not in use	No Academic Style	Other Building Type (Storage Shed)	N/A
114	269407	N/A	N/A		32.291651887714316, -83.4716697485415	88A and 88B Sixth St.	Appears not to meet	1961	Domestic residential- single family residence	Domestic residential- multiple dwelling	No Academic Style	Duplex	N/A
115	269408	N/A	N/A		32.291549127701735, -83.47134961503689	277 N. Dooley St.	Appears not to meet	1963	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
116	269409	N/A	N/A		32.291292801404026, -83.471384415891	273 N. Dooley St.	Appears not to meet	1963	Domestic residential- single family residence	Vacant/not in use	Plain	Ranch	Linear
117	269411	N/A	N/A		32.29108665677726, -83.47127424631968	271 N. Dooley St.	Appears to meet	~1920	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Shotgun	N/A
118	269412	N/A	N/A		32.290958035590535, -83.47124075979424	269 N. Dooley St.	Appears to meet	~1930	Domestic residential- single family residence	Vacant/not in use	Craftsman	Bungalow	Gable- Side Oriented

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
119	55108	371	259		32.29062202936799, -83.4712356646036	265 N. Dooley St.	May meet	~1902	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Central Hallway	N/A
120	269421	N/A	N/A		32.28997822776262, -83.47200973688477	8 Fifth St.	Appears not to meet	1948	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Rambling
121	271421	N/A	N/A		32.2901156046052, -83.47160859616226	14 Fifth St.	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unable to determine house type/ Possible American Small House	N/A
122	271425	N/A	N/A		32.29008785573424, -83.47148088536414	16 Fifth St.	Appears not to meet	1963	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
123	271426	N/A	N/A		32.2901480798611, -83.47119293213548	18 Fifth St.	Appears not to meet	1971	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
124	55107	370	N/A		32.29004755206863, -83.47118802764224	257 N. Dooley St.	Appears not to meet	~1945	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unable to determine house type/ Possible American Small House	N/A
125	55106	369	369		32.289800354565614, -83.47114725210496	253 N. Dooley St.	Appears not to meet	~1904	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	New South Cottage	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
126	271435	N/A	N/A		32.28964465872397, -83.47112616027906	251 N. Dooley St.	Appears not to meet	1972	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
127	55157	421	263		32.28917045118719, -83.47105380391243	65 MLK Blvd.	May meet	~1915	Domestic residential- single family residence	Domestic residential- single family residence	Folk Victorian	Central Hallway	N/A
128	55156	419	265		32.289067965367266, -83.47127890689134	63 MLK Blvd.	Appears not to meet	~1914	Domestic residential- single family residence	Vacant/not in use	Folk Victorian	New South Cottage	N/A
129	271441	N/A	N/A		32.2890054646238, -83.47203957077588	53A MLK Blvd.	Appears not to meet	~1955	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
130	271443	N/A	N/A		32.289209534344614, -83.47205566402995	53B MLK Blvd.	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
131	55151	415	N/A		32.28904845112769, -83.47389206621965	33 MLK Blvd.	Appears not to meet	~1904	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unable to determine house type/ Possible New South Cottage	N/A
132	271591	N/A	N/A		32.28897703209806, -83.4740566187879	29 MLK Blvd.	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
133	271624	N/A	N/A	North Dooley St. Cemetery	32.29107376391295, -83.47060999731153	101 Sixth St.	Appears not to meet	~1890	Cemetery	Cemetery	N/A	N/A	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
134	271646	N/A	N/A		32.289711095690414, -83.47066026694999	252 N. Dooley St.	Appears not to meet	1968	Domestic residential- single family residence	Vacant/not in use	Plain	Ranch	Linear
135	55113	376	261		32.28953229698598, -83.47066829282694	250 N. Dooley St.	Appears not to meet	~1914	Domestic residential- single family residence	Domestic residential- single family residence	Craftsman	Unable to determine house type	N/A
136	271592	N/A	N/A		32.28911655660507, -83.47045824313744	73 MLK Blvd.	Appears not to meet	1969	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
137	271430	N/A	N/A		32.2891206335829, -83.47030336610355	75 MLK Blvd.	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Central Hallway	N/A
138	271562	N/A	N/A	Lumpkin St. School	32.29064415990865, -83.46979461653424	163 N. Lumpkin St.	Appears to meet	~1950	Public School	Vacant/not in use	No Academic Style	School Building/ Equalization	N/A
139	271672	N/A	N/A		32.29136147829942, -83.46971781600053	171 N. Lumpkin St.	Appears to meet	1970	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
140	271712	N/A	N/A		32.29154176880148, -83.46968001953586	173 N. Lumpkin St.	Appears to meet	1965	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
141	271716	N/A	N/A		32.29168834368116, -83.4696691969227	175 N. Lumpkin St.	Appears to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
142	55089	352	N/A		32.291662682806376, -83.46923066004112	174 N. Lumpkin St.	Appears to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A
143	55088	351	N/A		32.291567435914246, -83.46923161089919	172 N. Lumpkin St.	Appears to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A
144	55087	350	N/A		32.29137365461192, -83.4692239238649	170 N. Lumpkin St.	Appears to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A
145	55086	349	N/A		32.29123684286749, -83.4691963159924	168 N. Lumpkin St.	Appears to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A
146	55085	348	N/A		32.29108037982288, -83.46919190312344	166 N. Lumpkin St.	Appears to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A
147	271904	N/A	N/A		32.29084312892536, -83.46916086459423	164 N. Lumpkin St.	May meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A
148	271905	N/A	N/A		32.2906848342881, -83.46914477134023	162 N. Lumpkin St.	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
149	271906	N/A	N/A		32.29095865618312, -83.46885611554052	35 Railroad St.	Appears not to meet	1963	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
150	271907	N/A	N/A		32.29111187168696, -83.46887144073378	39 Railroad St.	Appears not to meet	1967	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unknown possibly a Ranch	Compact
151	271909	N/A	N/A		32.2911209429934, -83.46870187483258	37 Railroad St.	Appears not to meet	~1980	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Manufactured House	N/A
152	271912	N/A	N/A		32.291439900674554, -83.46845068789179	42 Railroad St.	Appears not to meet	~1965	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unknown	N/A
153	271917	N/A	N/A		32.291283728232216, -83.4684309590557	40 Railroad St.	Appears not to meet	1967	Domestic residential- multi family residence	Vacant/not in use	No Academic Style	Duplex	N/A
154	271922	N/A	N/A		32.29068780476251, -83.46844139719394	11 Harris St.	Appears not to meet	1965	Commerce and trade- storage	Commerce and trade- storage	No Academic Style	Commercial Warehouse	N/A
155	271931	N/A	N/A		32.29073931984338, -83.46816221339701	15 Harris St.	Appears not to meet	~1950	Commerce and trade- specialty store/shop	Commerce and trade- specialty store/shop	No Academic Style	Road related building types- sales and service	N/A
156	271932	N/A	N/A		32.29073034592401, -83.46796198459077	17 Harris St.	Appears not to meet	~1965	Domestic residential- single family residence	Vacant/not in use	Plain	Ranch	Linear

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
157	271936	N/A	N/A		32.29088298976749, -83.46793289938688	23 Dozier St.	Appears not to meet	~1960	Social and Civic-Meeting Hall	Vacant/not in use	Plain	Clubhouse type/ other social/civic clubhouse type	N/A
158	271964	N/A	N/A		32.288386239314114, -83.4689296054578	128 N. Lumpkin St.	Appears not to meet	~1930	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Unknown- possible Saddlebag	N/A
159	272036	N/A	N/A		32.28864654102504, -83.46881217499437	132 N. Lumpkin St.	Appears not to meet	~1970	Commerce and trade- storage	Vacant/not in use	No Academic Style	Commercial Building Type- Warehouse	N/A
160	272038	N/A	N/A		32.28880646829962, -83.46887326311246	90 MLK Blvd.	Appears not to meet	~1970	Commerce and trade- storage	Vacant/not in use	No Academic Style	Commercial Building Type- Warehouse	N/A
161	272040	N/A	N/A		32.28877680377652, -83.46854035206746	96 MLK Blvd.	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Central Hallway	N/A
162	272043	N/A	N/A		32.288517271492864, -83.46843479544226	1 Railroad St.	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unknown- possible Central Hallway	N/A
163	272045	N/A	N/A		32.28853087622843, -83.46818803221288	0 Railroad St.	Appears not to meet	~1930	Domestic residential- single family residence	Vacant/not in use	Unknown	Unknown	N/A
164	272047	N/A	N/A		32.28853087622843, -83.46818803221288	100 MLK Blvd.	Appears not to meet	1950	Domestic residential- single family residence	Vacant/not in use	Plain	Ranch	Linear
165	272049	N/A	N/A		32.28929752439, -83.46795829141756	103 MLK Blvd.	Appears not to meet	1962	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unknown- possible Ranch	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
166	272051	N/A	N/A		32.289315095795196, -83.46776223442438	105 MLK Blvd.	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unknown	N/A
167	272052	N/A	N/A		32.28957451542387, -83.46783520051751	5 Dozier St.	Appears not to meet	1960	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
168	272053	N/A	N/A		32.28971341381554, -83.46785756226609	7 Dozier St.	Appears not to meet	~1955	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
169	272057	N/A	N/A		32.28975898132661, -83.46739046514392	8 Dozier St.	Appears to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A
170	272058	N/A	N/A		32.28992977232094, -83.46743260502504	10 Dozier St.	Appears not to meet	~1960	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
171	272060	N/A	N/A		32.29029409840073, -83.46747280111258	16 Dozier St.	More info needed	~1955	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
172	272062	N/A	N/A		32.29013510723763, -83.46860990263733	23 Railroad St.	Appears to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Side Gabled Cottage	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
173	272089	N/A	N/A		32.29000669660308, -83.46860558840518	21 Railroad St.	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A
174	272091	N/A	N/A		32.28985592495278, -83.46859353442065	19 Railroad St.	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A
175	272093	N/A	N/A		32.289387219464096, -83.46849910267949	13 Railroad St.	Appears not to meet	~1920	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Shotgun	N/A
176	273422	N/A	N/A		32.28924449894232, -83.46849510574613	97 MLK Jr. Blvd	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unknown	N/A
177	273424	N/A	N/A		32.28924233271875, -83.46898175804665	140 N. Lumpkin St.	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Side Gabled Cottage	N/A
178	273425	N/A	N/A		32.28986390975167, -83.46900280460365	150 N. Lumpkin St.	Appears not to meet	1974	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
179	273426	N/A	N/A		32.29008115869729, -83.46905673160319	154 N. Lumpkin St.	Appears not to meet	~1970	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Manufactured House	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
180	273427	N/A	N/A		32.29027249706119, -83.46905715583566	4 Harris St.	Appears not to meet	1973	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Unknown-possible Ranch	N/A
181	273428	N/A	N/A		32.29030113819767, -83.46882035628019	6 Harris St.	Appears not to meet	~1960	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unknown	N/A
182	273431	N/A	N/A		32.290321870662595, -83.46864334578662	8 Harris St.	Appears not to meet	~1960	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unknown	N/A
183	273434	N/A	N/A		32.289280012782754, -83.4688343567405	93 MLK Blvd	More info needed	~1930	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Unknown- possible side gable cottage	N/A
184	273440	N/A	N/A		32.28775618016767, -83.46983471787038	67 3rd St.	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Bungalow	Front gable
185	273441	N/A	N/A		32.288181478831476, -83.46982130737356	28 Carter St.	Appears not to meet	~1955	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
186	273444	N/A	N/A		32.288181478831476, -83.46982130737356	78 MLK Blvd.	Appears not to meet	~1960	Domestic residential- multi family residence	Vacant/not in use	No Academic Style	Duplex	N/A
187	273445	N/A	N/A		32.28868659080589, -83.46972830546117	80 MLK Blvd.	Appears not to meet	~1960	Domestic residential- single family residence	Vacant/not in use	Plain	Unknown- possible linear Ranch	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
188	273446	N/A	N/A	Pentecostal Episcopal COG	32.28876989827589, -83.4694356245558	135 N. Lumpkin St.	Appears not to meet	~1965	Religion- religious facility	Religion- religious facility	No Academic Style	Church/ Place of Worship- Front Gable	N/A
189	273448	N/A	N/A		32.28838182423295, -83.46939503733479	129 N. Lumpkin St.	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
190	273449	N/A	N/A		32.28824696390694, -83.46936739301024	127 N. Lumpkin St.	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
191	273595	N/A	N/A		32.28805782416809, -83.46940766887735	125 N. Lumpkin St.	Appears not to meet	~1945	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
192	273596	N/A	N/A		32.287906542153834, -83.47046435177897	224 N. Dooley St.	Appears not to meet	1967	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
193	273597	N/A	N/A		32.287906542153834, -83.47046435177897	226 N. Dooley St.	Appears to meet	~1890	Domestic residential- single family residence	Domestic residential- single family residence	Folk Victorian	Georgian Cottage	N/A
194	55119	382	181		32.28810265254475, -83.47047312099103	230 N. Dooley St.	Appears to meet	~1897	Domestic residential- single family residence	Domestic residential- single family residence	Folk Victorian	Georgian Cottage	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
195	273598	N/A	N/A		32.28824728836613, -83.4704834157469	232 N. Dooley St.	May meet	~1935	Domestic residential- single family residence	Commerce and Trade- business/ office	No Academic Style	American Small House	N/A
196	55118	381	183		32.28842803492842, -83.47051556311426	234 N. Dooley St.	Appears to meet	~1899	Domestic residential- single family residence	Domestic residential- single family residence	Folk Victorian	Georgian Cottage	N/A
197	55115	378	N/A		32.28873597068922, -83.4705663505028	238 N. Dooley St.	Appears not to meet	~1914	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Gabled Wing Cottage	N/A
198	273599	N/A	N/A		32.28875427499385, -83.47028563419556	74 MLK Blvd.	Appears not to meet	~1965	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
199	273600	N/A	N/A	New Mount Zion Community Church	32.28869973824526, -83.4700900495398	76 MLK Blvd.	Appears not to meet	~1930	Religion- religious facility	Religion- religious facility	No Academic Style	Front Gable Church	N/A
200	273601	N/A	N/A		32.28848767408443, -83.47009849362193	33 Carter Str.	Appears not to meet	~1961	Domestic residential- single family residence	Vacant/not in use	Unknown	Unknown/possible Ranch	N/A
201	273602	N/A	N/A		32.28782306650376, -83.47005009977356	23 Carter St.	Appears not to meet	1972	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Split Level	N/A
202	273603	N/A	N/A		32.288536051386124, -83.47243216665574	48 MLK Jr. Blvd.	Appears not to meet	~1940	Domestic residential- single family residence	Vacant/not in use	Unknown	Unknown- Possible American Small House	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
203	55162	426	N/A		32.2885882542198, -83.47219518503569	52 MLK Jr. Blvd.	Appears not to meet	~1960	Domestic residential- multi family residence	Vacant/not in use	No Academic Style	Duplex	N/A
204	55160	424	N/A		32.28860590795095, -83.47186378295365	56 MLK Jr. Blvd.	More info needed	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unknown- May be a Bungalow type.	Hipped
205	55159	423	266		32.28859781543987, -83.47170674043379	58 MKL Jr. Blvd	Appears to meet	~1899	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Queen Anne Cottage	N/A
206	273604	N/A	N/A		32.28851528911365, -83.4713797214771	36 Texas Alley	Appears not to meet	~1945	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
207	273605	N/A	N/A		32.28841854274412, -83.47138638544843	34 Texas Alley	Appears to meet	~1910	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Shotgun	N/A
208	273606	N/A	N/A		32.288257292313666, -83.47171293643467	58 MLK Jr. Blvd.	Appears not to meet	1975	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
209	273607	N/A	N/A		32.28799426627013, -83.47165661004533	27 Texas Alley	Appears not to meet	~1965	Domestic residential- single family residence	Domestic residential- single family residence	Unknown	Unknown- possible Ranch	Linear
210	273608	N/A	N/A		32.288079679156056, -83.47142290603539	28 Texas Alley	Appears not to meet	~1957	Domestic residential- single family residence	Vacant/not in use	Plain	Ranch	Linear

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
211	273609	N/A	N/A		32.28789285523924, -83.47141118148619	227 N. Dooley St.	Appears not to meet	~1960	Domestic residential- single family residence	Vacant/not in use	Plain	Ranch	Compact
212	273610	N/A	N/A		32.288732619403696, -83.47107371120529	64 MLK Blvd	Appears not to meet	1967	Unknown	Vacant/not in use	No Academic Style	Commercial Building Types- Single Retail	N/A
213	273611	N/A	N/A		32.288641921329706, -83.47099860935288	239 N. Dooley St.	Appears to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Central Hallway	N/A
214	27612	N/A	N/A		32.288535293062225, -83.47099296211405	237 N. Dooley St.	Appears not to meet	~1975	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Compact
215	273613	N/A	N/A		32.28840353494909, -83.4709893265321	235 N. Dooley St.	May meet	~1890	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Georgian Cottage	N/A
216	273614	N/A	N/A		32.28831601191934, -83.47095538386367	233 N. Dooley St.	Appears to meet	~1915	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Gabled Wing Cottage	N/A
217	273615	N/A	N/A		32.28808522307372, -83.47094441548703	231 N. Dooley St.	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Bungalow	Front Gable
218	55105	368	182		32.28794090715993, -83.47094328961147	227 N. Dooley St.	Appears to meet	~1920	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Extended Hall and Parlor	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
219	273616	N/A	N/A		32.28782748039716, 83.4709388371808	225 N. Dooley St.	Appears to meet	~1955	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
220	273617	N/A	N/A		32.28768887341699, -83.47091395213076	223 N. Dooley St.	Appears not to meet	1930	Domestic residential- single family residence	Commerce and Trade- business/ office	Neoclassic al Revival	Georgian House	N/A
221	55147	411	N/A		32.28750979276258, -83.47163157021139	43 3rd St.	Appears not to meet	~1890	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unknown- possible Central Hallway	N/A
222	273618	N/A	N/A		32.28765656656836, -83.47211099376624	35 3rd St.	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
223	273619	N/A	N/A		32.28765014402458, -83.47232934857234	33 3rd St.	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
224	273620	N/A	N/A		32.28766405094801, -83.47255449241553	31 3rd St. and 22 Henry Way	May meet	~1965	Unknown	Domestic residential- multiple dwelling	No Academic Style	Duplex	N/A
225	273621	N/A	N/A		32.28776749451958, -83.47250529216223	24 Henry Way	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
226	273622	N/A	N/A		32.28787232268037, -83.4725124871888	26 Henry Way	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
227	273623	N/A	N/A		32.28799613107945, -83.4725243226621	28 Henry Way	More info needed	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
228	273624	N/A	N/A		32.288362773519104, -83.47253077784747	34 Henry Way	Appears not to meet	1972	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
229	273625	N/A	N/A		32.28754643581204, -83.47280273612331	21 Henry Way	Appears to meet	~1940	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
230	273626	N/A	N/A		32.287655929018655, -83.4728077294266	23A and B Henry Way	Appears not to meet	~1940	Domestic residential- single family residence	Domestic residential- multiple dwelling	No Academic Style	Duplex	N/A
231	273627	N/A	N/A		32.28780574725907, -83.4727985770186	25 Henry Way	May meet	~1916	Domestic residential- single family residence	Domestic residential- single family residence	Craftsman	Gabled Wing Cottage	N/A
232	273629	N/A	N/A	Christian Hope Baptist Missionary Church	32.28855949957485, -83.4729953760127	42 MLK Jr. Blvd	Appears to meet	~1955	Unknown	Religion- religious facility	No Academic Style	Church/Place of Worship-Front Gable	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
233	273630	N/A	N/A		32.287381894036315, -83.47365425936158	24 Lovejoy St.	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
234	273631	N/A	N/A		32.287487791306255, -83.47377590590781	26 Lovejoy St.	Appears not to meet	~1940	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
235	273632	N/A	N/A		32.28772560635042, -83.47388447668513	30 Lovejoy St.	Appears to meet	~1915	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Gabled Wing Cottage	N/A
236	273633	N/A	N/A		32.28801559397061, -83.47417379156194	36 Lovejoy St.	Appears not to meet	1979	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
237	273634	N/A	N/A		32.28819390696214, -83.47434834333045	38 Lovejoy St.	Appears not to meet	~1950	Domestic residential- single family residence	Vacant/not in use	No Academic Style	American Small House	N/A
238	273635	N/A	N/A		32.28835183565352, -83.47449302469713	40 Lovejoy St.	Appears not to meet	~1960	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
239	273636	N/A	N/A		32.288644485063436, -83.47474151278973	46 Lovejoy St.	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Unknown-possible American Small House	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
240	273637	N/A	N/A		32.28787818180776, -83.47464221069035	39 Lovejoy St.	Appears to meet	~1915	Domestic residential- single family residence	Domestic residential- single family residence	Craftsman	Gabled Wing Cottage	N/A
241	273638	N/A	N/A		32.28776538031824, -83.47454035373525	35 Lovejoy St.	Appears to meet	~1915	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Gabled Wing Cottage	N/A
242	273639	N/A	N/A		32.287623994389755, -83.47440969262362	33 Lovejoy St.	More info needed	~1960	Domestic residential- single family residence	Vacant/not in use	Unknown	Unknown-possible Ranch	N/A
243	273640	N/A	N/A		32.28735708658408, -83.47515959711923	60A Progress Ave.	Appears not to meet	~1955	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
244	273641	N/A	N/A		32.287348016643165, -83.47489137621776	60B Progress Ave.	Appears not to meet	~1960	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Two-story Duplex	N/A
245	273642	N/A	N/A		32.287513953031215, -83.4753022606023	64 Progress Ave.	Appears to meet	1956	Unknown	Commercial- office building	Modern Movement - Contempor ary	One- story Office Building	N/A
246	273643	N/A	N/A		32.28768632890818, -83.47541105147315	66 Progress Ave.	Appears not to meet	~1895	Domestic residential- single family residence	Commerce and Trade- business/ office	No Academic Style	Queen Anne Cottage	N/A

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
247	55177	441	N/A		32.28798091703038, -83.47570831043402	68 Progress Ave.	Appears to meet	~1920	Domestic residential- single family residence	Domestic residential- single family residence	Craftsman	Bungalow	Front Gable
248	55178	442	269		32.28798091703038, -83.47570831043402	70 Progress Ave.	Appears to meet	~1902	Domestic residential- single family residence	Domestic residential- single family residence	Folk Victorian	New South Cottage	N/A
249	273644	N/A	N/A		32.288180244935084, -83.47579588758605	74 Progress Ave.	Appears to meet	~1940	Domestic residential- single family residence	Domestic residential- single family residence	Folk Victorian	American Small House	N/A
250	55176	440	202		32.28595067280856, -83.47392970166682	36 Progress Ave.	Appears to meet	~1920	Domestic residential- single family residence	Domestic residential- single family residence	Craftsman	Unknown- possible Bungalow	Front gable
251	273646	N/A	N/A		32.286000522617826, -83.47355144990912	5 Second St.	Appears to meet	~1940	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
252	273647	N/A	N/A		32.286286493134966, -83.4727561278697	6 Lovejoy St.	Appears not to meet	~1955	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
253	273649	N/A	N/A		32.286515624907345, -83.47290442547046	8 Lovejoy St.	Appears not to meet	~1960	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear

Historic Resources Survey Report
City of Hawkinsville ■ Pulaski County, GA
September 25, 2020 ■ Terracon Project No. 49197855




Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
254	273650	N/A	N/A		32.28682763804098, -83.47305315528746	14 Lovejoy St.	Appears not to meet	~1960	Commercial storage-warehouse	Vacant/not in use	No Academic Style	Commercial building-warehouse	N/A
255	273651	N/A	N/A		32.28713378757036, -83.47324168389129	22 Third St.	Appears not to meet	~1960	Commercial storage-warehouse	Commercial storage-warehouse	No Academic Style	Commercial building-warehouse	N/A
256	55141	405	188		32.28723242637676, -83.47113243368544	50 Third St.	Appears not to meet	~1909	Domestic residential-single family residence	Domestic residential- single family residence	No Academic Style	Unknown- possible saddlebag	N/A
257	55142	406	N/A		32.287226650898546, -83.47132530494459	48 Third St.	Appears to meet	~1907	Domestic residential-single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A
258	55144	408	189		32.287190633609924, -83.47155662669778	42 Third St.	Appears to meet	~1890	Domestic residential-single family residence	Domestic residential- single family residence	Craftsman	Georgian Cottage	N/A
259	55143	407	N/A		32.28718864583854, -83.47183641763405	40 Third St.	More info needed	~1924	Domestic residential-single family residence	Vacant/not in use	Unknown	Unknown-possible Craftsman	Front gable
260	273655	N/A	N/A		32.28715222667713, -83.4721825423481	36 Third St.	Appears not to meet	~1950	Domestic residential-single family residence	Domestic residential- single family residence	Craftsman	American Small House	N/A
261	273656	N/A	N/A		32.286812737718954, -83.47250904411548	12 Henry Way	Appears not to meet	1961	Domestic residential-single family residence	Domestic residential- single family residence	Plain	Ranch	Linear

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
262	273662	N/A	N/A		32.28611228823882, -83.47247640824499	19 Second St.	Appears not to meet	~1920	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Bungalow	Hip
263	273663	N/A	N/A		32.28613035828787, -83.47233449290074	21 Second St.	Appears not to meet	~1950	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
264	273664	N/A	N/A		32.28623905882498, -83.47212284012207	23 Second St.	Appears not to meet	1968	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear
265	273665	N/A	N/A		32.286252531651776, -83.47196168299472	25 Second St.	Appears not to meet	1972	Unknown	Vacant/not in use	No Academic Style	Commercial business office/store	N/A
266	55137	401	194		32.28622631790073, -83.47172626344849	27 Second St.	Appears to meet	~1909	Domestic residential- single family residence	Vacant/not in use	No Academic Style	Gabled Wing Cottage	N/A
267	55164	428	N/A		32.288685004499484, -83.47354121175684	36 MLK Blvd.	Appears not to meet	~1930	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	Saddlebag	N/A
268	273666	N/A	N/A		32.288690769816405, -83.47375691548712	34 MLK Blvd.	Appears not to meet	~1947	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A
269	273667	N/A	N/A		32.288697088744755, -83.47395927976092	32 MLK Blvd.	Appears not to meet	~1955	Domestic residential- single family residence	Domestic residential- single family residence	Plain	Ranch	Linear

Surveyed #	GNAHRGIS #	1990 #	1976 #	Name	Coordinates	Address	NRHP Status	Construction Date	Original Use	Current Use	Style	Building/ Resource Type	Building Subtype
270	273645	N/A	N/A		32.288389273135785, -83.47595681957866	78 Progress Ave.	Appears to meet	~1940	Domestic residential- single family residence	Domestic residential- single family residence	No Academic Style	American Small House	N/A


APPENDIX B: SURVEY MAP



LEGEND

- PROJECT BOUNDARY
- SURVEYED PARCELS
- TAX PARCELS
- PROPOSED RANCH HISTORIC DISTRICT

THIS DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES



Project Mng:	JDM	Project No.	49197855	 Terracon Consulting Engineers and Scientists 2105 Newpoint Place, Ste. 600 Lawrenceville, GA 30043 (770) 623-0755 (770) 623-9628		CULTURAL RESOURCES HISTORIC RESOURCES SURVEY REPORT HAWKINSVILLE PULASKI COUNTY, GEORGIA		Appendix
Drawn By:	RLW	Scale:	AS SHOWN					B
Checked By:	RLW/MRF	File No.	49197855-2					
Approved By:	JDM	Date:	SEPTEMBER 2020					